

# DIVISION OF HIGHWAYS STATE OF NORTH CAROLINA SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS  
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200825

ItemNumber	Sec #	Quantity	Unit	Description
000100000-N	800	Lump Sum		MOBILIZATION
002900000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL STATION ***** (24+92.50)
004300000-N	226	Lump Sum		GRADING
005000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB- BING
005700000-E	226	5,000	CY	UNDERCUT EXCAVATION
031800000-E	300	17	TON	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS
034300000-E	310	108	LF	15" SIDE DRAIN PIPE
037200000-E	310	32	LF	18" RC PIPE CULVERTS, CLASS III
037800000-E	310	24	LF	24" RC PIPE CULVERTS, CLASS III
099500000-E	340	321	LF	PIPE REMOVAL
112100000-E	520	900	TON	AGGREGATE BASE COURSE
122000000-E	545	75	TON	INCIDENTAL STONE BASE
148900000-E	610	2,540	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
149800000-E	610	2,030	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B
151900000-E	610	1,480	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
156000000-E	620	301	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
169300000-E	654	20	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR
200000000-N	806	20	EA	RIGHT OF WAY MARKERS
202200000-E	815	112	CY	SUBDRAIN EXCAVATION
203300000-E	815	84	CY	SUBDRAIN FINE AGGREGATE
204400000-E	815	500	LF	6" PERFORATED SUBDRAIN PIPE
205500000-E	815	15	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS
206600000-N	815	1	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET
207700000-E	815	6	LF	6" OUTLET PIPE (SUBDRAINS)

ItemNumber	Sec #	Quantity	Unit	Description
225300000-E	840	2	CY	PIPE COLLARS
255600000-E	846	75	LF	SHOULDER BERM GUTTER
303000000-E	862	2,175	LF	STEEL BM GUARDRAIL
315000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
321500000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III
327000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
353600000-E	866	40	LF	CHAIN LINK FENCE, 48" FABRIC
354200000-E	866	8	EA	METAL LINE POSTS FOR 48" CHAIN LINK FENCE
354800000-E	866	4	EA	METAL TERMINAL POSTS FOR 48" CHAIN LINK FENCE
357200000-E	867	190	LF	CHAIN LINK FENCE RESET
357800000-N	SP	1	EA	GENERIC FENCING ITEM SINGLE SWING 20' CHAIN LINK FENCE GATE
364900000-E	876	8	TON	PLAIN RIP RAP, CLASS B
365600000-E	876	1,155	SY	FILTER FABRIC FOR DRAINAGE
402500000-E	901	4.5	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (D)
402500000-E	901	35	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (E)
407200000-E	903	84	LF	SUPPORTS, 3-LB STEEL U-CHANNEL
409600000-N	904	2	EA	SIGN ERECTION, TYPE D
410200000-N	904	6	EA	SIGN ERECTION, TYPE E
415500000-N	907	7	EA	DISPOSAL OF SIGN SYSTEM, U- CHANNEL
419200000-N	907	2	EA	DISPOSAL OF SUPPORT, U-CHANNEL
440000000-E	1110	160	SF	WORK ZONE SIGNS (STATIONARY)
441000000-E	1110	57	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
444500000-E	1145	96	LF	BARRICADES (TYPE III)
468500000-E	1205	5,700	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)

ItemNumber	Sec #	Quantity	Unit	Description
468600000-E	1205	5,700	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
490000000-N	1252	36	EA	PERMANENT RAISED PAVEMENT MARKERS
530000000-E	1505	6	TON	FOUNDATION CONDITIONING MATE- RIAL, UTILITIES CLASS ***** (IV)
530600000-E	SP	6	TON	BEDDING MATERIAL, UTILITIES CLASS ***** (IV)
567800000-E	SP	2	EA	*** LINE STOP ASSEMBLY (20')
575600000-E	1520	430	LB	DUCTILE IRON SEWER PIPE FIT- TINGS, ***** (250# MIN WP)
588200000-N	SP	2	EA	GENERIC UTILITY ITEM 20" X 20" TAPPING SLEEVE, VALVE & VALVE MANHOLE, 200# WP
588800000-E	SP	104.8	LF	GENERIC UTILITY ITEM 20" DI RESTRAINED JOINT FORCE MAIN SEWER PIPE, FC 250
588800000-E	SP	250.6	LF	GENERIC UTILITY ITEM 24" HDPE FORCE MAIN SEWER PIPE SDR 9, 200# WP BY DIRECTIONAL BORE
589400000-E	SP	25	CY	GENERIC UTILITY ITEM CEMENT GROUT FOR FILLING ABAN- DONED SANITARY FORCE MAIN SEW- ER PIPE
590600000-E	SP	5,500	LB	GENERIC UTILITY ITEM DI RESTRAINED JOINT FORCE MAIN SEWER PIPE FITTINGS, 250# MIN WP
600000000-E	1605	11,300	LF	TEMPORARY SILT FENCE
600600000-E	1610	175	TON	STONE FOR EROSION CONTROL, CLASS A
600900000-E	1610	700	TON	STONE FOR EROSION CONTROL, CLASS B
601200000-E	1610	700	TON	SEDIMENT CONTROL STONE
601500000-E	1615	9	ACR	TEMPORARY MULCHING
601800000-E	1620	350	LB	SEED FOR TEMPORARY SEEDING
602100000-E	1620	1.25	TON	FERTILIZER FOR TEMPORARY SEED- ING
602400000-E	1622	100	LF	TEMPORARY SLOPE DRAINS
602700000-N	1622	5	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
603000000-E	1630	2,200	CY	SILT EXCAVATION
603300000-E	1631	1,100	SY	SYNTHETIC ROVING
603600000-E	1631	2,200	SY	MATting FOR EROSION CONTROL
607000000-N	SP	18	EA	SPECIAL STILLING BASINS
608400000-E	1660	9	ACR	SEEDING & MULCHING
608700000-E	1660	5.5	ACR	MOWING
609000000-E	1661	100	LB	SEED FOR REPAIR SEEDING
609300000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
609600000-E	1662	225	LB	SEED FOR SUPPLEMENTAL SEEDING
610800000-E	1665	6.75	TON	FERTILIZER TOPDRESSING
611400000-N	SP	5	HR	SPECIALIZED HAND MOWING
611700000-N	1675	12	EA	RESPONSE FOR EROSION CONTROL
613500000-E	SP	3.8	ACR	GENERIC EROSION CONTROL ITEM RIPPING

27 OCT 2003 10:24  
RD08S01E Monday October 27 2003 B2963\_fin\_sum.m RLCribbs rd-08oce34