



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

MICHAEL F. EASLEY
GOVERNOR

LYNDO TIPPETT
SECRETARY

November 10, 2004

Addendum No. 1

RE: Contract ID: C201010
WBS # 34885.3.2
F.A. # STP-0620 (12)
Cumberland County (U-2912)
Owens Drive Extension From I-95 Business
To NC-87 at SR-2283 (East Mountain Drive)
In Fayetteville.

November 16, 2004 Letting

To Whom It May Concern:

Reference is made to the plans and proposal form recently furnished to you on the above-mentioned project.

The following revisions have been made to the plans:

On Sheet Nos. 2 and 2-A a note has been added concerning the temporary pavement. Please void Sheet Nos. 2 and 2-A in your plans and staple the revised Sheet Nos. 2 and 2-A thereto.

On Sheet Nos. 3B, 3D and 3F, the drainage summary has been revised to add "Class IV" pipe and correct the "Class III" pipe. Please void Sheet Nos. 3B, 3D and 3F in your plans and staple the revised Sheet Nos. 3B, 3D and 3F thereto.

Sheet No. 3H has been revised to correct the quantity of "Removal of Existing Asphalt Pavement." Please void Sheet No. 3H in your plans and staple the revised Sheet No. 3H thereto.

Sheet No. 7 has been revised to correct a pipe description. Please void Sheet No. 7 in your plans and staple revised Sheet No. 7 thereto.

Sheet No. 10 has been revised to show the location of "Concrete Valley Gutter." Please void Sheet No. 10 in your plans and staple the revised Sheet No. 10 thereto.

The following revisions have been made to the proposal form:

New Page Nos. 26A thru 26C have been added to include a project special provision entitled "Building Removal and Sealing Abandoned Wells." Please staple the New Page Nos. 26A thru 26C after Page No. 26 in your proposal.

MAILING ADDRESS:
NC DEPARTMENT OF TRANSPORTATION
CONTRACTS & PROPOSALS
1591 MAIL SERVICE CENTER
RALEIGH NC 27699-1591

TELEPHONE: 919-250-4124
FAX: 919-250-4127

WEBSITE: WWW.DOH.DOT.STATE.NC.US

LOCATION:
CENTURY CENTER COMPLEX
BUILDING B - ENTRANCE B 15
1020 BIRCH RIDGE DRIVE
RALEIGH NC

On Page No. 1 of the item sheets, the quantity for line item “10-015600000-M-250 Removal of Existing Asphalt Pavement” has been revised. By copy of this addendum, the pay item quantity is hereby increased from 8,805M2 to 11,394M2. Also on Page No. 1 of the item sheets, the quantity for line item “18-037200000-M-310 450MM RC Pipe Culverts, Class III” has been revised. By copy of this addendum, the pay item quantity is hereby reduced from 247.2M to 224.4M. Also on Page No. 1 of the item sheets, the quantity for line item “19-037800000-M-310 600MM RC Pipe Culverts, Class III” has been revised. By copy of this addendum, the pay item quantity is hereby increased from 546.3M to 548.4M. The Contractor’s bid price must be based on these revised pay item quantities.

On Page No.2 of the item sheets, by copy of this addendum the following two pay items are hereby deleted: “22-040200000-M-310 1200MM RC Pipe Culverts, Class III” and “25-072600000-M-310 800MM Bit Coat CS Pipe Culverts, Type B, 2.01MM Thick.”

On Page No. 10 and 11 of the item sheets, eight new pay items are being added. By copy of this addendum the following pay items are hereby added:

<u>Item Number</u>	<u>Quantity</u>
173-001500000-N-205 Sealing Abandoned Wells	2 EA
174-044800000-M-310 1200MM RC Pipe Culverts, Class IV	40.8 M
175-044800000-M-310 1500MM RC Pipe Culverts, Class IV	84 M
176-098700000-M-310 750MM Bit Coat CS Pipe Culverts, 2.75MM Thick (12GA)	49.2 M
177-225300000-M-840 Pipe Collars	2.63 M3
178-230800000-M-840 Masonry Drainage Structures	5.94 M
179-258000000-M-846 Concrete Valley Gutter	25 M

The Contractor’s bid price must include these new pay items. The Contact will be prepared accordingly.

Page No. 3
Cumberland County

The Expedite file has been updated to reflect these revisions. Please download the Expedite addendum file and follow the instructions for applying the addendum. Bid Express will not accept your bid unless the addendum has been applied.

Sincerely,

A handwritten signature in black ink, appearing to read "R. A. Garris", with a long horizontal flourish extending to the right.

R. A. Garris, PE
Contract Officer

RAG/jag/pa
Attachments

Cc: Mr. W. S. Varnedoe, PE
Mr. S. D. DeWitt, PE
Mr. E. C. Powell, PE
Mr. T. R. Gibson, PE
Ms. D. M. Barbour, PE
Mr. Art McMillan, PE
Mr. J. V. Barbour, PE
Mr. Mark Staley (2)
Mr. Ayden Flowers
Mr. R. E. Davenport, Jr., PE
Ms. Marsha Byrd
Ms. Taylor Mishoe
Project File (2)

BUILDING REMOVAL AND SEALING ABANDONED WELLS:**01-01-02**

Remove the buildings and appurtenances listed below in accordance with Section 215 of the Standard Specifications and the following provisions:

Prior to removal of any building, comply with the notification requirements of Title 40 Code of Federal Regulations, Part 61, Subpart M, which are applicable to asbestos. Give notification to the North Carolina Department of Health and Human Services, Division of Epidemiology, Asbestos Hazard Management Branch and/or the appropriate county agency when enforcement of the Federal Regulation is performed by the county. Submit a copy of the notification to the Engineer prior to the building removal.

The Department has performed asbestos assessments for building items identified below. Copies of this report may be obtained through the Division Right-of-Way Agent. When asbestos is discovered after the opening of bids for the project, the cost of asbestos removal and disposal will be paid for in accordance with Article 104-7 of the Standard Specifications. Perform removal and disposal of asbestos in accordance with the requirements of Title 40 Code of Federal Regulations.

When a building has had or will have asbestos removed and the Contractor elects to remove the building such that it becomes a public area, the Contractor is responsible for any additional costs incurred including final air monitoring.

Comply with all Federal, State and local regulations when performing building removal and/or asbestos removal and disposal. Any fines resulting from violations of any regulation are the sole responsibility of the Contractor and the Contractor agrees to indemnify and hold harmless the Department against any assessment of such fines.

Prior to removal of any Underground Storage Tank (UST), comply with the notification requirements of the Title 40 Code of Federal Regulations, Part 280.71(a). Give notification to the appropriate regional office of the North Carolina Department of Environment, and Natural Resources, Division of Environmental Management, Groundwater Section. Submit a copy of the notification to the Engineer prior to the removal of the underground storage tank.

Permanently close UST systems by removal and dispose of in compliance with the regulations set forth in Title 40, Code of Federal Regulations, Part 280.71 and North Carolina Administrative Code Title 15A, Chapter 2, Subchapter 2N and any applicable local regulations. Assess Underground Storage Tank sites at closure for the presence of contamination as required in NCAC Title 15A, Chapter 2, Subchapter 2N, Section .0803 and as directed by the appropriate Regional Office of the Division of Environmental Management. Remove and dispose of UST systems and contents in a safe manner in conformance with requirements of American Petroleum Institute Bulletin 1604, "Removal and Disposal of Used Underground Petroleum Storage Tanks", Chapters 3 through 6. (Note: As an exception to these requirements, the filling of the tank with water as a means of expelling vapors from the tank as described in section 4.2.6.1 of API Bulletin 1604, will not be allowed. Where underground storage tanks are indicated below, there

will be no direct payment for the closure or assessment. When the contract does not indicate the presence of storage tanks and storage tanks are discovered after the opening of bids for the project, the cost of closure, assessment and/or removal will be paid for in accordance with Article 104-7 of the Standard Specifications.

Disposition of any contaminated material associated with underground storage tanks will be made as provided in Article 107-26 of the Standard Specifications.

Building Removal (Item No. 1)

Parcel 009A – Right of Survey Station 10+48, Survey Line Y8
One-Story Frame Dwelling

Building Removal (Item No. 2)

Parcel 009A – Right of Survey Station 10+50, Survey Line Y8
Pump House

Building Removal (Item No. 3)

Parcel 009A – Right of Survey Station 10+82, Survey Line Y8
Gazebo

Building Removal (Item No. 4)

Parcel 009A – Right of Survey Station 10+82, Survey Line Y8
Above Ground Pool

Building Removal (Item No. 5)

Parcel 009A – Right of Survey Station 11+08, Survey Line Y8
One-Story Frame Dwelling

Building Removal (Item No. 6)

Parcel 010B – Right of Survey Station 11+80, Survey Line L Rev.
One-Story Block Dwelling

Building Removal (Item No. 7)

Parcel 010B – Right of Survey Station 12+20, Survey Line L Rev.
Shed

Building Removal (Item No. 8)

Parcel 010B – Left of Survey Station 11+08, Survey Line Y8
One-Story Block Building

Building Removal (Item No. 9)

Parcel 010B – Right of Survey Station 12+40, Survey Line L Rev.
Shed

Building Removal (Item No. 10)

Parcel 033 – Right of Survey Station 27+40, Survey Line L Rev.
Electric Gate with Masonry Housing

Contract C201010 (U-2912)

26 - C

Building Removal (Item No. 11)

Parcel 040 – Right of Survey Station 30+40, Survey Line L Rev.

One-Story Frame Dwelling

NOTE: The tanks at Parcel 19A will be removed by others.

The Contractor shall seal any abandoned wells which are listed below, in accordance with Section 205 of the Standard Specifications.

Item Removal (Item No. 1)

Parcel 009A – Right of Survey Station 10+50, Survey Line Y8

Well

Item Removal (Item No. 2)

Parcel 010B – Left of Survey Station 10+98, Survey Line Y8

Well

SP2R15