

150 140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	LL	PI	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C. SAND	F. SAND	SILT	CLAY	10	40	200		
SS-13	27' LT	22+00	0.0-1.5	A-6(11)	36	14	4.9	19.1	47.1	28.8	99	96	81	-	-
SS-14	27' LT	22+00	5.7-6.5	A-7-6(20)	47	27	5.8	21.8	33.3	39.1	100	97	77	-	-
SS-15	27' LT	22+00	7.5-9.0	A-7-6(28)	53	33	4.5	17.9	38.5	39.1	97	94	82	-	-

LEGEND:  
 A: ROADWAY EMBANKMENT, RED-BROWN, MEDIUM STIFF TO STIFF, SLIGHTLY PLASTIC, MOIST, SANDY CLAY  
 B: ALLUVIAL, GRAY, STIFF, HIGHLY PLASTIC, MOIST, SILTY CLAY  
 C: WEATHERED ROCK (SILTSTONE)

