STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201124

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ********** (14+23.00-L-)
0036000000-E	225	200	CY	UNDERCUT EXCAVATION
0043000000-N	226	Lump Sum		GRADING
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUBBING
0195000000-E	265	300	CY	SELECT GRANULAR MATERIAL
0196000000-E	270	200	SY	FABRIC FOR SOIL STABILIZATION
0318000000-E	300	3	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS
0582000000-E	310	28	LF	15" CS PIPE CULVERTS, 0.064" THICK
0636000000-E	310	4	EA	**" CS PIPE ELBOWS, *****" THICK (15", 0.064")
1220000000-E	545	50	TON	INCIDENTAL STONE BASE
1489000000-E	610	250	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
1525000000-E	SP	340	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A
1560000000-E	620	33	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
1693000000-E	654	50	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR
2000000000-N	806	9	EA	RIGHT OF WAY MARKERS
2286000000-N	840	2	EA	MASONRY DRAINAGE STRUCTURES
2367000000-N	840	2	EA	FRAME WITH TWO GRATES, STD 840.29
2556000000-E	846	35	LF	SHOULDER BERM GUTTER
3030000000-E	862	325	LF	STEEL BM GUARDRAIL
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III
3270000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
3656000000-E	876	150	SY	FILTER FABRIC FOR DRAINAGE
3659000000-N	SP	2	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON
4400000000-E	1110	323	SF	WORK ZONE SIGNS (STATIONARY)
4410000000-E	1110	94	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
4425000000-N	1125	2	EA	WARNING FLAG SETS
4445000000-E	1145	84	LF	BARRICADES (TYPE III)
4810000000-E	1205	8,400	LF	PAINT PAVEMENT MARKING LINES (4")
4900000000-N	1252	15	EA	PERMANENT RAISED PAVEMENT MARKERS
6000000000-E	1605	630	LF	TEMPORARY SILT FENCE
6006000000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
6009000000-E	1610	225	TON	STONE FOR EROSION CONTROL, CLASS B
6012000000-E	1610	75	TON	SEDIMENT CONTROL STONE
6015000000-E	1615	1	ACR	TEMPORARY MULCHING
6018000000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING
6021000000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING
6024000000-E	1622	50	LF	TEMPORARY SLOPE DRAINS
6027000000-N	1622	2	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
6030000000-E	1630	360	CY	SILT EXCAVATION
6036000000-E	1631	925	SY	MATTING FOR EROSION CONTROL
6038000000-E	SP	90	SY	PERMANENT SOIL REINFORCEMENT MAT
6042000000-E	1632	40	LF	1/4" HARDWARE CLOTH
6084000000-E	1660	1	ACR	SEEDING & MULCHING
6087000000-E	1660	0.5	ACR	MOWING
6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
6096000000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
6108000000-E	1665	0.75	TON	FERTILIZER TOPDRESSING
6114000000-N	SP	1.5	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
6147000000-E	SP	1,150	LF	GENERIC EROSION CONTROL ITEM SAFETY FENCE

5/28/99
16-AUG-2004 14:05
W:\TIP Projects\Scheffel\B-4134\Roadway\Proj\100% plans\b4134_rdy_tsh.mstt100%.dgn
mtundell AT DS214565