

County : Harnett, Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1220000000-E	545	INCIDENTAL STONE BASE	1,566 TON		
0003	1245000000-E	SP	SHOULDER RECONSTRUCTION	129.32 SMI		
0004	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1")	2,564 SY		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	46,739 SY		
0006	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (3")	9,780 SY		
0007	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1")	1,742 SY		
0008	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	4,517 SY		
0009	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (1-1/2" TO 4-1/2")	1,760 SY		
0010	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	776 TON		
0011	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	5,301 TON		
0012	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	32,003 TON		
0013	1520000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S9.5B (LEVELING COURSE)	91 TON		
0014	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	4,945 TON		
0015	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	52,787 TON		
0016	1525100000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A (LEVELING COURSE)	21 TON		

County : Harnett, Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0017	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	5,626 TON		
0018	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	297 TON		
0019	1704000000-E	SP	PATCHING EXISTING PAVEMENT	457 TON		
0020	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	30 LF		
0021	2605000000-N	SP	WHEELCHAIR RAMPS	6 EA		
0022	2815000000-N	858	ADJUSTMENT OF DROP INLETS	1 EA		
0023	2830000000-N	858	ADJUSTMENT OF MANHOLES	93 EA		
0024	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	95 EA		
0025	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	324,575 LF		
0026	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	267,670 LF		
0027	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	1,000 LF		
0028	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	9,850 LF		
0029	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	300 LF		
0030	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	1,452 LF		
0031	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120MIL)	56 EA		
0032	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	377 EA		
0033	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	644,810 LF		

County : Harnett, Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0034	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	50 LF		
0035	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	36 LF		
0036	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	4,367 EA		
0037	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	1,360 EA		
0038	6084000000-E	1660	SEEDING & MULCHING	157.64 ACR		
0039	7288000000-E	1715	TRENCHING (PAVED)	100 LF		
0040	7300000000-E	1715	TRENCHING (UNPAVED)	100 LF		
0041	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	5 EA		
0042	7420000000-E	1722	2" RISER WITH WEATHERHEAD	5 EA		
0043	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	5,650 LF		
0044	7456000000-E	1726	LEAD-IN CABLE	800 LF		
1305/Oct18/Q1434047.96/D15156920000/E44			Total Amount Of Bid For Entire Project :			

C201316
HARNETT & CUMBERLAND COUNTIES

2/16/99

Contract No: C201316

Counties: Harnett & Cumberland

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General