

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0043000000-N	226	GRADING	Lump Sum	L.S.	
0003	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0004	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	62 TON		
0005	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	240 LF		
0006	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	4 LF		
0007	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	328 LF		
0008	0744000000-E	310	48" BIT COAT CS PIPE CULVERTS, TYPE B 0.109" THICK	8 LF		
0009	0995000000-E	340	PIPE REMOVAL	105 LF		
0010	0996000000-N	350	PIPE CLEAN-OUT	2 EA		
0011	1220000000-E	545	INCIDENTAL STONE BASE	150 TON		
0012	1330000000-E	607	INCIDENTAL MILLING	100 SY		
0013	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	230 TON		
0014	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	160 TON		
0015	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	840 TON		
0016	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	73 TON		
0017	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	290 TON		
0018	2022000000-E	815	SUBDRAIN EXCAVATION	22.4 CY		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2033000000-E	815	SUBDRAIN FINE AGGREGATE	16.8 CY		
0020	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0021	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0022	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0023	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0024	2099000000-E	816	SHOULDER DRAIN	100 LF		
0025	2253000000-E	840	PIPE COLLARS	1.1 CY		
0026	2264000000-E	840	PIPE PLUGS	0.2 CY		
0027	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	17 EA		
0028	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	3 EA		
0029	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	3 EA		
0030	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	3 EA		
0031	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	6 EA		
0032	2396000000-N	840	FRAME WITH COVER, STD 840.54	2 EA		
0033	2451000000-N	840	CONCRETE APRON FOR DROP INLETS	3 EA		
0034	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	750 LF		
0035	2591000000-E	848	4" CONCRETE SIDEWALK	390 SY		
0036	2598000000-E	848	CONCRETE WHEELCHAIR RAMPS	50 SY		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2612000000-E	848	6" CONCRETE DRIVEWAY	120 SY		
0038	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	140 SY		
0039	2830000000-N	858	ADJUSTMENT OF MANHOLES	10 EA		
0040	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	8 EA		
0041	3628000000-E	876	PLAIN RIP RAP, CLASS I	25 TON		
0042	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	325 SY		
0043	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	492 SF		
0044	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	180 SF		
0045	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	32 SF		
0046	4425000000-N	1125	WARNING FLAG SETS	7 EA		
0047	4430000000-N	1130	DRUMS	60 EA		
0048	4435000000-N	1135	CONES	50 EA		
0049	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0050	4450000000-N	1150	FLAGGER	272 HR		
0051	4460000000-N	1155	WARNING LIGHTS (TYPE B)	2 EA		
0052	4615000000-E	1205	REMOVABLE TAPE PAVEMENT MARK- ING LINES (4")	1,046 LF		
0053	4635000000-E	1205	REMOVABLE TAPE PAVEMENT MARK- ING LINES (24")	61 LF		
0054	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	68 EA		
0055	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,190 LF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	36 LF		
0057	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	8 EA		
0058	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	5,207 LF		
0059	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	72 LF		
0060	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	16 EA		
0061	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	300 LF		
0062	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	32 EA		
0063	5300000000-E	1505	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)	44 TON		
0064	5306000000-E	SP	BEDDING MATERIAL, UTILITIES CLASS ***** (VI)	44 TON		
0065	5318000000-E	1505	PAVEMENT REPAIR FOR UTILITY WORK	1 TON		
0066	5360000000-E	1510	6" DI WATER PIPE, PC 350	510 LF		
0067	5414000000-E	1510	3/4" COPPER WATER PIPE, TYPE K	120 LF		
0068	5480000000-E	1510	DUCTILE IRON WATER PIPE FITTINGS, 250# MIN WP	850 LB		
0069	5510000000-E	1510	3/4" CORPORATION STOP	3 EA		
0070	5540000000-E	1510	6" GATE VALVE & VALVE BOX, 200# WP	3 EA		
0071	5582000000-E	1510	***X*** TAPPING SADDLE (6" X 3/4")	3 EA		
0072	5648000000-N	1510	RELOCATE EXISTING WATER METER	3 EA		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	5672000000-N	1510	RELOCATE EXISTING FIRE HYDRANT	1	EA	
0074	5726000000-E	1520	8" DI SEWER PIPE, PC 350	209	LF	
0075	5775000000-E	1525	4' DIA PRECAST CONC SEWER MANHOLE 0-6' DEPTH	2	EA	
0076	5780000000-E	1525	PRECAST CONC MANHOLE WALL, ** DIA, OVER 6' HT (4')	1	LF	
0077	5798000000-E	1530	FILL OR REMOVE ABANDONED *** PIPE, ***** (8", TC SEWER)	306	LF	
0078	5882000000-N	SP	GENERIC UTILITY ITEM STEEL H-PILE PIER	2	EA	
0079	5888000000-E	SP	GENERIC UTILITY ITEM 8" DI RIGID RESTRAINED JOINT SEWER PIPE, PC 350	100	LF	
0080	6000000000-E	1605	TEMPORARY SILT FENCE	340	LF	
0081	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	150	TON	
0082	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	130	TON	
0083	6012000000-E	1610	SEDIMENT CONTROL STONE	180	TON	
0084	6015000000-E	1615	TEMPORARY MULCHING	0.5	ACR	
0085	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
0086	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25	TON	
0087	6030000000-E	1630	SILT EXCAVATION	210	CY	
0088	6036000000-E	1631	MATTING FOR EROSION CONTROL	465	SY	
0089	6042000000-E	1632	1/4" HARDWARE CLOTH	460	LF	
0090	6069000000-E	1638	STILLING BASINS	40	CY	

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	6084000000-E	1660	SEEDING & MULCHING	0.5	ACR	
0092	6087000000-E	1660	MOWING	0.5	ACR	
0093	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0094	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0095	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0096	6108000000-E	1665	FERTILIZER TOPDRESSING	0.25	TON	
0097	6111000000-E	SP	IMPERVIOUS DIKE	325	LF	
0098	6114000000-N	SP	SPECIALIZED HAND MOWING	1	HR	
0099	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8	EA	
0100	7060000000-E	1705	SIGNAL CABLE	735	LF	
0101	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	13	EA	
0102	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	3	EA	
0103	7264000000-E	1710	MESSENGER CABLE (3/8")	90	LF	
0104	7288000000-E	1715	TRENCHING (PAVED)	77	LF	
0105	7300000000-E	1715	TRENCHING (UNPAVED)	188	LF	
0106	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	7	EA	
0107	7360000000-N	1720	WOOD POLE	2	EA	
0108	7372000000-N	1721	GUY ASSEMBLY	2	EA	
0109	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1	EA	
0110	7420000000-E	1722	2" RISER WITH WEATHERHEAD	2	EA	

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0111	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	1,254 LF		
0112	7456000000-E	1726	LEAD-IN CABLE	1,040 LF		
0113	7980000000-N	SP	GENERIC SIGNAL ITEM INSTALL CONTROLLER W/ CABINET (TYPE 2070L, POLE MOUNTED)	2 EA		
0114	7980000000-N	SP	GENERIC SIGNAL ITEM INSTALL DETECTOR CARD (TYPE 2070L)	6 EA		
CULVERT ITEMS						
0115	8056000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14+82.00 -L-)	Lump Sum	L.S.	
0116	8126000000-N	414	CULVERT EXCAVATION, STA ***** (14+82.00 -L-)	Lump Sum	L.S.	
0117	8133000000-E	414	FOUNDATION CONDITIONING MATER- IAL, BOX CULVERT	147 TON		
0118	8196000000-E	420	CLASS A CONCRETE (CULVERT)	247.5 CY		
0119	8245000000-E	425	REINFORCING STEEL (CULVERT)	36,221 LB		
0120	8821000000-E	SP	GENERIC CULVERT ITEM ARCHITECTURAL CONCRETE SURFACE TREATMENT	1,057 SF		
0950/Sep30/Q59770.25/D544821100000/E120				Total Amount Of Bid For Entire Project :		

C201306
HENDERSON COUNTY

2/16/99

Contract No: C201306

County: Henderson

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General