

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (12+52.50)	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (15+60.00)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	250 CY		
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	1,000 TON		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	15 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	700 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	13 TON		
0012	0343000000-E	310	15" SIDE DRAIN PIPE	60 LF		
0013	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	60 LF		
0014	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0015	1121000000-E	520	AGGREGATE BASE COURSE	480 TON		
0016	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0017	1275000000-E	600	PRIME COAT	335 GAL		
0018	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	145 TON		

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	10 TON		
0020	2022000000-E	815	SUBDRAIN EXCAVATION	115 CY		
0021	2033000000-E	815	SUBDRAIN FINE AGGREGATE	85 CY		
0022	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0023	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15 EA		
0024	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0025	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0026	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0027	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	1 EA		
0028	2556000000-E	846	SHOULDER BERM GUTTER	12 LF		
0029	2570000000-N	SP	MODIFIED CONCRETE FLUME	1 EA		
0030	3030000000-E	862	STEEL BM GUARDRAIL	100 LF		
0031	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	25 LF		
0032	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0033	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0034	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	8 EA		
0035	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	7 EA		
0036	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	225 SY		
0037	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	52 SF		
0039	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0040	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	36 SF		
0041	4430000000-N	1130	DRUMS	15 EA		
0042	4435000000-N	1135	CONES	15 EA		
0043	4445000000-E	1145	BARRICADES (TYPE III)	20 LF		
0044	4450000000-N	1150	FLAGGER	240 HR		
0045	4485000000-E	1170	PORTABLE CONCRETE BARRIER	120 LF		
0046	4500000000-E	1170	RESET PORTABLE CONCRETE BARRIER	60 LF		
0047	6000000000-E	1605	TEMPORARY SILT FENCE	450 LF		
0048	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	125 TON		
0049	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	200 TON		
0050	6012000000-E	1610	SEDIMENT CONTROL STONE	60 TON		
0051	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0052	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0053	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25 TON		
0054	6024000000-E	1622	TEMPORARY SLOPE DRAINS	25 LF		
0055	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	1 EA		
0056	6030000000-E	1630	SILT EXCAVATION	200 CY		

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6036000000-E	1631	MATTING FOR EROSION CONTROL	750 SY		
0058	6042000000-E	1632	1/4" HARDWARE CLOTH	20 LF		
0059	6084000000-E	1660	SEEDING & MULCHING	1.5 ACR		
0060	6087000000-E	1660	MOWING	1 ACR		
0061	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0062	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0063	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0064	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		
0065	6114000000-N	SP	SPECIALIZED HAND MOWING	1.5 HR		
0066	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		
0067	6123000000-E	1670	REFORESTATION	0.15 ACR		

**STRUCTURE ITEMS**

0068	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (12+52.50 -L-)	Lump Sum	L.S.	
0069	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+60.00 -L-)	Lump Sum	L.S.	
0070	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (12+52.00 -L-)	Lump Sum	L.S.	
0071	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (15+60.00 -L-)	Lump Sum	L.S.	
0072	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	54.9 CY		

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	821000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (12+52.50 -L-)	Lump Sum	L.S.	
0074	821000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15+60.00 -L-)	Lump Sum	L.S.	
0075	821700000-E	425	REINFORCING STEEL (BRIDGE)	7,691 LB		
0076	836400000-E	450	HP12X53 STEEL PILES	1,540 LF		
0077	839100000-N	450	STEEL PILE POINTS	28 EA		
0078	850300000-E	460	CONCRETE BARRIER RAIL	238.3 LF		
0079	860800000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	530 TON		
0080	862200000-E	876	FILTER FABRIC FOR DRAINAGE	587 SY		
0081	865700000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0082	876200000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,072.36 LF		

0638/Oct06/Q19182.96/D350132100000/E82

Total Amount Of Bid For Entire Project :

C201073  
JACKSON COUNTY

2/16/99

Contract No: C201073

County: Jackson

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General