

County : Johnston, Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0000900000-N	SP	GENERIC MISCELLANEOUS ITEM CRITICAL PATH METHOD SCHEDULE	Lump Sum	L.S.	
0004	0000900000-N	SP	GENERIC MISCELLANEOUS ITEM DESIGN AND CONSTRUCTION FOR TRAFFIC CONTROL AND EROSION CONTROL	Lump Sum	L.S.	
0005	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0006	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0007	0022000000-E	225	UNCLASSIFIED EXCAVATION	5,000 CY		
0008	0036000000-E	225	UNDERCUT EXCAVATION	1,000 CY		
0009	0106000000-E	230	BORROW EXCAVATION	50,000 CY		
0010	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	100 SY		
0011	0163000000-E	250	REMOVAL OF EXISTING CONCRETE PAVEMENT	2,700 SY		
0012	0195000000-E	265	SELECT GRANULAR MATERIAL	1,000 CY		
0013	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	600 SY		
0014	0227000000-E	SP	GENERIC GRADING ITEM SAFETY CLEARING	2 ACR		
0015	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0016	1121000000-E	520	AGGREGATE BASE COURSE	400 TON		
0017	1275000000-E	600	PRIME COAT	450 GAL		
0018	1330000000-E	607	INCIDENTAL MILLING	2,500 SY		

County : Johnston, Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1493000000-E	610	ASPHALT CONC BASE COURSE, TYPE B37.5C	71,000 TON		
0020	1508000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0D	124,000 TON		
0021	1550000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S12.5D	90,000 TON		
0022	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	3,037 TON		
0023	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	5,828 TON		
0024	1570000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 76-22	4,950 TON		
0025	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	400 TON		
0026	1840000000-E	665	MILLED RUMBLE STRIPS	151,000 LF		
0027	1891000000-E	SP	GENERIC PAVING ITEM 8-1/2" CONTINUOUSLY REINFORCED CONCRETE PAVEMENT REPAIR	2,700 SY		
0028	1891000000-E	SP	GENERIC PAVING ITEM MILLING SHOULDERS, 9-3/4"DEPTH	210,000 SY		
0029	2022000000-E	815	SUBDRAIN EXCAVATION	840 CY		
0030	2033000000-E	815	SUBDRAIN FINE AGGREGATE	504 CY		
0031	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	3,000 LF		
0032	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	10 EA		
0033	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	6 EA		
0034	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	36 LF		
0035	2473000000-N	SP	GENERIC DRAINAGE ITEM EXISTING SHOULDER DRAIN OUTLET CLEAN-OUT	40 EA		

County : Johnston, Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	2500000000-E	842	CONCRETE RETAINING WALLS	500 CY		
0037	2815000000-N	858	ADJUSTMENT OF DROP INLETS	22 EA		
0038	3030000000-E	862	STEEL BM GUARDRAIL	5,800 LF		
0039	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	5 EA		
0040	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	5 EA		
0041	3285000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE M-350	4 EA		
0042	3360000000-E	863	REMOVE EXISTING GUARDRAIL	2,500 LF		
0043	3389600000-N	865	CABLE GUIDERAIL ANCHOR UNITS	20 EA		
0044	3420000000-E	SP	GENERIC GUARDRAIL ITEM REMOVE & RESET EXISTING DOUBLE FACED CABLE GUIDERAIL	17,000 LF		
1433/Oct26/Q756966.0/D65459900000/E44			Total Amount Of Bid For Entire Project :			

Contract No: C201238

Counties: Johnston-Wilson

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General