

| ItemNumber | Sec # | Quantity | Unit | Description | ItemNumber | Sec # | Quantity | Unit | Description |
|-------------|-------|----------|------|---|--------------|-------|----------|------|--|
| 477000000-E | 1205 | 1,040 | LF | COLD APPLIED PLASTIC PAVEMENT MARKING LINES (4") | 732400000-N | 1716 | 15 | EA | JUNCTION BOX (STANDARD SIZE) |
| 481000000-E | 1205 | 72,607 | LF | PAINT PAVEMENT MARKING LINES (4") | 733600000-N | 1716 | 9 | EA | JUNCTION BOX (OVER-SIZED) |
| 482000000-E | 1205 | 120 | LF | PAINT PAVEMENT MARKING LINES (8") | 737200000-N | 1721 | 3 | EA | GUY ASSEMBLY |
| 483500000-E | 1205 | 144 | LF | PAINT PAVEMENT MARKING LINES (24") | 743200000-E | 1722 | 3 | EA | 2" RISER WITH HEAT SHRINK TUBING |
| 490000000-N | 1252 | 683 | EA | PERMANENT RAISED PAVEMENT MARKERS | 744400000-E | 1725 | 4,740 | LF | INDUCTIVE LOOP SAWCUT |
| 530000000-E | 1505 | 50 | TON | FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI) | 745600000-E | 1726 | 4,740 | LF | LEAD-IN CABLE |
| 530600000-E | SP | 50 | TON | BEDDING MATERIAL, UTILITIES CLASS ***** (IV) | 751600000-E | 1730 | 4,510 | LF | COMMUNICATIONS CABLE (**FIBER) (12) |
| 536000000-E | 1510 | 951 | LF | 6" DI WATER PIPE, PC 350 | 755200000-N | 1731 | 3 | EA | INTERCONNECT CENTER |
| 548000000-E | 1510 | 600 | LB | DUCTILE IRON WATER PIPE FITTINGS, 250# MN WP | 756400000-N | 1732 | 3 | EA | FIBER-OPTIC TRANSCEIVER |
| 584000000-E | 1540 | 318 | LF | *** STEEL ENCASUREMENT PIPE, ***** THICK, BY OPEN CUT (12-3/4", 0.188") | 756600000-N | 1733 | 8 | EA | DELINEATOR MARKER |
| 600000000-E | 1605 | 27,785 | LF | TEMPORARY SILT FENCE | 757400000-N | SP | 1 | EA | FURNISH FIBER-OPTIC TRANSCEIVER |
| 600600000-E | 1610 | 735 | TON | STONE FOR EROSION CONTROL, CLASS A | 7575180000-N | SP | 1 | EA | CABLE TRANSFER |
| 600900000-E | 1610 | 21,025 | TON | STONE FOR EROSION CONTROL, CLASS B | 758800000-N | 1741 | 7 | EA | SIGNAL SUPPORT MAST ARM WITH METAL POLE |
| 601200000-E | 1610 | 9,225 | TON | SEDIMENT CONTROL STONE | 759000000-N | SP | 1 | EA | DOUBLE MAST ARM WITH METAL POLE |
| 601500000-E | 1615 | 110 | ACR | TEMPORARY MULCHING | 761300000-N | SP | 8 | EA | SOIL TEST |
| 601800000-E | 1620 | 3,750 | LB | SEED FOR TEMPORARY SEEDING | 761400000-E | SP | 105 | LF | DRILLED PIER FOUNDATION (** DIA) (42") |
| 602100000-E | 1620 | 15 | TON | FERTILIZER FOR TEMPORARY SEEDING | 761400000-E | SP | 15 | LF | DRILLED PIER FOUNDATION (** DIA) (48") |
| 602400000-E | 1622 | 2,440 | LF | TEMPORARY SLOPE DRAINS | 763100000-N | 1744 | 8 | EA | MAST ARM WITH METAL POLE DESIGN |
| 602700000-N | 1622 | 41 | EA | INLET PROTECTION AT TEMPORARY SLOPE DRAINS | 763600000-N | 1745 | 6 | EA | SIGN FOR SIGNALS |
| 602900000-E | SP | 11,140 | LF | SAFETY FENCE | 768400000-N | 1750 | 3 | EA | SIGNAL CABINET FOUNDATION |
| 603000000-E | 1630 | 137,875 | CY | SILT EXCAVATION | 768800000-N | SP | 3 | EA | CABINET BASE ADAPTER |
| 603600000-E | 1631 | 16,745 | SY | MATTING FOR EROSION CONTROL | 775600000-N | 1751 | 3 | EA | CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED) |
| 603800000-E | SP | 1,710 | SY | PERMANENT SOIL REINFORCEMENT MAT | 778000000-N | SP | 14 | EA | DETECTOR CARD (TYPE 2070L) |
| 604200000-E | 1632 | 2,930 | LF | 1/4" HARDWARE CLOTH | 796000000-N | SP | 2 | EA | METAL POLE FOUNDATION REMOVAL |
| 606900000-E | 1638 | 440 | CY | STILLING BASINS | 797200000-N | SP | 2 | EA | METAL POLE REMOVAL |
| 608400000-E | 1660 | 202.5 | ACR | SEEDING & MULCHING | 798000000-N | SP | 1 | EA | GENERIC SIGNAL ITEM MODIFY CONTROLLER WITH CABINET NEMA TS-1 |
| 608700000-E | 1660 | 62.5 | ACR | MOWING | | | | | |
| 609000000-E | 1661 | 900 | LB | SEED FOR REPAIR SEEDING | | | | | |
| 609300000-E | 1661 | 2 | TON | FERTILIZER FOR REPAIR SEEDING | | | | | |
| 609600000-E | 1662 | 2,500 | LB | SEED FOR SUPPLEMENTAL SEEDING | | | | | |
| 610800000-E | 1665 | 151.75 | TON | FERTILIZER TOPDRESSING | | | | | |
| 610920000-E | SP | 1.85 | ACR | SPECIALIZED SEEDING UNDER GUIDERAIL & GUARDRAIL (CENTIPEDE) | | | | | |
| 611100000-E | SP | 37 | LF | IMPERVIOUS DIKE | | | | | |
| 611400000-N | SP | 40 | HR | SPECIALIZED HAND MOWING | | | | | |
| 611700000-N | 1675 | 36 | EA | RESPONSE FOR EROSION CONTROL | | | | | |
| 611800000-N | SP | 96 | EA | ROOTWADS | | | | | |
| 612000000-E | SP | 1,130 | CY | CULVERT DIVERSION CHANNEL | | | | | |
| 612300000-E | 1670 | 4.5 | ACR | REFORESTATION | | | | | |
| 612600000-E | SP | 2.11 | ACR | STREAMBANK REFORESTATION | | | | | |
| 706000000-E | 1705 | 2,000 | LF | SIGNAL CABLE | | | | | |
| 712000000-E | 1705 | 15 | EA | VEHICLE SIGNAL HEAD (12", 3 SECTION) | | | | | |
| 714400000-E | 1705 | 6 | EA | VEHICLE SIGNAL HEAD (12", 5 SECTION) | | | | | |
| 725200000-E | 1710 | 3,050 | LF | MESSENGER CABLE (1/4") | | | | | |
| 727900000-E | 1715 | 370 | LF | TRACER WIRE | | | | | |
| 730000000-E | 1715 | 2,190 | LF | TRENCHING (UNPAVED) | | | | | |
| 730100000-E | SP | 1,130 | LF | DIRECTIONAL DRILL POLYETHYLENE CONDUIT, ***** (** CONDUIT) (2", 2) | | | | | |
| 730200000-E | SP | 280 | LF | DIRECTIONAL DRILL POLYETHYLENE CONDUIT, 1-1/4" (** CONDUIT) (4) | | | | | |

7/2/99

05-JUN-2004 09:07
 R:\R-2417\B\Resdway\Proj\2417bb_rdy_tah.dgn
 B:\BRYL