

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200895

ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION	1011000000-N	500	Lump Sum		FINE GRADING	2619000000-E	850	65	SY	4" CONCRETE PAVED DITCH
0001000000-E	200	Lump Sum		CLEARING & GRUBBING . ACRE(S)	1044000000-E	501	58,850	SY	LIME TREATED SOIL (SLURRY METHOD)	2655000000-E	852	1,000	SY	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)
0008000000-E	200	4	ACR	SUPPLEMENTARY CLEARING & GRUBBING	1066000000-E	501	589	TON	LIME FOR LIME TREATED SOIL	2675000000-E	852	110	SY	3" CORRUGATED CONCRETE ISLANDS
0015000000-N	205	5	EA	SEALING ABANDONED WELLS	1110000000-E	510	1,000	TON	STABILIZER AGGREGATE	3000000000-N	SP	2	EA	IMPACT ATTENUATOR UNIT, TYPE 350
0022000000-E	225	455,000	CY	UNCLASSIFIED EXCAVATION	1121000000-E	520	45,900	TON	AGGREGATE BASE COURSE	3030000000-E	862	9,750	LF	STEEL BM GUARDRAIL
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (20+02.46-Y1-)	1176000000-E	542	58,850	SY	*** SOIL CEMENT BASE (7")	3150000000-N	862	20	EA	ADDITIONAL GUARDRAIL POSTS
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (565+49.40-LT-)	1187000000-E	542	244	TON	PORTLAND CEMENT FOR SOIL CEMENT BASE	3180000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE ***** (B-77)
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (565+49.40-RT-)	1198000000-E	SP	736	TON	AGGREGATE FOR SOIL CEMENT BASE	3210000000-N	862	7	EA	GUARDRAIL ANCHOR UNITS, TYPE CAT-1
0036000000-E	225	5,000	CY	UNDERCUT EXCAVATION	1220000000-E	545	500	TON	INCIDENTAL STONE BASE	3215000000-N	862	10	EA	GUARDRAIL ANCHOR UNITS, TYPE III
0080000000-E	SP	500	TON	CLASS IV SUBGRADE STABILIZATION	1275000000-E	600	1,187	GAL	PRIME COAT	3270000000-N	SP	12	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
0106000000-E	230	1,400,000	CY	BORROW EXCAVATION	1489000000-E	610	420	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	3270000000-N	SP	12	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
0134000000-E	240	15,000	CY	DRAINAGE DITCH EXCAVATION	1491000000-E	610	11,800	TON	ASPHALT CONC BASE COURSE, TYPE B25.0C	3285000000-N	SP	2	EA	GUARDRAIL ANCHOR UNITS, TYPE M-350
0141000000-E	240	2,400	LF	BERM DITCH CONSTRUCTION	1503000000-E	610	23,700	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	3389400000-E	865	8,400	LF	DOUBLE FACED CABLE GUIDERAIL
0156000000-E	250	8,700	SY	REMOVAL OF EXISTING ASPHALT PAVEMENT	1523000000-E	610	20,100	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	3389600000-N	865	12	EA	CABLE GUIDERAIL ANCHOR UNITS
0192000000-N	260	24	HR	PROOF ROLLING	1525000000-E	SP	1,100	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	3503000000-E	866	22,500	LF	WOVEN WIRE FENCE, 47" FABRIC
0195000000-E	265	18,000	CY	SELECT GRANULAR MATERIAL	1560000000-E	620	1,711	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	3509000000-E	866	1,450	EA	4" TIMBER FENCE POSTS, 7'-6" LONG
0196000000-E	270	17,500	SY	FABRIC FOR SOIL STABILIZATION	1565000000-E	620	1,206	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	3515000000-E	866	400	EA	5" TIMBER FENCE POSTS, 8'-0" LONG
0255000000-E	SP	200	TON	GENERIC GRADING ITEM DISPOSAL OF CONTAMINATED SOIL	1693000000-E	654	200	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR	3557000000-E	866	22,500	LF	ADDITIONAL BARBED WIRE
0318000000-E	300	1,500	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	1840000000-E	665	39,800	LF	MILLED RUMBLE STRIPS	3628000000-E	876	515	TON	PLAIN RIP RAP, CLASS I
0343000000-E	310	168	LF	15" SIDE DRAIN PIPE	2022000000-E	815	175	CY	SUBDRAIN EXCAVATION	3649000000-E	876	2,600	TON	PLAIN RIP RAP, CLASS B
0354000000-E	310	308	LF	**** RC PIPE CULVERTS, CLASS ***** (36", V)	2033000000-E	815	100	CY	SUBDRAIN FINE AGGREGATE	3651000000-E	SP	40	TON	BOULDERS
0366000000-E	310	4,470	LF	15" RC PIPE CULVERTS, CLASS III	2044000000-E	815	500	LF	6" PERFORATED SUBDRAIN PIPE	3656000000-E	876	12,390	SY	FILTER FABRIC FOR DRAINAGE
0372000000-E	310	1,918	LF	18" RC PIPE CULVERTS, CLASS III	2055000000-E	815	15	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	4048000000-E	902	13	CY	REINFORCED CONCRETE SIGN FOOTINGS
0378000000-E	310	1,136	LF	24" RC PIPE CULVERTS, CLASS III	2066000000-N	815	1	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	4054000000-E	902	1	CY	PLAIN CONCRETE SIGN FOOTINGS
0384000000-E	310	946	LF	30" RC PIPE CULVERTS, CLASS III	2077000000-E	815	6	LF	6" OUTLET PIPE (SUBDRAINS)	4060000000-E	903	2,541	LB	SUPPORTS, BREAKAWAY STEEL BEAM
0390000000-E	310	172	LF	36" RC PIPE CULVERTS, CLASS III	2099000000-E	816	400	LF	SHOULDER DRAIN	4066000000-E	903	7,169	LB	SUPPORTS, SIMPLE STEEL BEAM
0396000000-E	310	316	LF	42" RC PIPE CULVERTS, CLASS III	2110000000-E	816	400	LF	4" SHOULDER DRAIN PIPE	4072000000-E	903	822	LF	SUPPORTS, 3-LB STEEL U-CHANNEL
0448000000-E	310	460	LF	**** RC PIPE CULVERTS, CLASS IV (24")	2121000000-E	816	18.5	LF	4" OUTLET PIPE (SHOULDER DRAINS)	4096000000-N	904	5	EA	SIGN ERECTION, TYPE D
0448000000-E	310	488	LF	**** RC PIPE CULVERTS, CLASS IV (36")	2143000000-E	818	10	TON	BLOTTING SAND	4102000000-N	904	26	EA	SIGN ERECTION, TYPE E
0448000000-E	310	688	LF	**** RC PIPE CULVERTS, CLASS IV (42")	2209000000-E	838	40	CY	ENDWALLS	4108000000-N	904	11	EA	SIGN ERECTION, TYPE F
0448000000-E	310	648	LF	**** RC PIPE CULVERTS, CLASS IV (48")	2253000000-E	840	2	CY	PIPE COLLARS	4110000000-N	904	11	EA	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)
0570000000-E	310	56	LF	6" CS PIPE CULVERTS, 0.064" THICK (SPRING BOX)	2275000000-E	SP	5	CY	FLOWABLE FILL	4110000000-N	904	6	EA	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (B)
0708000000-E	310	1,464	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	2286000000-N	840	89	EA	MASONRY DRAINAGE STRUCTURES	4400000000-E	1110	835	SF	WORK ZONE SIGNS (STATIONARY)
0714000000-E	310	68	LF	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	2308000000-E	840	22	LF	MASONRY DRAINAGE STRUCTURES	4405000000-E	1110	296	SF	WORK ZONE SIGNS (PORTABLE)
0720000000-E	310	184	LF	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	2364200000-N	840	21	EA	FRAME WITH TWO GRATES, STD 840.20	4410000000-E	1110	220	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
0726000000-E	310	116	LF	30" BIT COAT CS PIPE CULVERTS, TYPE B 0.079" THICK	2365000000-N	840	44	EA	FRAME WITH TWO GRATES, STD 840.22	4425000000-N	1125	4	EA	WARNING FLAG SETS
0806000000-E	310	28	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2366000000-N	840	16	EA	FRAME WITH TWO GRATES, STD 840.24	4430000000-N	1130	275	EA	DRUMS
0807000000-E	310	4	EA	18" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2374000000-N	840	2	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	4435000000-N	1135	124	EA	CONES
0808000000-E	310	4	EA	24" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2374000000-N	840	3	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	4445000000-E	1145	284	LF	BARRICADES (TYPE III)
0809000000-E	310	6	EA	30" BIT COAT CS PIPE ELBOWS, TYPE B 0.079" THICK	2374000000-N	840	1	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	4455000000-N	1150	384	MD	FLAGGER
0995000000-E	340	692	LF	PIPE REMOVAL	2396000000-N	840	1	EA	FRAME WITH COVER, STD 840.54	4520000000-N	1266	85	EA	TUBULAR MARKERS (FIXED)
1000000000-E	462	500	SY	6" SLOPE PROTECTION	2440000000-N	840	6	EA	CONCRETE APRON FOR CATCH BASIN	4650000000-N	1251	240	EA	TEMPORARY RAISED PAVEMENT MARKERS
					2451000000-N	840	81	EA	CONCRETE APRON FOR DROP INLETS	4685000000-E	1205	59,500	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
					2535000000-E	846	1,300	LF	***X*** CONCRETE CURB (8" X 18")	4686000000-E	1205	25,668	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
					2549000000-E	846	2,500	LF	2'-6" CONCRETE CURB & GUTTER	4695000000-E	1205	3,341	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)
					2556000000-E	846	4,550	LF	SHOULDER BERM GUTTER	4710000000-E	1205	653	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)
					2570000000-N	SP	2	EA	MODIFIED CONCRETE FLUME	4721000000-E	1205	8	EA	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120MIL)
					2580000000-E	846	725	LF	CONCRETE VALLEY GUTTER	4725000000-E	1205	61	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)

5/28/99

F:\10-2004\12-36_b4256_rdy_typ.dgn
V:\web\at\DS212419