

CHANNEL MIGRATION TENDENCY(14): *NONE OBSERVED*

GEOTECHNICAL ADJUSTED SCOUR ELEVATIONS (15): *NO SCOUR ANTICIPATED ON ANY END BENT ASSUMING ADEQUATE RIP-RAP IS USED ON EB-2.*

*NO SCOUR IS PREDICTED FOR BENT 1.*

*NO SCOUR IS PREDICTED FOR BENT 2 (SBL). NO SCOUR IS ANTICIPATED ON BENT 2 (NBL) ASSUMING ADEQUATE RIP-RAP IS USED.*

*THE GEOLOGICAL SCOUR FOR B3-A (SBL) IS AT ELEV. 214.0m, FOR B3-B(SBL) & B3- A & B (NBL) IS AT ELEV 216.0m.*

REPORTED BY: *CCM* DATE: *APRIL 4 2000,*

### INSTRUCTIONS

- (1) GIVE THE DESCRIPTION OF THE SPECIFIC SITE GIVING ROUTE NUMBER AND BODY OF WATER CROSSED.
- (2) NOTE ANY EVIDENCE OF SCOUR AT THE EXISTING END BENTS OR ABUTMENTS (UNDERMINING, SLOUGHING, SCOUR LOCATIONS DEGRADATIONS, ETC.)
- (3) NOTE ANY EXISTING SCOUR PROTECTION (RIPRAP, ETC.)
- (4) DESCRIBE THE EXTENT OF ANY EXISTING SCOUR PROTECTION.
- (5) DESCRIBE WHETHER OR NOT THE SCOUR PROTECTION APPEARS TO BE WORKING.
- (6) NOTE ANY DAMS, FALLEN TREES, DEBRIS AT BENTS, ETC.
- (7) DESCRIBE THE CHANNEL BED MATERIAL; A SAMPLE SHOULD BE TAKEN FOR GRAIN SIZE DISTRIBUTION, ATTACH LAB RESULTS.
- (8) DESCRIBE THE CHANNEL BANK MATERIAL; A SAMPLE SHOULD BE TAKEN FOR GRAIN SIZE DISTRIBUTION, ATTACH LAB RESULTS.
- (9) DESCRIBE THE FOUNDATION BEARING MATERIAL
- (10) DESCRIBE THE BANK COVERING (GRASS, TREES, RIPRAP, NONE, ETC.)
- (11) GIVE THE APPROXIMATE FLOOD PLAIN WIDTH (ESTIMATE).
- (12) DESCRIBE THE FLOOD PLAIN COVERING (GRASS, TREES, CROPS, ETC.)
- (13) CHECK THE APPROPRIATE SPACE AS TO WHETHER THE STREAM IS DEGRADING OR AGGRADING.
- (14) DESCRIBE THE POTENTIAL OF THE BODY OF WATER TO MIGRATE Laterally DURING THE LIFE OF THE BRIDGE (APPROXIMATELY 100 YEARS).
- (15) GIVE THE GEOTECHNICAL ADJUSTED SCOUR ELEVATION EXPECTED OVER THE LIFE OF THE BRIDGE (APPROXIMATELY 100 YEARS). THIS CAN BE GIVEN AS AN ELEVATION RANGE ACROSS THE SITE, OR ON A BENT BY BENT BASIS WHERE VARIATIONS EXIST. DISCUSS RELATIONSHIP BETWEEN THE HYDRAULICS THEORETICAL SCOUR AND THE GEOTECHNICAL ADJUSTED SCOUR ELEVATION. IF THE GEOTECHNICAL ADJUSTED SCOUR ELEVATION IS DEPENDENT ON SCOUR COUNTER MEASURES, EXPLAIN. (RIPRAP ARMORING ON SLOPES, ETC.) THE GEOTECHNICAL ADJUSTED SCOUR ELEVATION IS BASED ON THE ERODABILITY OF MATERIALS WITH CONSIDERATION FOR JOINTING, FOLIATION, BEDDING ORIENTATION AND FREQUENCY; CORE RECOVERY PERCENTAGE; PERCENT RQD; DIFFERENTIAL WEATHERING; SHEAR STRENGTH; OBSERVATIONS AT EXISTING STRUCTURES; OTHER TESTS DEEMED APPROPRIATE; AND OVERALL GEOLOGIC CONDITIONS AT THE SITE.