

County : Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0000700000-N	SP	FIELD OFFICE	Lump Sum	L.S.	
0004	0001000000-M	200	CLEARING & GRUBBING ... HEC-TARE(S)	Lump Sum	L.S.	
0005	0008000000-M	200	SUPPLEMENTARY CLEARING & GRUB-BING	2 HA		
0006	0015000000-N	205	SEALING ABANDONED WELLS	9 EA		
0007	0022000000-M	225	UNCLASSIFIED EXCAVATION	1,650,500 M3		
0008	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (123+52.783)	Lump Sum	L.S.	
0009	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (123+79.487)	Lump Sum	L.S.	
0010	0036000000-M	225	UNDERCUT EXCAVATION	17,000 M3		
0011	0106000000-M	230	BORROW EXCAVATION	318,500 M3		
0012	0134000000-M	240	DRAINAGE DITCH EXCAVATION	31,100 M3		
0013	0141000000-M	240	BERM DITCH CONSTRUCTION	140 M		
0014	0156000000-M	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	3,200 M2		
0015	0177000000-M	250	BREAKING OF EXISTING ASPHALT PAVEMENT	1,100 M2		
0016	0192000000-N	260	PROOF ROLLING	30 HR		
0017	0195000000-M	265	SELECT GRANULAR MATERIAL	15,000 M3		
0018	0196000000-M	270	FABRIC FOR SOIL STABILIZATION	14,100 M2		
0019	0300000000-M	300	SELECT MATERIAL, CLASS II	4,600 MTN		

County : Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	0306000000-M	300	SELECT MATERIAL, CLASS III	4,700 MTN		
0021	0312000000-M	300	SELECT MATERIAL, CLASS IV	26,500 MTN		
0022	0318000000-M	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	1,665 MTN		
0023	0343000000-M	310	375MM SIDE DRAIN PIPE	31.2 M		
0024	0354000000-M	310	****MM RC PIPE CULVERTS, CLASS *** (1050MM , V)	124.8 M		
0025	0354000000-M	310	****MM RC PIPE CULVERTS, CLASS *** (1350MM, V)	183.6 M		
0026	0354000000-M	310	****MM RC PIPE CULVERTS, CLASS *** (1650MM, V)	111.6 M		
0027	0354000000-M	310	****MM RC PIPE CULVERTS, CLASS *** (750MM, V)	153.6 M		
0028	0366000000-M	310	375MM RC PIPE CULVERTS, CLASS III	1,642.6 M		
0029	0372000000-M	310	450MM RC PIPE CULVERTS, CLASS III	585.6 M		
0030	0378000000-M	310	600MM RC PIPE CULVERTS, CLASS III	86.4 M		
0031	0384000000-M	310	750MM RC PIPE CULVERTS, CLASS III	108 M		
0032	0448000000-M	310	****MM RC PIPE CULVERTS, CLASS IV (1050MM)	440.4 M		
0033	0448000000-M	310	****MM RC PIPE CULVERTS, CLASS IV (1200MM)	121.2 M		
0034	0448000000-M	310	****MM RC PIPE CULVERTS, CLASS IV (450MM)	66 M		

County : Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	0448000000-M	310	****MM RC PIPE CULVERTS, CLASS IV (600MM)	178.8	M	
0036	0448000000-M	310	****MM RC PIPE CULVERTS, CLASS IV (750MM)	302.4	M	
0037	0448000000-M	310	****MM RC PIPE CULVERTS, CLASS IV (900MM)	238.8	M	
0038	0453000000-M	310	***MM PIPE END SECTION (375MM)	2	EA	
0039	0588000000-M	310	450MM CS PIPE CULVERTS, 1.63MM THICK	20.4	M	
0040	0594000000-M	310	600MM CS PIPE CULVERTS, 1.63MM THICK	32.4	M	
0041	0708000000-M	310	400MM BIT COAT CS PIPE CULVERTS, TYPE B 1.63MM THICK	700.8	M	
0042	0714000000-M	310	450MM BIT COAT CS PIPE CULVERTS, TYPE B 1.63MM THICK	120	M	
0043	0720000000-M	310	600MM BIT COAT CS PIPE CULVERTS, TYPE B 1.63MM THICK	32.4	M	
0044	0726000000-M	310	800MM BIT COAT CS PIPE CULVERTS, TYPE B 2.01MM THICK	22.8	M	
0045	0732000000-M	310	900MM BIT COAT CS PIPE CULVERTS, TYPE B 2.01MM THICK	49.2	M	
0046	0806000000-M	310	400MM BIT COAT CS PIPE ELBOWS, TYPE B 1.63MM THICK	40	EA	
0047	0807000000-M	310	450MM BIT COAT CS PIPE ELBOWS, TYPE B 1.63MM THICK	12	EA	
0048	0809000000-M	310	800MM BIT COAT CS PIPE ELBOWS, TYPE B 2.01MM THICK	2	EA	
0049	0986000000-M	SP	GENERIC PIPE ITEM 150MM PVC PIPE, SDR 80 (SPRING BOX)	32	M	
0050	0995000000-M	340	PIPE REMOVAL	226	M	

County : Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0051	0996000000-N	350	PIPE CLEAN-OUT	1 EA		
0052	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0053	1121000000-M	520	AGGREGATE BASE COURSE	17,000 MTN		
0054	1220000000-M	545	INCIDENTAL STONE BASE	100 MTN		
0055	1275000000-M	600	PRIME COAT	7,200 L		
0056	1489000000-M	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,400 MTN		
0057	1491000000-M	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	2,100 MTN		
0058	1498000000-M	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	3,500 MTN		
0059	1503000000-M	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	1,900 MTN		
0060	1519000000-M	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,850 MTN		
0061	1539000000-M	610	ASPHALT CONC SURFACE COURSE, TYPE S12.5C	800 MTN		
0062	1560000000-M	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	525 MTN		
0063	1565000000-M	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	45 MTN		
0064	1693000000-M	654	ASPHALT PLANT MIX PAVEMENT REPAIR	50 MTN		
0065	2022000000-M	815	SUBDRAIN EXCAVATION	450 M3		
0066	2033000000-M	815	SUBDRAIN FINE AGGREGATE	220 M3		
0067	2044000000-M	815	150MM PERFORATED SUBDRAIN PIPE	500 M		
0068	2055000000-M	815	150MM SUBDRAIN PIPE WYES, TEES, & ELBOWS	50 EA		

County: Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0069	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	4 EA		
0070	2077000000-M	815	150MM OUTLET PIPE (SUBDRAINS)	8 M		
0071	2209000000-M	838	ENDWALLS	31 M3		
0072	2220000000-M	838	REINFORCED ENDWALLS	9 M3		
0073	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	116 EA		
0074	2297000000-M	840	MASONRY DRAINAGE STRUCTURES	4 M3		
0075	2308000000-M	840	MASONRY DRAINAGE STRUCTURES	26 M		
0076	2354000000-N	840	FRAME WITH GRATE, STD 840.22	5 EA		
0077	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	110 EA		
0078	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0079	2619000000-M	850	100MM CONCRETE PAVED DITCH	17 M2		
0080	3030000000-M	862	STEEL BM GUARDRAIL	392.43 M		
0081	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	2 EA		
0082	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0083	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	1 EA		
0084	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	5 EA		
0085	3503000000-M	866	WOVEN WIRE FENCE, 1200MM FAB- RIC	15,800 M		
0086	3509000000-M	866	100MM TIMBER FENCE POSTS, 2.30M LONG	3,300 EA		
0087	3515000000-M	866	125MM TIMBER FENCE POSTS, 2.50M LONG	850 EA		

County: Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0088	3557000000-M	866	ADDITIONAL BARBED WIRE	50 M		
0089	3559000000-M	866	** STRAND BARBED WIRE FENCE WITH POSTS (4)	325 M		
0090	3575000000-M	SP	GENERIC FENCING ITEM 4 STRAND BARBED WIRE WITH 1 STRAND ELECTRIC WIRE FENCE	150 M		
0091	3628000000-M	876	PLAIN RIP RAP, CLASS I	475 MTN		
0092	3642000000-M	876	PLAIN RIP RAP, CLASS A	2 MTN		
0093	3649000000-M	876	PLAIN RIP RAP, CLASS B	4,475 MTN		
0094	3651000000-M	SP	BOULDERS	350 MTN		
0095	3656000000-M	876	FILTER FABRIC FOR DRAINAGE	13,100 M2		
0096	4400000000-M	1110	WORK ZONE SIGNS (STATIONARY)	35 M2		
0097	4405000000-M	1110	WORK ZONE SIGNS (PORTABLE)	18 M2		
0098	4410000000-M	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	15 M2		
0099	4430000000-N	1130	DRUMS	170 EA		
0100	4435000000-N	1135	CONES	50 EA		
0101	4445000000-M	1145	BARRICADES (TYPE III)	115 M		
0102	4455000000-N	1150	FLAGGER	300 MD		
0103	4810000000-M	1205	PAINT PAVEMENT MARKING LINES (100MM)	13,200 M		
0104	4830000000-M	1205	PAINT PAVEMENT MARKING LINES (400MM)	30 M		
0105	4835000000-M	1205	PAINT PAVEMENT MARKING LINES (600MM)	24 M		

County : Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0106	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	4 EA		
0107	4850000000-M	1205	REMOVAL OF PAVEMENT MARKING LINES (100MM)	800 M		
0108	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	105 EA		
0109	5300000000-M	1505	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (II)	30 MTN		
0110	5306000000-M	SP	BEDDING MATERIAL, UTILITIES CLASS ***** (II)	20 MTN		
0111	5360000000-M	1510	150MM DI WATER PIPE, PC 2.41MPA	4 M		
0112	5414000000-M	1510	20MM COPPER WATER PIPE, TYPE K	63 M		
0113	5474000000-M	1510	200MM PVC WATER PIPE, (C900), DR *** , ****MPA WP (14, 1.38MPA WP)	637.5 M		
0114	5480000000-M	1510	DUCTILE IRON WATER PIPE FITTINGS, 1.72MPA MIN WP	315 KG		
0115	5504000000-M	1510	***MM CORPORATION STOP (20MM)	1 EA		
0116	5540000000-M	1510	150MM GATE VALVE & VALVE BOX, 1.38MPA WP	2 EA		
0117	5546000000-M	1510	200MM GATE VALVE & VALVE BOX, ****MPA WP (1.38MPA WP)	2 EA		
0118	5582000000-M	1510	*** X ***MM TAPPING SADDLE (200MM X 20MM)	1 EA		
0119	5648000000-N	1510	RELOCATE EXISTING WATER METER	1 EA		
0120	5672000000-N	1510	RELOCATE EXISTING FIRE HYDRANT	2 EA		
0121	6000000000-M	1605	TEMPORARY SILT FENCE	980 M		

County : Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0122	6006000000-M	1610	STONE FOR EROSION CONTROL, CLASS A	420 MTN		
0123	6009000000-M	1610	STONE FOR EROSION CONTROL, CLASS B	17,965 MTN		
0124	6012000000-M	1610	SEDIMENT CONTROL STONE	6,590 MTN		
0125	6015000000-M	1615	TEMPORARY MULCHING	74 HA		
0126	6018000000-M	1620	SEED FOR TEMPORARY SEEDING	3,225 KG		
0127	6021000000-M	1620	FERTILIZER FOR TEMPORARY SEED- ING	25.75 MTN		
0128	6024000000-M	1622	TEMPORARY SLOPE DRAINS	2,165 M		
0129	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	104 EA		
0130	6030000000-M	1630	SILT EXCAVATION	79,700 M3		
0131	6033000000-M	1631	SYNTHETIC ROVING	7,780 M2		
0132	6036000000-M	1631	MATTING FOR EROSION CONTROL	3,890 M2		
0133	6037000000-M	SP	COIR FIBER MAT	1,200 M2		
0134	6042000000-M	1632	6.4MM HARDWARE CLOTH	95 M		
0135	6045000000-M	SP	***MM TEMPORARY PIPE (450MM)	65 M		
0136	6054000000-M	1637	***X***X***MM PERFORATED CS PIPE TEE RISER, 1.63MM THICK (450MM X 450MM X 450MM)	1 EA		
0137	6054000000-M	1637	***X***X***MM PERFORATED CS PIPE TEE RISER, 1.63MM THICK (600MM X 600MM X 600MM)	2 EA		
0138	6069000000-M	1638	STILLING BASINS	210 M3		
0139	6070000000-N	SP	SPECIAL STILLING BASINS	12 EA		

County : Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0140	6084000000-M	1660	SEEDING & MULCHING	76.5 HA		
0141	6087000000-M	1660	MOWING	41.5 HA		
0142	6090000000-M	1661	SEED FOR REPAIR SEEDING	900 KG		
0143	6093000000-M	1661	FERTILIZER FOR REPAIR SEEDING	3 MTN		
0144	6096000000-M	1662	SEED FOR SUPPLEMENTAL SEEDING	2,150 KG		
0145	6108000000-M	1665	FERTILIZER TOPDRESSING	128.5 MTN		
0146	6109000000-M	SP	SPECIALIZED SEEDING UNDER GUIDERAIL & GUARDRAIL (HARD FESCUE/BUEGRASS)	0.35 HA		
0147	6111000000-M	SP	IMPERVIOUS DIKE	105 M		
0148	6114000000-N	SP	SPECIALIZED HAND MOWING	20 HR		
0149	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	32 EA		
0150	6118000000-N	SP	ROOTWADS	10 EA		
0151	6120000000-M	SP	CULVERT DIVERSION CHANNEL	1,670 M3		
0152	6123000000-M	1670	REFORESTATION	5 HA		
0153	6126000000-M	SP	STREAMBANK REFORESTATION	0.55 HA		

CULVERT ITEMS

0154	8049000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18+51.500-Y9-)	Lump Sum	L.S.	
0155	8126000000-N	414	CULVERT EXCAVATION, STA ***** (132+58.000-L-)	Lump Sum	L.S.	
0156	8126000000-N	414	CULVERT EXCAVATION, STA ***** (158+95.000-L-)	Lump Sum	L.S.	

County : Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0157	8126000000-N	414	CULVERT EXCAVATION, STA ***** (18+51.500-Y9-)	Lump Sum	L.S.	
0158	8133000000-M	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	758 MTN		
0159	8196000000-M	420	CLASS A CONCRETE (CULVERT)	1,320.3 M3		
0160	8245000000-M	425	REINFORCING STEEL (CULVERT)	114,610 KG		
0161	8590000000-M	876	PLAIN RIP RAP, CLASS ** (I)	28 MTN		
0162	8594000000-M	876	PLAIN RIP RAP CLASS B	117.7 MTN		
0163	8622000000-M	876	FILTER FABRIC FOR DRAINAGE	28 M2		
STRUCTURE ITEMS						
0164	8096000000-M	SP	PILE EXCAVATION IN SOIL	22.1 M		
0165	8097000000-M	SP	PILE EXCAVATION NOT IN SOIL	11 M		
0166	8105500000-M	SP	****MM DIA DRILLED PIERS IN SOIL (1524MM)	109.6 M		
0167	8105600000-M	SP	****MM DIA DRILLED PIERS NOT IN SOIL (1524MM)	100.4 M		
0168	8111000000-M	SP	PERMANENT STEEL CASING FOR ****MM DRILLED PIER (1524MM)	50.1 M		
0169	8113000000-N	SP	SID INSPECTION	8 EA		
0170	8114000000-N	SP	SPT TESTING	8 EA		
0171	8115000000-N	SP	CROSSHOLE SONIC LOGGING	6 EA		
0172	8116000000-M	SP	CSL TUBES	921.44 M		

County : Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0173	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (123+38.105-L-RIGHT LANE)	Lump Sum	L.S.	
0174	8147000000-M	420	REINFORCED CONCRETE DECK SLAB	3,887 M2		
0175	8161000000-M	420	GROOVING BRIDGE FLOORS	3,828.6 M2		
0176	8182000000-M	420	CLASS A CONCRETE (BRIDGE)	872.4 M3		
0177	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (123+38.105-L-LEFT LANE)	Lump Sum	L.S.	
0178	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (123+38.105-L-RIGHT LANE)	Lump Sum	L.S.	
0179	8217000000-M	425	REINFORCING STEEL (BRIDGE)	147,576 KG		
0180	8238000000-M	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	22,343 KG		
0181	8280000000-M	440	APPROX KG STRUCTURAL STEEL	759,200 LS		
0182	8364000000-M	450	HP310X79 STEEL PILES	435 M		
0183	8391000000-N	450	STEEL PILE POINTS	48 EA		
0184	8503000000-M	460	CONCRETE BARRIER RAIL	627.448 M		
0185	8531000000-M	462	100MM SLOPE PROTECTION	622 M2		
0186	8608000000-M	876	PLAIN RIP RAP CLASS II (600MM THICK)	1,781 MTN		
0187	8622000000-M	876	FILTER FABRIC FOR DRAINAGE	1,818 M2		
0188	8650000000-N	SP	POT BEARINGS	Lump Sum	L.S.	
0189	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0190	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

1044/Oct11/Q3377921.168/D758832300000/E190

Total Amount Of Bid For Entire Project :

C200910 (R-2206B)
LINCOLN COUNTY

2/16/99

Contract No: C200910

County: Lincoln

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General