



### FINAL PAVEMENT MARKING SCHEDULE

| SYMBOL | DESCRIPTION  | BREAKDOWN | TOTAL QUANTITY |
|--------|--|-----------|----------------|
| PA     | PAINT (4")<br>WHITE EDGELINE (2X)                    | 15920 LF  |                |
| PD     | 2 FT. WHITE MINISKIP (2X)                            | 106 LF    |                |
| PE     | WHITE SOLID LANE LINE (2X)                           | 800 LF    |                |
| PI     | YELLOW DOUBLE CENTER (1X)                            | 6000 LF   |                |
|        |  | TOTAL     | 22826 LF       |
| PV     | PAINT (8")<br>YELLOW DIAGONAL (2X)                   | 40 LF     |                |
|        |  | TOTAL     | 40 LF          |
| P4     | PAINT (24")<br>WHITE STOPBAR (2X)                    | 264 LF    |                |
|        |  | TOTAL     | 264 LF         |
| MA     | PERMANENT RAISED PAVEMENT MARKERS<br>YELLOW & YELLOW | 80 EA     |                |
|        |  | TOTAL     | 80 EA          |

**NOTE:**  
SEE SHEET TCP-6a FOR PAVEMENT MARKING DETAIL

|                              |                |  |  |
|------------------------------|----------------|--|--|
| APPROVED: <i>[Signature]</i> | DATE: 6-8-04   | <b>PHASE III DETAIL<br/>FINAL PAVEMENT MARKING /SCHEDULE</b> |  |
|                              |                |  |  |
| SCALE: NONE                  | DATE: JAN 2004 |  |  |
| DWG. BY: MRM                 | DESIGN BY: MRM |  |  |
| REVIEWED BY: JWW             |                |  |  |
|                              |                | REVISIONS  |  |
|                              |                | CARD FILE  |  |

02-JUN-2004 12:03  
 R:\TCP\B3879-TCP-06-10-04.dgn  
 mmmn\qupez AT 11/10/04