

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0043000000-N	226	GRADING	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	400 CY		
0005	0134000000-E	240	DRAINAGE DITCH EXCAVATION	200 CY		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0007	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0008	0206000000-E	SP	TEMPORARY SHORING - BARRIER SUPPORTED	425 SF		
0009	0343000000-E	310	15" SIDE DRAIN PIPE	160 LF		
0010	0344000000-E	310	18" SIDE DRAIN PIPE	56 LF		
0011	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	72 LF		
0012	0588000000-E	310	18" CS PIPE CULVERTS, 0.064" THICK	60 LF		
0013	0594000000-E	310	24" CS PIPE CULVERTS, 0.064" THICK	154 LF		
0014	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	64 LF		
0015	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0016	0995000000-E	340	PIPE REMOVAL	300 LF		
0017	1121000000-E	520	AGGREGATE BASE COURSE	1,080 TON		
0018	1220000000-E	545	INCIDENTAL STONE BASE	300 TON		
0019	1275000000-E	600	PRIME COAT	815 GAL		

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	1330000000-E	607	INCIDENTAL MILLING	1,080		SY
0021	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,010		TON
0022	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	840		TON
0023	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,840		TON
0024	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	203		TON
0025	2000000000-N	806	RIGHT OF WAY MARKERS	30		EA
0026	2022000000-E	815	SUBDRAIN EXCAVATION	23		CY
0027	2033000000-E	815	SUBDRAIN FINE AGGREGATE	17		CY
0028	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100		LF
0029	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3		EA
0030	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1		EA
0031	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6		LF
0032	2253000000-E	840	PIPE COLLARS	1.1		CY
0033	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4		EA
0034	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3		EA
0035	2396000000-N	840	FRAME WITH COVER, STD 840.54	1		EA
0036	2529000000-E	SP	GENERIC GRADING ITEM (SF) TEMPORARY FABRIC WALL	1,900		SF
0037	2556000000-E	846	SHOULDER BERM GUTTER	20		LF
0038	3030000000-E	862	STEEL BM GUARDRAIL	250		LF

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	75 LF		
0040	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0041	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0042	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0043	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0044	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	150 LF		
0045	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III)	4 EA		
0046	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	4 EA		
0047	3642000000-E	876	PLAIN RIP RAP, CLASS A	2 TON		
0048	3649000000-E	876	PLAIN RIP RAP, CLASS B	13 TON		
0049	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	343 SY		
0050	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0051	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	19 SF		
0052	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	165 LF		
0053	4102000000-N	904	SIGN ERECTION, TYPE E	3 EA		
0054	4129000000-N	906	RELOCATE SIGN, TYPE ***** (D)	3 EA		
0055	4129000000-N	906	RELOCATE SIGN, TYPE ***** (E)	2 EA		

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	17 EA		
0057	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	5 EA		
0058	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	224 SF		
0059	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	48 SF		
0060	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	42 SF		
0061	4425000000-N	1125	WARNING FLAG SETS	6 EA		
0062	4430000000-N	1130	DRUMS	20 EA		
0063	4435000000-N	1135	CONES	14 EA		
0064	4445000000-E	1145	BARRICADES (TYPE III)	72 LF		
0065	4450000000-N	1150	FLAGGER	240 HR		
0066	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	1 EA		
0067	4485000000-E	1170	PORTABLE CONCRETE BARRIER	500 LF		
0068	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	80 EA		
0069	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	31,626 LF		
0070	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	40 LF		
0071	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	312 LF		
0072	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	80 EA		
0073	6000000000-E	1605	TEMPORARY SILT FENCE	870 LF		
0074	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	150 TON		

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	710 TON		
0076	6012000000-E	1610	SEDIMENT CONTROL STONE	210 TON		
0077	6015000000-E	1615	TEMPORARY MULCHING	10 ACR		
0078	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	350 LB		
0079	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.5 TON		
0080	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50 LF		
0081	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0082	6030000000-E	1630	SILT EXCAVATION	1,450 CY		
0083	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,750 SY		
0084	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	165 SY		
0085	6042000000-E	1632	1/4" HARDWARE CLOTH	40 LF		
0086	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	55 SY		
0087	6084000000-E	1660	SEEDING & MULCHING	10 ACR		
0088	6087000000-E	1660	MOWING	6 ACR		
0089	6090000000-E	1661	SEED FOR REPAIR SEEDING	100 LB		
0090	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0091	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	250 LB		
0092	6108000000-E	1665	FERTILIZER TOPDRESSING	7.25 TON		
0093	6114000000-N	SP	SPECIALIZED HAND MOWING	1.5 HR		
0094	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0095	6123000000-E	1670	REFORESTATION	0.5 ACR		
0096	7060000000-E	1705	SIGNAL CABLE	670 LF		
0097	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	8 EA		
0098	7264000000-E	1710	MESSENGER CABLE (3/8")	510 LF		
0099	7300000000-E	1715	TRENCHING (UNPAVED)	1,180 LF		
0100	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	7 EA		
0101	7360000000-N	1720	WOOD POLE	6 EA		
0102	7372000000-N	1721	GUY ASSEMBLY	8 EA		
0103	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
0104	7420000000-E	1722	2" RISER WITH WEATHERHEAD	6 EA		
0105	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	1,884 LF		
0106	7456000000-E	1726	LEAD-IN CABLE	2,590 LF		
0107	7684000000-N	1750	SIGNAL CABINET FOUNDATION	1 EA		
0108	7688000000-N	SP	CABINET BASE ADAPTER	1 EA		
0109	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	1 EA		
0110	7780000000-N	SP	DETECTOR CARD (TYPE 2070L)	6 EA		
0124	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (22+61 -L-)	Lump Sum	L.S.	

County : Nash

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>STRUCTURE ITEMS</b>						
0111	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (22+61.00-L-)	Lump Sum	L.S.	
0112	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (22+61.00-L-)	Lump Sum	L.S.	
0113	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (22+61.00-L-)	Lump Sum	L.S.	
0114	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	70.9 CY		
0115	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (22+61.00-L-)	Lump Sum	L.S.	
0116	8217000000-E	425	REINFORCING STEEL (BRIDGE)	12,952 LB		
0117	8364000000-E	450	HP12X53 STEEL PILES	1,870 LF		
0118	8406000000-N	SP	GALVANIZING STEEL PILES AT STA ***** (22+61.00-L-)	Lump Sum	L.S.	
0119	8503000000-E	460	CONCRETE BARRIER RAIL	384.76 LF		
0120	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	134 TON		
0121	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	150 SY		
0122	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0123	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	3,072 LF		

0955/Nov01/Q78265.76/D545566200000/E124

Total Amount Of Bid For Entire Project :

Contract No: C200964  
County: Nash

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General