

SHOULDER CONSTRUCTION

Project: 37427 - MA07115R

Sheet 5A of 8

Begin Station	End Station	Location	Shoulder Construction LF	SHM	Remarks
177+00.00	180+20.00	LT	320	0.06	
177+00.00	179+20.00	RT	220	0.04	
185+50.00	187+50.00	LF	200	0.04	
192+80.00	194+30.00	RT	150	0.03	
209+50.00	211+00.00	LT	150	0.03	
219+75.00	222+75.00	RT	300	0.06	Ditch will have to be moved
342+00.00	344+50.00	RT	250	0.05	Ditch will have to be moved
346+50.00	350+50.00	LT	400	0.08	Ditch will have to be moved
352+75.00	355+75.00	LT	300	0.06	Ditch will have to be moved
358+50.00	361+00.00	RT	250	0.05	Ditch will have to be moved
TOTAL			2,540	0.48	
NOTES: Station 165+00 is at the North side of SR 1129 (Davis Road), stations increase heading North.					