

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200959

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0022000000-E	225	13,600	CY	UNCLASSIFIED EXCAVATION
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+97.50)
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB- BING
0057000000-E	226	700	CY	UNDERCUT EXCAVATION
0063000000-N	SP	Lump Sum		GRADING
0080000000-E	SP	100	TON	CLASS IV SUBGRADE STABILIZA- TION
0196000000-E	270	500	SY	FABRIC FOR SOIL STABILIZATION
0343000000-E	310	148	LF	15" SIDE DRAIN PIPE
0366000000-E	310	84	LF	15" RC PIPE CULVERTS, CLASS III
0708000000-E	310	64	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
0806000000-E	310	2	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK
0995000000-E	340	89	LF	PIPE REMOVAL
0996000000-N	350	1	EA	PIPE CLEAN-OUT
1121000000-E	520	180	TON	AGGREGATE BASE COURSE
1220000000-E	545	100	TON	INCIDENTAL STONE BASE
1275000000-E	600	66	GAL	PRIME COAT
1489000000-E	610	600	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
1525000000-E	SP	400	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A
1560000000-E	620	52	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
2286000000-N	840	3	EA	MASONRY DRAINAGE STRUCTURES
2367000000-N	840	3	EA	FRAME WITH TWO GRATES, STD 840.29
2556000000-E	846	190	LF	SHOULDER BERM GUTTER
3420000000-E	SP	350	LF	GENERIC GUARDRAIL ITEM STEEL BM GUARDRAIL (WEATHERING STEEL)

ItemNumber	Sec #	Quantity	Unit	Description
3435000000-N	SP	5	EA	GENERIC GUARDRAIL ITEM ADDITIONAL GUARDRAIL POSTS (WEATHERING STEEL)
3435000000-N	SP	4	EA	GENERIC GUARDRAIL ITEM GUARDRAIL ANCHOR UNITS, TYPE 350 (WEATHERING STEEL)
3435000000-N	SP	4	EA	GENERIC GUARDRAIL ITEM GUARDRAIL ANCHOR UNITS, TYPE III (WEATHERING STEEL)
3642000000-E	876	250	TON	PLAIN RIP RAP, CLASS A
3649000000-E	876	10	TON	PLAIN RIP RAP, CLASS B
3656000000-E	876	160	SY	FILTER FABRIC FOR DRAINAGE
4400000000-E	1110	192	SF	WORK ZONE SIGNS (STATIONARY)
4410000000-E	1110	57	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
4425000000-N	1125	6	EA	WARNING FLAG SETS
4445000000-E	1145	60	LF	BARRICADES (TYPE III)
4810000000-E	1205	10,200	LF	PAINT PAVEMENT MARKING LINES (4")
4900000000-N	1252	32	EA	PERMANENT RAISED PAVEMENT MARKERS
6000000000-E	1605	550	LF	TEMPORARY SILT FENCE
6006000000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
6009000000-E	1610	450	TON	STONE FOR EROSION CONTROL, CLASS B
6012000000-E	1610	150	TON	SEDIMENT CONTROL STONE
6015000000-E	1615	3	ACR	TEMPORARY MULCHING
6018000000-E	1620	100	LB	SEED FOR TEMPORARY SEEDING
6021000000-E	1620	0.5	TON	FERTILIZER FOR TEMPORARY SEED- ING
6030000000-E	1630	1,050	CY	SILT EXCAVATION
6036000000-E	1631	1,200	SY	MATTING FOR EROSION CONTROL
6042000000-E	1632	75	LF	1/4" HARDWARE CLOTH
6084000000-E	1660	3.5	ACR	SEEDING & MULCHING
6087000000-E	1660	2	ACR	MOWING

ItemNumber	Sec #	Quantity	Unit	Description
6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
6096000000-E	1662	75	LB	SEED FOR SUPPLEMENTAL SEEDING
6108000000-E	1665	3	TON	FERTILIZER TOPDRESSING
6114000000-N	SP	1.5	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL

5/28/99