

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0022000000-E	225	UNCLASSIFIED EXCAVATION	13,600 CY		
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+97.50)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	700 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	100 TON		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0009	0343000000-E	310	15" SIDE DRAIN PIPE	148 LF		
0010	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	84 LF		
0011	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	64 LF		
0012	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0013	0995000000-E	340	PIPE REMOVAL	89 LF		
0014	0996000000-N	350	PIPE CLEAN-OUT	1 EA		
0015	1121000000-E	520	AGGREGATE BASE COURSE	180 TON		
0016	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0017	1275000000-E	600	PRIME COAT	66 GAL		
0018	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	600 TON		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	400 TON		
0020	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	52 TON		
0021	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0022	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
0023	2556000000-E	846	SHOULDER BERM GUTTER	190 LF		
0024	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (350, WEATHERING STEEL)	4 EA		
0025	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (III, WEATHERING STEEL)	4 EA		
0026	3420000000-E	SP	GENERIC GUARDRAIL ITEM STEEL BM GUARDRAIL (WEATHERING STEEL)	350 LF		
0027	3435000000-N	SP	GENERIC GUARDRAIL ITEM ADDITIONAL GUARDRAIL POSTS (WEATHERING STEEL)	5 EA		
0028	3642000000-E	876	PLAIN RIP RAP, CLASS A	250 TON		
0029	3649000000-E	876	PLAIN RIP RAP, CLASS B	10 TON		
0030	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	160 SY		
0031	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	192 SF		
0032	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	57 SF		
0033	4425000000-N	1125	WARNING FLAG SETS	6 EA		
0034	4445000000-E	1145	BARRICADES (TYPE III)	60 LF		
0035	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	10,200 LF		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	32 EA		
0037	6000000000-E	1605	TEMPORARY SILT FENCE	550 LF		
0038	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0039	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	450 TON		
0040	6012000000-E	1610	SEDIMENT CONTROL STONE	150 TON		
0041	6015000000-E	1615	TEMPORARY MULCHING	3 ACR		
0042	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0043	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5 TON		
0044	6030000000-E	1630	SILT EXCAVATION	1,050 CY		
0045	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,200 SY		
0046	6042000000-E	1632	1/4" HARDWARE CLOTH	75 LF		
0047	6084000000-E	1660	SEEDING & MULCHING	3.5 ACR		
0048	6087000000-E	1660	MOWING	2 ACR		
0049	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0050	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0051	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0052	6108000000-E	1665	FERTILIZER TOPDRESSING	3 TON		
0053	6114000000-N	SP	SPECIALIZED HAND MOWING	1.5 HR		
0054	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		

County: Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
0055	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (17+97.50-L-)	Lump Sum	L.S.	
0056	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+97.50-L-)	Lump Sum	L.S.	
0057	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (1, 17+97.50-L-)	Lump Sum	L.S.	
0058	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (2, 17+97.50-L-)	Lump Sum	L.S.	
0059	8096000000-E	SP	PILE EXCAVATION IN SOIL	61 LF		
0060	8097000000-E	SP	PILE EXCAVATION NOT IN SOIL	22 LF		
0061	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	675 CY		
0062	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	4,918 SF		
0063	8161000000-E	420	GROOVING BRIDGE FLOORS	5,472 SF		
0064	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	158 CY		
0065	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+97.50-L-)	Lump Sum	L.S.	
0066	8217000000-E	425	REINFORCING STEEL (BRIDGE)	29,244 LB		
0067	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,560 LB		
0068	8262000000-E	430	45" PRESTRESSED CONCRETE GIR- DERS	635.89 LF		
0069	8364000000-E	450	HP12X53 STEEL PILES	190 LF		
0070	8391000000-N	450	STEEL PILE POINTS	9 EA		
0071	8468000000-E	460	ONE BAR METAL RAIL	309.85 LF		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	8517000000-E	460	1'-***"X ***** CONCRETE PARA-PET (1'-0" X 1'-6")	325.23 LF		
0073	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	515 TON		
0074	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	570 SY		
0075	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0076	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

1308/Oct12/Q76684.72/D362878100000/E76

Total Amount Of Bid For Entire Project :

Contract No: C201318

County: Randolph

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General