



NOTE: USE FABRIC FOR SOIL STABILIZATION IN LIEU OF UNDERCUT AT  
 -RPC- STA.10+00 TO 10+70; PLACE ON NATURAL GROUND TO  
 A DISTANCE OF 0.6m BEYOND EDGE OF PROP. PAVEMENT  
 QUANTITY = 588 SM

MEARLE LOCKLEAR  
 DB 846 PG 788

-L-		-RPB-		-RPC-	
Pi Sta. 10+225.00	Pi Sta. 10+40.005	Pi Sta. 10+40.005	Pi Sta. 10+46.827	Pi Sta. 14+16.858	Pi Sta. 14+16.858
$\Delta = 2' 39" 40.8" (RT)$	$\Delta = 2' 39" 40.8" (RT)$	$\Delta = 2' 39" 40.8" (RT)$	$\Delta = 2' 39" 40.8" (RT)$	$\Delta = 2' 39" 40.8" (RT)$	$\Delta = 2' 39" 40.8" (RT)$
L = 306.897	L = 306.897	L = 306.897	L = 306.897	L = 306.897	L = 306.897
LT = 63.243	LT = 63.243	LT = 63.243	LT = 63.243	LT = 63.243	LT = 63.243
R = 7000.000	R = 7000.000	R = 7000.000	R = 7000.000	R = 7000.000	R = 7000.000
SE = NC	SE = NC	SE = 0.07	SE = 0.07	SE = 0.08	SE = 0.08

NOTE: FOR PROFILE OF -L-, SEE SHEET NO.29 & NO.30  
 FOR PROFILE OF -RPB-, SEE SHEET NO.38  
 FOR PROFILE OF -RPC-, SEE SHEET NO.39 & NO.40