



STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS **SUMMARY OF EARTHWORK**

IN CUBIC METERS

LOCATION	UNCL. EXCAVATION	UNDERCUT	EMBT +%	BORROW	WASTE
SUMMARY NO.1					
-L- 85+80 TO 86+54	0		16104	16104	
-SR3- 25+82 TO 26+37	0	425	2495	2495	425
-L- 86+54 TO 95+54	18		111524	111506	
SUMMARY NO. 1 TOTAL:	18	425	130123	130105	425
SUMMARY NO.2					
-L- 95+54 TO 104+54	0		83874	83874	
SUMMARY NO. 2 TOTAL:	0		83874	83874	
SUMMARY NO.3					
-L- 104+54 TO 113+54(BRID)	4		313055	313051	
-RBY1- 12+05 TO 15+00	526		10457	9931	
-LBY1- 11+05 TO 11+68	0		6828	6828	
-RCY1- 12+51 TO 18+85	596		36309	35713	
-LCY1- 11+20 TO 12+82	0		17773	17773	
-Y1- 11+80 TO 20+10	2307		8615	6308	
-SR4- 9+95 TO 12+90	0	1633	5998	5998	1633
SUMMARY NO. 3 TOTAL:	3433	1633	399035	395602	1633
SUMMARY NO.4					
-L- 114+13.618(BRID) TO 123+13.62	0		316602	316602	
-SR1- 10+00 TO 21+94.54	175		46709	46534	
-SR2- 10+00 TO 18+46.43	465		64948	64483	
SUMMARY NO. 4 TOTAL:	640		428259	427619	
SUMMARY NO. 5					
-L- 123+13.62 TO 132+13.62	3843		116184	112341	
-SR1- 21+94.54 TO 31+08.16	0		27335	27335	
-SR2- 18+46.43 TO 21+01.34	264		2604	2340	
SUMMARY NO. 5 TOTAL:	4107		146123	142016	
SUMMARY NO.6					
-L- 132+13.62 TO 138+09.82(BRID)	616		413795	413179	
PER GEOTECH REC. 7/23/04					
-L- 137+73.50 TO 138+21.50	0		1800	1800	
-SR1- 31+08.16 TO 31+50.39	0		909	909	
SUMMARY NO. 6 TOTAL:	616		416504	415888	
SUMMARY NO.7					
-L- 138+60.823(BRID) TO 147+60.82	140		441775	441635	
PER GEOTECH REC. 7/23/04					
-L- 138+41 TO 138+89	0		1800	1800	
SUMMARY NO. 7 TOTAL:	140		443575	443435	

IN CUBIC METERS

LOCATION	UNCL. EXCAVATION	UNDERCUT	EMBT +%	BORROW	WASTE
SUMMARY NO.8					
-L- 147+60.82 TO 153+80	1376		53067	51691	
SUMMARY NO. 8 TOTAL:	1376		53067	51691	
SUMMARIES SUBTOTAL					
	10330	2058	2100560	2090230	2058
PER GEOTECH REC. 7/23/04					
-L- 137+73 TO 138+21	2900				2900
-L- 138+41 TO 138+89					
SHOULDER CONSTRUCTION					
ADDITIONAL UNDERCUT					
		2000	2500	2500	2000
SELECT MAT'L IN LIEU OF BORROW					
				-41000	
SELECT MAT'L IN LIEU OF BORROW					
				-11000	
PER GEOTECH REC. 7/23/04					
USE WASTE IN LIEU OF BORROW					
				-2900	-2900
TOTAL	13230	4058	2169579	2104349	4058
5% - REPL. TOPSOIL - BORROW PITS					
				105218	
GRAND TOTAL					
	13230	4058	2169579	2209567	4058
SAY					
	13300			2210000	
DDE					
	22739				