

DETAIL FOR ALTERNATE "B"

GENERAL NOTES


SLOPE PROTECTION SHALL BE PLACED UNDER THE ENDS OF THE BRIDGE AS SHOWN IN THE DETAILS. METHOD OF MEASUREMENT AND BASIS OF PAYMENT SHALL BE AS PRESCRIBED IN SECTION 462 OF THE STANDARD SPECIFICATIONS. FOR BERM WIDTH, SEE GENERAL DRAWING.

ALTERNATE "B"

ALTERNATE "B" SHALL CONSIST OF STONE SLOPE PROTECTION, FILTER FABRIC AND 8" OF STONE SHALL BE PLACED OVER THE AREA SHOWN ON THE PLANS TO BE COVERED WITH SLOPE PROTECTION. THE COST OF THE FILTER FABRIC AND STONE, SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE BID PER SQUARE YARD FOR 8" SLOPE PROTECTION. SUBGRADING, STONE TYPE, STONE SIZING, AND HERBICIDE PROTECTION, SHALL BE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS EXCEPT THE HERBICIDE TYPE SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL PRIOR TO APPLICATION.

BRIDGE @ STA. 28+95.00 -SBL-	8 INCH SLOPE PROTECTION	FILTER FABRIC
	SQUARE YARDS	SQUARE YARDS
END BENT 2	68	68

PROJECT NO. I-4025A
 YADKIN-SURRY COUNTY
 STATION: 28+95.00 -SBL-



STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

**SLOPE PROTECTION
 DETAILS
 END BENT 2**

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	TOTAL SHEETS
1			3			5-73
2			4			78

DRAWN BY: A.S. CALLAWAY DATE: 4/9/04
 CHECKED BY: B.N. BARODAWALA DATE: 8/24/04