

SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201210

ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION	2132000000-N	816	11	EA	CONCRETE PAD FOR SHOULDER DRAIN PIPE OUTLET	4847110000-E	SP	467	LF	POLYUREA PAVEMENT MARKING LINES (8")
0000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING	2209000000-E	838	3	CY	ENDWALLS	4850000000-E	1205	5,405	LF	REMOVAL OF PAVEMENT MARKING LINES (4")
0022000000-E	225	37,300	CY	UNCLASSIFIED EXCAVATION	2253000000-E	840	2	CY	PIPE COLLARS	4875000000-N	1205	3	EA	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (28+95.000)	2286000000-N	840	13	EA	MASONRY DRAINAGE STRUCTURES	4880000000-E	1205	10,377	LF	CURING COMPOUND REMOVAL, LINES
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING	2308000000-E	840	9	LF	MASONRY DRAINAGE STRUCTURES	4885000000-N	1205	3	EA	CURING COMPOUND REMOVAL, SYMBOLS & CHARACTERS
0057000000-E	226	1,000	CY	UNDERCUT EXCAVATION	2364200000-N	840	1	EA	FRAME WITH TWO GRATES, STD 840.20	4900000000-N	1252	20	EA	PERMANENT RAISED PAVEMENT MARKERS
0063000000-N	SP	Lump Sum		GRADING	2365000000-N	840	7	EA	FRAME WITH TWO GRATES, STD 840.22	4905000000-N	1253	80	EA	SNOWPLOWABLE RAISED PAVEMENT MARKERS
0080000000-E	SP	420	TON	CLASS IV SUBGRADE STABILIZATION	2407000000-N	840	4	EA	STEEL FRAME WITH TWO GRATES, STD 840.37	6000000000-E	1605	1,100	LF	TEMPORARY SILT FENCE
0134000000-E	240	2	CY	DRAINAGE DITCH EXCAVATION	2484000000-E	SP	140	LF	GENERIC DRAINAGE ITEM SLOTTED DRAIN, 15" CS SLOTTED DRAIN, 0.064" THICK	6006000000-E	1610	200	TON	STONE FOR EROSION CONTROL, CLASS A
0141000000-E	240	225	LF	BERM DITCH CONSTRUCTION	2556000000-E	846	710	LF	SHOULDER BERM GUTTER	6009000000-E	1610	600	TON	STONE FOR EROSION CONTROL, CLASS B
0192000000-N	260	3	HR	PROOF ROLLING	2570000000-N	SP	2	EA	MODIFIED CONCRETE FLUME	6012000000-E	1610	1,620	TON	SEDIMENT CONTROL STONE
0195000000-E	265	250	CY	SELECT GRANULAR MATERIAL	2619000000-E	850	50	SY	4" CONCRETE PAVED DITCH	6015000000-E	1615	6	ACR	TEMPORARY MULCHING
0196000000-E	270	1,500	SY	FABRIC FOR SOIL STABILIZATION	3030000000-E	862	1,075	LF	STEEL BM GUARDRAIL	6018000000-E	1620	200	LB	SEED FOR TEMPORARY SEEDING
0199000000-E	SP	7,000	SF	TEMPORARY SHORING	3150000000-N	862	10	EA	ADDITIONAL GUARDRAIL POSTS	6021000000-E	1620	1	TON	FERTILIZER FOR TEMPORARY SEEDING
0206000000-E	SP	2,000	SF	TEMPORARY SHORING - BARRIER SUPPORTED	3180000000-N	862	2	EA	GUARDRAIL ANCHOR UNITS, TYPE ***** (WBEAM)	6024000000-E	1622	100	LF	TEMPORARY SLOPE DRAINS
0318000000-E	300	155	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	3210000000-N	862	1	EA	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	6027000000-N	1622	1	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
0366000000-E	310	492	LF	15" RC PIPE CULVERTS, CLASS III	3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III	6030000000-E	1630	3,200	CY	SILT EXCAVATION
0372000000-E	310	108	LF	18" RC PIPE CULVERTS, CLASS III	3270000000-N	SP	1	EA	GUARDRAIL ANCHOR UNITS, TYPE 350	6036000000-E	1631	3,600	SY	MATTING FOR EROSION CONTROL
0378000000-E	310	24	LF	24" RC PIPE CULVERTS, CLASS III	3285000000-N	SP	2	EA	GUARDRAIL ANCHOR UNITS, TYPE M-350	6042000000-E	1632	640	LF	1/4" HARDWARE CLOTH
0582000000-E	310	316	LF	15" CS PIPE CULVERTS, 0.064" THICK	3360000000-E	863	1,194	LF	REMOVE EXISTING GUARDRAIL	6070000000-N	SP	40	EA	SPECIAL STILLING BASINS
0588000000-E	310	84	LF	18" CS PIPE CULVERTS, 0.064" THICK	3503000000-E	866	910	LF	WOVEN WIRE FENCE, 47" FABRIC	6084000000-E	1660	7.5	ACR	SEEDING & MULCHING
0594000000-E	310	400	LF	24" CS PIPE CULVERTS, 0.064" THICK	3509000000-E	866	55	EA	4" TIMBER FENCE POSTS, 7'-6" LONG	6087000000-E	1660	3.5	ACR	MOWING
0806000000-E	310	2	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	3515000000-E	866	30	EA	5" TIMBER FENCE POSTS, 8'-0" LONG	6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
0808000000-E	310	2	EA	24" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	3570000000-E	866	100	LF	ADDITIONAL BARBED WIRE	6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
0995000000-E	340	192	LF	PIPE REMOVAL	3628000000-E	876	35	TON	PLAIN RIP RAP, CLASS I	6096000000-E	1662	150	LB	SEED FOR SUPPLEMENTAL SEEDING
1220000000-E	545	75	TON	INCIDENTAL STONE BASE	3649000000-E	876	3	TON	PLAIN RIP RAP, CLASS B	6108000000-E	1665	5.5	TON	FERTILIZER TOPDRESSING
1489000000-E	610	1,460	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	3656000000-E	876	2,200	SY	FILTER FABRIC FOR DRAINAGE	6109000000-E	SP	0.15	ACR	SPECIALIZED SEEDING UNDER GUIDERAIL & GUARDRAIL (HARD FESCUE/BLUEGRASS)
1491000000-E	610	3,370	TON	ASPHALT CONC BASE COURSE, TYPE B25.0C	4400000000-E	1110	1,174	SF	WORK ZONE SIGNS (STATIONARY)	6114000000-N	SP	3	HR	SPECIALIZED HAND MOWING
1503000000-E	610	970	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	4405000000-E	1110	553	SF	WORK ZONE SIGNS (PORTABLE)	6117000000-N	1675	16	EA	RESPONSE FOR EROSION CONTROL
1519000000-E	610	540	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	4410000000-E	1110	20	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)					
1523000000-E	610	940	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	4415000000-N	1115	3	EA	FLASHING ARROW PANELS, TYPE C					
1560000000-E	620	289	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	4420000000-N	1120	2	EA	CHANGEABLE MESSAGE SIGNS					
1565000000-E	620	62	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	4430000000-N	1130	150	EA	DRUMS					
1840000000-E	665	4,190	LF	MILLED RUMBLE STRIPS	4435000000-N	1135	20	EA	CONES					
1847000000-E	710	7,100	SY	***** PORT CEM CONC PAVEMENT, THROUGH LANES (WITH DOWELS) (13")	4445000000-E	1145	24	LF	BARRICADES (TYPE III)					
1902000000-N	710	Lump Sum		SURFACE TESTING CONCRETE PAVEMENT	4450000000-N	1150	1,200	HR	FLAGGER					
1924000000-N	725	Lump Sum		FIELD LABORATORY RENTAL, PORT CEM CONC PAVEMENT	4460000000-N	1155	6	EA	WARNING LIGHTS (TYPE B)					
2022000000-E	815	70	CY	SUBDRAIN EXCAVATION	4465000000-N	1160	4	EA	TEMPORARY CRASH CUSHIONS					
2033000000-E	815	35	CY	SUBDRAIN FINE AGGREGATE	4480000000-N	1165	2	EA	TRUCK MOUNTED IMPACT ATTENUATOR (60 MPH)					
2044000000-E	815	200	LF	6" PERFORATED SUBDRAIN PIPE	4485000000-E	1170	3,650	LF	PORTABLE CONCRETE BARRIER					
2055000000-E	815	6	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	4490000000-E	1170	950	LF	PORTABLE CONCRETE BARRIER (ANCHORED)					
2066000000-N	815	1	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	4495000000-E	1170	405	LF	PORTABLE CONCRETE BARRIER (DRAINAGE)					
2077000000-E	815	6	LF	6" OUTLET PIPE (SUBDRAINS)	4615000000-E	1205	13,410	LF	REMOVABLE TAPE PAVEMENT MARKING LINES (4")					
2099000000-E	816	3,550	LF	SHOULDER DRAIN	4645000000-N	1205	6	EA	REMOVABLE TAPE PAVEMENT MARKING SYMBOL					
2110000000-E	816	3,550	LF	4" SHOULDER DRAIN PIPE	4650000000-N	1251	1,000	EA	TEMPORARY RAISED PAVEMENT MARKERS					
2121000000-E	816	500	LF	4" OUTLET PIPE (SHOULDER DRAINS)	4805000000-N	1205	3	EA	COLD APPLIED PLASTIC PAVEMENT MARKING SYMBOL					
					4810000000-E	1205	8,550	LF	PAINT PAVEMENT MARKING LINES (4")					
					4847000000-E	SP	9,910	LF	POLYUREA PAVEMENT MARKING LINES (4")					

04/07/2004 P:\Roadway\Proc\14025a_3series.dgn K & Associates, P.C.