



NOTE:
 FOR UTILITY INFORMATION, SEE
 UTILITY PLANS AND SPECIAL PROVISIONS.

TOTAL BILL OF MATERIAL

	CONSTRUCTION, MAINTENANCE & REMOVAL OF TEMPORARY ACCESS	REMOVAL OF EXISTING STRUCTURE	3'-6" Ø DRILLED PIERS IN SOIL	3'-6" Ø DRILLED PIERS NOT IN SOIL	PERMANENT STEEL CASING FOR 3'-6" Ø DRILLED PIER	CROSSHOLE SONIC LOGGING	CSL TUBES	UNCLASSIFIED STRUCTURE EXCAVATION	REINFORCED CONCRETE DECK SLAB	GROOVING BRIDGE FLOORS	CLASS A CONCRETE	BRIDGE APPROACH SLABS	REINFORCING STEEL	SPIRAL COLUMN REINFORCING STEEL	45" PRESTRESSED CONCRETE GIRDERS	HP 12 X 53 STEEL PILES	STEEL PILE POINTS	CONCRETE BARRIER RAIL	PLAIN RIP RAP CLASS II (2'-0" THICK)	FILTER FABRIC FOR DRAINAGE	ELASTOMERIC BEARINGS	EVAZOTE JOINT SEALS		
	LUMP SUM	LUMP SUM	LIN. FT.	LIN. FT.	LIN. FT.	EACH	LIN. FT.	LUMP SUM	SQ. FT.	SQ. FT.	CU. YDS.	LUMP SUM	LBS.	LBS.	No.	LIN. FT.	No.	LIN. FT.	EACH	LIN. FT.	TONS	SQ.YDS.	LUMP SUM	LUMP SUM
SUPERSTRUCTURE									4,150	4,819		LUMP SUM			12	520.17			265.63			LUMP SUM	LUMP SUM	
END BENT No. 1											21.6		3,240			6	90	6			415	461		
BENT No. 1			24.00	20.00	28.00	1	196.00				17.2		5,468	1,258										
BENT No. 2			15.00	19.00	20.00		156.00				19.9		5,454	1,261										
END BENT No. 2											21.3		3,314			6	90	6			575	639		
TOTAL	LUMP SUM	LUMP SUM	39.00	39.00	48.00	1	352.00	LUMP SUM	4,150	4,819	80.0	LUMP SUM	17,476	2,519	12	520.17	12	180	12	265.63	990	1,100	LUMP SUM	LUMP SUM

PROJECT NO. B-3403
ALLEGHANY COUNTY
 STATION: 15+17.50 -L-

SHEET 3 OF 3



STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH

GENERAL DRAWING
 BRIDGE ON
 SR 1422 (FOX RIDGE RD.)
 OVER BRUSH CREEK
 BETWEEN SR 1433 AND SR 1453

DRAWN BY: MIKE BRITT DATE: 8-18-04
 CHECKED BY: B.N. GRADY DATE: 9-04

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-3
1			3			TOTAL SHEETS
2			4			34