

STATE OF NORTH CAROLINA
 DIVISION OF HIGHWAYS
SUMMARY OF EARTHWORK

IN CUBIC YARDS

LOCATION	UNCL. EXCAVATION	UNDERCUT	EMBT + %	BORROW	WASTE
SUMMARY #1					
-L- 10+75 TO 14+50.00 (BRIDGE)	10	0	2315	2305	0
TOTAL SUMMARY #1	10	0	2315	2305	0
SUMMARY #2					
-L- 15+85 (BRIDGE) TO 22+39.73	2014	0	6343	4329	0
TOTAL SUMMARY #2	2014	0	6343	4329	0
SUBTOTAL SUMMARY #1 & #2	2024	0	8658	6634	0
PROJECT TOTALS	2024	0	8658	6634	0
LOSS DUE TO CLEARING & GRUBBING	-100	0	0	100	0
PROJECT TOTALS	1924	0	8658	6734	0
EST. 5% TO REPLACE TOPSOIL	0	0	0	337	0
GRAND TOTALS	1924	0	8658	7071	0
SAY	2000			7100	
UNDERCUT	500				
DDE	30				

-L- PAVEMENT STRUCTURE VOLUME = 11 CY

NOTE: APPROXIMATE QUANTITIES ONLY. UNCLASSIFIED EXCAVATION, FINE GRADING, CLEARING AND GRUBBING, BREAKING OF EXISTING PAVEMENT AND REMOVAL OF EXISTING PAVEMENT WILL BE PAID FOR AT THE CONTRACT LUMP SUM PRICE FOR "GRADING".

SUMMARY OF PAVEMENT REMOVAL

LINE	STATION TO STATION		LOC LT/RT/CL	ASPHALT REMOVAL SY	ASPHALT BREAK-UP SY
L	12+25.00	12+75.00	CL	97	
L	12+75.00	14+39.00	LT		319
L	14+39.00	14+92.00	LT	103	
L	15+72.00	15+96.00	LT	47	
L	15+96.00	20+75.00	LT		931
L	20+75.00	21+25.00	CL	97	
			TOTAL:	344	1250
			SAY:	350	1250

REVISIONS