

County : Alleghany

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (15+17.50)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	500 TON		
0008	0106000000-E	230	BORROW EXCAVATION	7,100 CY		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	30 CY		
0010	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0011	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	50 TON		
0013	0344000000-E	310	18" SIDE DRAIN PIPE	24 LF		
0014	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	264 LF		
0015	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	56 LF		
0016	0720000000-E	310	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	80 LF		
0017	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0018	0995000000-E	340	PIPE REMOVAL	90 LF		

County : Alleghany

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0996000000-N	350	PIPE CLEAN-OUT	1 EA		
0020	1121000000-E	520	AGGREGATE BASE COURSE	220 TON		
0021	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0022	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	650 TON		
0023	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	350 TON		
0024	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	51 TON		
0025	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	50 TON		
0026	2000000000-N	806	RIGHT OF WAY MARKERS	18 EA		
0027	2022000000-E	815	SUBDRAIN EXCAVATION	134 CY		
0028	2033000000-E	815	SUBDRAIN FINE AGGREGATE	101 CY		
0029	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	600 LF		
0030	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	18 EA		
0031	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
0032	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		
0033	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	6 EA		
0034	2363000000-N	840	FRAME WITH TWO GRATES, STD 840.***** (840.33)	4 EA		
0035	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	2 EA		
0036	2556000000-E	846	SHOULDER BERM GUTTER	60 LF		
0037	3030000000-E	862	STEEL BM GUARDRAIL	700 LF		

County : Alleghany

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0039	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0040	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0041	3559000000-E	866	** STRAND BARBED WIRE FENCE WITH POSTS (4)	1,740 LF		
0042	3649000000-E	876	PLAIN RIP RAP, CLASS B	250 TON		
0043	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,190 SY		
0044	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	3 EA		
0045	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	305 SF		
0046	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0047	4425000000-N	1125	WARNING FLAG SETS	4 EA		
0048	4430000000-N	1130	DRUMS	25 EA		
0049	4435000000-N	1135	CONES	25 EA		
0050	4445000000-E	1145	BARRICADES (TYPE III)	96 LF		
0051	4450000000-N	1150	FLAGGER	24 HR		
0052	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	9,320 LF		
0053	6000000000-E	1605	TEMPORARY SILT FENCE	500 LF		
0054	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0055	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	280 TON		
0056	6012000000-E	1610	SEDIMENT CONTROL STONE	280 TON		

County : Alleghany

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6015000000-E	1615	TEMPORARY MULCHING	3 ACR		
0058	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0059	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5 TON		
0060	6024000000-E	1622	TEMPORARY SLOPE DRAINS	90 LF		
0061	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
0062	6029000000-E	SP	SAFETY FENCE	250 LF		
0063	6030000000-E	1630	SILT EXCAVATION	795 CY		
0064	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,330 SY		
0065	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	260 SY		
0066	6042000000-E	1632	1/4" HARDWARE CLOTH	120 LF		
0067	6070000000-N	SP	SPECIAL STILLING BASINS	8 EA		
0068	6084000000-E	1660	SEEDING & MULCHING	3.5 ACR		
0069	6087000000-E	1660	MOWING	2 ACR		
0070	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0071	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0072	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0073	6108000000-E	1665	FERTILIZER TOPDRESSING	2.5 TON		
0074	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0075	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		

County : Alleghany

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
0076	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (15+17.50-L-)	Lump Sum	L.S.	
0077	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+17.50-L-)	Lump Sum	L.S.	
0078	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SO IL	39 LF		
0079	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	39 LF		
0080	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	48 LF		
0081	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0082	8116000000-E	SP	CSL TUBES	352 LF		
0083	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (15+17.50-L-)	Lump Sum	L.S.	
0084	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	4,150 SF		
0085	8161000000-E	420	GROOVING BRIDGE FLOORS	4,819 SF		
0086	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	80 CY		
0087	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15+17.50-L-)	Lump Sum	L.S.	
0088	8217000000-E	425	REINFORCING STEEL (BRIDGE)	17,476 LB		
0089	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,519 LB		
0090	8262000000-E	430	45" PRESTRESSED CONCRETE GIR- DERS	520.17 LF		
0091	8364000000-E	450	HP12X53 STEEL PILES	180 LF		
0092	8391000000-N	450	STEEL PILE POINTS	12 EA		

County : Alleghany

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0093	8503000000-E	460	CONCRETE BARRIER RAIL	265.63 LF		
0094	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	990 TON		
0095	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	1,100 SY		
0096	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0097	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
1414/Nov10/Q62656.55/D422765080000/E97			Total Amount Of Bid For Entire Project :			

C200956 (B-3403)
ALLEGHANY CO.

2/16/99

Contract No: C200956

County: Alleghany

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General