042597

METRIC	PROJECT REFERENCE NO.	SHEET NO.
5 0 10 SCALE	R-2562C	UC-23
	DESIGNED BY: CSG	
	DRAWN BY: CSG	
	CHECKED BY:	
	APPROVED BY:	
	REVISED:	
NORTH CAROLINA DEPARTMENT OF TRANSPORTATION		
DESIGN SERVICES UNIT PHONE:(919)250-4128 FAX:(919)250-4119		UTILITY CONSTRUCTION PLANS ONLY

NORTH CAROLINA SEAL 10157 ENGINEER DONALD B. WILKINS 10/11/04

UTILITY CONSTRUCTION

NC GRID NAD '83

70 KENNETH ROBERT WILLIS AND WIFE
KATHY LOUISE WILLIS
DB 293 PG 828

PROP. 1-RELOCATE EXISTING WATER METER
PROP. 24M-20MM PE WATER TUBING, SDR 9, 1.38 MPA WP

72 JOSEPH WALTER BRYAN AND WIFE
CECEILE K. BRYAN
DB 166 PG 120

ABANDON

74 DANIEL BRANTLEY WILLIS, JR AND WIFE
DEBORAH W. WILLIS
DB 242 PG 741

POT STA. 173+26.257 -L- REV.=
POT STA. 10+00.000 -Y6-

73 JOSEPH WALTER BRYAN AND WIFE
CECEILE K. BRYAN
DB 251 PG 450

71 EDNA W. CANADY
DB 270 PG 634

75 DAVID ELBERT WILLIS
DB 242 PG 738

DAVID ELBERT WILLIS
DB 242 PG 738
76

CLYDE BALDWIN SUGGS
DB 302 PG 063
77

PROP. 252M-200MM PVC WATER PIPE, SDR 21, 1.38 MPA WP
PROP. 4-200MM 45° DI BENDS
PROP. 1-200MM GATE VALVE & VALVE BOX, 1.38 MPA WP
PROP. 1 RELOCATE EXISTING FIRE HYDRANT
PROP. 1-150MM GATE VALVE & VALVE BOX, 1.38 MPA WP
PROP. 1-150MM 45° DI BEND
PROP. 1-200MM X 150MM DI TEE
PROP. 16M-150MM DI WATER PIPE, PC. 2.41
PROP. 1-RELOCATE EXISTING WATER METER
PROP. 1-200MM X 20MM TAPPING SADDLE
PROP. 1-20MM CORPORATION STOP
PROP. 5M-20MM PE WATER TUBING, SDR 9, 1.38 MPA WP

END CONSTRUCTION
POT STA. 10+70.000 -Y6-

MATCH LINE -L- REV. STA. 170+11 SHEET UC-22

MATCH LINE -L- REV. STA. 173+51 SHEET UC-24

SEE SHEET 25B FOR -Y6- INTERSECTION DETAIL
SEE SHEET 43 FOR -L- REV. PROFILE
SEE SHEET 47 FOR -Y6- PROFILE

11-OCT-2004 09:11
spoon
R:\U\Utility Plans\Proj\UC23023.pah