042457

METRIC	PROJECT REFERENCE NO.	SHEET NO.
5 0 10 SCALE	R-2562C	UC-11
	DESIGNED BY: CSG	
	DRAWN BY: CSG	
	CHECKED BY:	
	APPROVED BY:	
	REVISED:	
	NORTH CAROLINA DEPARTMENT OF TRANSPORTATION	
	DESIGN SERVICES UNIT PHONE:(919)250-4128 FAX:(919)250-4119	UTILITY CONSTRUCTION PLANS ONLY

NORTH CAROLINA SEAL 10157 ENGINEER DAVID B. WILKINS 10/11/04

UTILITY CONSTRUCTION

NC GRID NAD 83

(33) WHITE C. PHARR, JR. DB 223 PG 16

(36) JAMES L. ALLEN, JR. & WIFE CYNTHIA JANE ALLEN DB 311 PG 39

(37) JAMES L. ALLEN DB 292 PG 863

(35) DANNY R. & WIFE JAMIE M. BOWEN DB 398 PG 632

ABANDON

MATCH LINE -L- REV. STA. 129+40 SHEET UC-10

MATCH LINE -L- REV. STA. 132+15 SHEET UC-12

130+00 131+00 132+00

PROP.06 PAVED SHLD. PROP.12 PAVED SHLD. PROP. DRIVE PROP.R/W EXIST R/W

PROPOSED SPECIAL DITCH SEE DETAIL A

PROPOSED SPECIAL DITCH SEE DETAIL N

+20.000 -L- REV 27m (88.582')

+05.000 -L- REV 26.22m (86.027')

+80.000 -L- REV 32m (104.987')

+65.766 S 42° 00' 44.8" E -L- REV -70.0 R

+47.000 S 42° 00' 44.8" E -L-

+49.000 -2.0 R

+36.86

2GI TYPE D

2GI TYPE A

FALSE SUMP

60' TAPER

NC HWY 87 7.2 BST

3.0 BST

3.2 SOIL

SURVEY -BL-

S 41° 57' 33.3" E

S 41° 57' 28.2" E

REMOVE 375 mm CONC

REMOVE (2)TV&TV(FO)

REMOVE 200 mm

REMOVE 100 mm

PINCL 37+15.258 BL-37

KUPCHOS PLACE

AMES CUB LN

ISBKD

CONC

NO ADDITIONAL RECORD INFORMATION AVAILABLE FOR THE GAS SERVICE AT THIS LOCATION.

NO ADDITIONAL RECORD INFORMATION AVAILABLE FOR THE TELE LINE AT THIS LOCATION.

NO ASSOCIATED WPNG FOUND OR THIS WM.

NO ADDITIONAL RECORD INFORMATION AVAILABLE FOR THE GAS SERVICES AT THESE LOCATIONS.

GAS REG. STA.

CLASS 'B' RIP RAP EST. 0.9 TONS W/ 4.2 SQ.m F.F.

CLASS 'B' RIP RAP EST. 2.7 TONS W/ 9.2 SQ.m F.F.

(34) JANICE SHAW PHARR DB 119 PG 497

(93) GURNEY F. ALLEN SR. & WIFE DORIS B. ALLEN DB 283 PG 725

(94) GURNEY F. ALLEN SR. & WIFE DORIS B. ALLEN DB 212 PG 320

GURNEY F. ALLEN SR. & WIFE DORIS B. ALLEN DB 146 PG 793

PROP. 302M-200MM PVC WATER PIPE, SDR21, 1.38 MPA WP
PROP. 1-200MM GATE VALVE & VALVE BOX, 1.38 MPA WP
PROP. 1-RELOCATE EXIST. FIRE HYDRANT
PROP. 1-150MM GATE VALVE & VALVE BOX, 1.38 MPA WP
PROP. 4M-150MM DI WATER PIPE, PC 350
PROP. 1-RELOCATE EXISTING WATER METER
PROP. 38M-20MM PE WATER TUBING, SDR 9, 1.38 MPA WP
PROP. 1-200MM X 20MM TAPPING SADDLE
PROP. 1-20MM CORPORATION STOP

SEE SHEET 37 FOR -L- REV. PROFILE

11-OCT-2004 08:39
R:\Utilities\Projects\Proj\UC1101.psh
sgoodson 41.5527935