S:\Roadway\R-2562c\CADD\earthwork\log\main1lt.txt

PROJ. REFERENCE NO.	SHEET NO.
R-2562C	X-0 (4 OF 4)

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
CROSS-SECTION SUMMARY

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

Station Main4L (rt)	Uncl. Exc. (cu. meters)	Embt (cu. meters)
184+00.000	0	145
184+20.000	25	182
184+40.000	41	233
184+60.000	28	248
184+80.000	13	230
185+00.000	1	171
185+20.000	6	106
185+40.000	20	70
185+60.000	34	55
185+80.000	41	53
186+00.000	38	45
186+41.594	28	33

Station Main5 (lt)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
186+46.994	214	37
186+80.000	203	67
187+00.000	209	61
187+20.000	222	57
187+40.000	235	51
187+60.000	238	48
187+80.000	231	44
188+00.000	210	37
188+20.000	169	41
188+40.000	131	44
188+60.000	108	47
188+80.000	78	38
189+00.000	84	12
189+20.000	115	0
189+40.000	118	0
189+60.000	101	0
189+80.000	81	0
190+00.000	66	1

Station Main5 (rt)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
186+46.994	28	33
186+80.000	30	17
187+00.000	43	8
187+20.000	71	3
187+40.000	113	1
187+60.000	101	3
187+80.000	56	6
188+00.000	44	8
188+20.000	43	13
188+40.000	47	23
188+60.000	54	29
188+80.000	62	22

Station Main5 (rt)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
189+00.000	86	8
189+20.000	98	0
189+40.000	100	0
189+60.000	112	0
189+80.000	109	0
190+00.000	107	0

Station Y2Rev (lt)	Uncl. Exc. (cu. meters)	Embt (cu. meters)
10+14.000	0	0
10+40.000	150	0
10+60.000	68	0
10+80.000	28	0
11+00.000	43	0
11+20.000	36	0
11+40.000	30	0
11+50.000	23	0

Station Y2Rev (rt)	Uncl. Exc. (cu. meters)	Embt (cu. meters)
10+14.000	0	0
10+40.000	125	2
10+60.000	34	2
10+75.000	5	0

Station Y3 (lt)	Uncl. Exc. (cu. meters)	Embt (cu. meters)
10+14.400	0	0
10+40.000	46	0
10+71.190	56	0

Station Y3 (rt)	Uncl. Exc. (cu. meters)	Embt (cu. meters)
10+14.400	0	0
10+40.000	27	16
10+71.190	51	1

Station Y4 (lt)	Uncl. Exc. (cu. meters)	Embt (cu. meters)
10+14.500	0	0
10+80.000	0	308

Station Y4 (rt)	Uncl. Exc. (cu. meters)	Embt (cu. meters)
10+14.500	0	0
10+40.000	3	4
10+60.000	31	3
10+80.000	43	0

Station Y5 (lt)	Uncl. Exc. (cu. meters)	Embt (cu. meters)
10+14.200	0	0
10+40.000	60	95
10+75.456	102	6

Station Y5 (rt)	Uncl. Exc. (cu. meters)	Embt (cu. meters)
10+14.200	0	0
10+40.000	5	114
10+75.456	21	0

Station Y6 (lt)	Uncl. Exc. (cu. meters)	Embt (cu. meters)
10+14.600	0	0
10+70.000	17	0

Station Y6 (rt)	Uncl. Exc. (cu. meters)	Embt (cu. meters)
10+14.600	0	0
10+70.000	38	0

Station Y7 (lt)	Uncl. Exc. (cu. meters)	Embt (cu. meters)
10+09.200	0	0
10+55.452	22	0

Station Y7 (rt)	Uncl. Exc. (cu. meters)	Embt (cu. meters)
10+09.200	0	0
10+55.452	48	0

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.