

04257

METRIC
SCALE

NTS









PROJECT REFERENCE NO. **R-2562D**
SHEET NO. **UC-23**

DESIGNED BY: **MRB**
DRAWN BY: **MRB**
CHECKED BY: **RBW**
APPROVED BY: **RBW**
REVISED:

NORTH CAROLINA PROFESSIONAL ENGINEER
10157
RODOLPH B. WILKINS

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DESIGN SERVICES UNIT
PHONE: (919) 250-4128
FAX: (919) 250-4119

UTILITY CONSTRUCTION PLANS ONLY



MAXIMUM TRENCH WIDTH AT TOP OF PIPE

NOMINAL PIPE SIZE (mm)	TRENCH WIDTH (meters)	NOMINAL PIPE SIZE (mm)	TRENCH WIDTH (meters)
102	0.72	508	1.12
152	0.76	610	1.22
203	0.81	762	1.37
254	0.86	914	1.57
305	0.91	1067	1.68
356	0.97	1219	1.83
406	1.02	1400	1.98
457	1.07		

30-AUG-2004 08:00 R-2562D_UC22-ut-ut-49p
mbr:rbw