

R:\Roadway\Estimate\Final\earthwork\l1_left_ew.log

**STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS**

PROJ. REFERENCE NO.	SHEET NO.
R-2562D	X-0C

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt
L3	(cu. meters)	(cu. meters)	L4	(cu. meters)	(cu. meters)	L4	(cu. meters)	(cu. meters)	Y2	(cu. meters)	(cu. meters)	Y6A	(cu. meters)	(cu. meters)	Y13	(cu. meters)	(cu. meters)
26+40.000	0	428	35+20.000	103	0	38+80.000	123	16	10+20.000	0	0	10+80.000	25	0	10+20.000	0	0
26+60.000	0	520	35+40.000	195	1	39+00.000	111	8	10+40.000	54	138				10+40.000	15	4
26+80.000	0	536	35+60.000	228	2	39+20.000	123	6	10+60.000	80	75	Station	Uncl. Exc.	Embt	10+60.000	20	0
27+00.000	0	405	35+80.000	247	5	39+40.000	121	15	10+80.000	36	8	Y7	(cu. meters)	(cu. meters)			
27+20.000	0	287	36+00.000	241	6	39+60.000	98	49	11+00.000	20	0						
27+40.000	0	203	36+20.000	204	4	39+80.000	86	82				10+20.000	0	0			
27+60.000	19	109	36+40.000	195	2	40+00.000	78	82	Station	Uncl. Exc.	Embt	10+40.000	27	0			
27+80.000	52	113	36+60.000	208	0	40+20.000	81	60	Y3	(cu. meters)	(cu. meters)	10+60.000	18	0			
28+00.000	43	163	36+80.000	203	0	40+40.000	87	50									
28+20.000	19	202	37+00.000	206	0	40+60.000	87	45	10+20.000	0	0	Station	Uncl. Exc.	Embt			
28+40.000	9	291	37+20.000	233	0	40+80.000	85	26	10+40.000	8	40	Y8	(cu. meters)	(cu. meters)			
28+60.000	0	435	37+40.000	266	0				10+60.000	18	26						
28+80.000	0	511	37+60.000	293	0	Station	Uncl. Exc.	Embt	10+80.000	22	20	10+20.000	0	0			
29+00.000	0	505	37+80.000	275	0							10+40.000	24	0			
29+20.000	0	583	38+00.000	235	0	L6	(cu. meters)	(cu. meters)	Station	Uncl. Exc.	Embt	10+80.000	51	0			
29+40.000	0	613	38+20.000	139	0	11+80.000	0	0	Y4	(cu. meters)	(cu. meters)	11+00.000	20	1			
29+60.000	0	631	38+40.000	51	0	12+00.000	44	0				11+20.000	21	1			
29+80.000	0	688	38+60.000	38	0	12+20.000	43	0	10+20.000	0	0	11+40.000	20	0			
30+00.000	0	664	38+80.000	31	0	12+40.000	36	7	10+40.000	19	0						
30+20.000	0	644	39+00.000	40	0	12+60.000	34	14	10+60.000	34	0	Station	Uncl. Exc.	Embt	TEMPORARY PAVEMENT (LEFT)		
30+40.000	0	593	39+20.000	44	0	12+80.000	28	20	10+80.000	48	0	Y9	(cu. meters)	(cu. meters)	Station	Uncl. Exc.	Embt
30+60.000	0	568	39+40.000	44	0	13+00.000	25	24							Lrev	(cu. meters)	(cu. meters)
30+80.000	0	535	39+60.000	32	0	13+20.000	28	28	Station	Uncl. Exc.	Embt	10+00.000	0	0	33+40.000	0	1
31+00.000	0	495	39+80.000	23	0	13+40.000	26	36	Y4A	(cu. meters)	(cu. meters)	10+20.000	25	3	33+60.000	0	7
31+20.000	0	581	40+00.000	28	10	13+60.000	30	47				10+40.000	15	19	33+80.000	0	14
31+40.000	0	644	40+20.000	32	17	13+80.000	33	47	10+20.000	0	0				34+00.000	0	13
31+60.000	0	573	40+40.000	29	11	14+00.000	36	39	10+40.000	43	0	Station	Uncl. Exc.	Embt	34+20.000	0	13
31+80.000	0	512	40+60.000	24	3	14+20.000	40	38				Y10	(cu. meters)	(cu. meters)	34+40.000	0	17
32+00.000	0	479	40+80.000	27	0	14+40.000	39	28	Station	Uncl. Exc.	Embt				34+60.000	0	20
32+20.000	1	373				14+60.000	79	9	Y5	(cu. meters)	(cu. meters)	10+00.000	0	0			
32+40.000	12	170	Station	Uncl. Exc.	Embt	14+80.000	146	0				10+20.000	86	0			
32+60.000	23	49				15+00.000	148	22	10+20.000	0	0	10+40.000	78	0			
32+80.000	13	112	L4	(cu. meters)	(cu. meters)	15+20.000	121	48	10+40.000	11	0						
33+00.000	0	168	34+80.000	60	51	15+40.000	94	53				Station	Uncl. Exc.	Embt			
			35+00.000	179	156	15+60.000	51	51	Station	Uncl. Exc.	Embt						
Station	Uncl. Exc.	Embt	35+20.000	206	161	15+80.000	39	46	Y5A	(cu. meters)	(cu. meters)	10+20.000	0	0			
L3	(cu. meters)	(cu. meters)	35+40.000	263	151	16+00.000	33	62				10+40.000	15	65			
			35+60.000	325	143	16+20.000	39	83	10+20.000	0	0						
33+00.000	0	0	35+80.000	402	122	16+40.000	40	64	10+40.000	20	0						
33+20.000	0	146	36+00.000	477	114	16+60.000	17	74	10+60.000	16	0	Station	Uncl. Exc.	Embt			
33+40.000	0	207	36+20.000	494	123	16+80.000	11	170	10+80.000	15	0						
33+60.000	0	257	36+40.000	504	108	17+00.000	8	298				Y11	(cu. meters)	(cu. meters)	TEMPORARY PAVEMENT (RIGHT)		
33+80.000	0	195	36+60.000	495	86	17+20.000	2	491	Station	Uncl. Exc.	Embt	10+00.000	0	0	Station	Uncl. Exc.	Embt
34+00.000	4	130	36+80.000	442	88	17+40.000	0	710	Y6	(cu. meters)	(cu. meters)	10+20.000	18	0	Lrev	(cu. meters)	(cu. meters)
34+20.000	19	75	37+00.000	407	93							10+40.000	13	1			
34+40.000	23	60	37+20.000	373	104	Station	Uncl. Exc.	Embt	10+20.000	21	21				28+60.000	0	0
34+60.000	10	98	37+40.000	300	123				Station	Uncl. Exc.	Embt				28+80.000	18	0
			37+60.000	239	130	Y1	(cu. meters)	(cu. meters)				Y12	(cu. meters)	(cu. meters)	29+00.000	18	0
Station	Uncl. Exc.	Embt	37+80.000	212	124	10+60.000	0	0	Station	Uncl. Exc.	Embt				29+20.000	27	0
L4	(cu. meters)	(cu. meters)	38+00.000	201	99	10+80.000	21	2	Y6A	(cu. meters)	(cu. meters)	10+20.000	0	0	29+40.000	34	0
			38+20.000	179	68	11+00.000	12	64				10+40.000	73	0	29+60.000	39	0
34+80.000	11	0	38+40.000	147	51				10+20.000	0	0	10+60.000	52	0	29+80.000	48	0
35+00.000	32	0	38+60.000	135	38				10+80.000	22	0	10+80.000	15	0	30+00.000	54	0