

PROJECT NO. R-2237B
CALDWELL COUNTY

BALANCE CARD
VOLUMES ARE IN CUBIC YARDS

LINE	STATION TO STATION	TOTAL UNCLASS. EXC.	ROCK EXC.	UNDERCUT EXC.	SUITABLE EARTH EXC.	ROCK EXCAVATION +25%	TOTAL EXCAVATION +%	TOTAL EMBANKMENT	ROCK EMBANKMENT	EARTH EMBANKMENT	TOTAL EMBANKMENT +%	BORROW	UNSUITABLE WASTE	ROCK SUITABLE WASTE	EARTH SUITABLE WASTE	TOTAL WASTE
	SUMMARY NO. 11															
-L-	280+00.00-297+50.00	9,693	3,332	0	6,361	4,165	10,526	166,044	3,332	161,879	189,493	179,800	0	0	0	0
-Y2-	10+30.00-10+80.00	65	0	0	65	0	65	0	0	0	0	0	0	0	65	65
	TOTAL SUMMARY NO. 11	9,758	3,332	0	6,426	4,165	10,591	166,044	3,332	161,879	189,493	179,800	0	0	65	65
	SUMMARY NO. 12															
-L-	297+50.00-322+50.00	976,112	886,869	0	89,243	1,108,586	1,197,829	48,672	38,938	0	38,938	0	0	1,059,914	89,243	1,149,157
-Y4-	10+30.00-10+80.00	364	0	0	364	0	364	0	0	0	0	0	0	0	364	364
	TOTAL SUMMARY NO. 12	976,476	886,869	0	89,607	1,108,586	1,198,193	48,672	38,938	0	38,938	0	0	1,059,914	89,607	1,149,521
	SUMMARY NO. 13															
-L-	322+50.00-328+50.00	365	348	0	17	435	452	542,149	348	541,714	623,319	622,954	0	0	0	0
	TOTAL SUMMARY NO. 13	365	348	0	17	435	452	542,149	348	541,714	623,319	622,954	0	0	0	0
	SUMMARY NO. 14															
-L-	328+50.00-333+50.00	174,187	144,315	0	29,872	180,394	210,266	1,484	1,187	0	1,187	0	0	178,910	29,872	208,782
	TOTAL SUMMARY NO. 14	174,187	144,315	0	29,872	180,394	210,266	1,484	1,187	0	1,187	0	0	178,910	29,872	208,782
	SUMMARY NO. 15															
-L-	333+50.00-340+00.00	8,664	5,647	0	3,017	7,059	10,076	150,129	5,647	143,070	170,178	161,514	0	0	0	0
	TOTAL SUMMARY NO. 15	8,664	5,647	0	3,017	7,059	10,076	150,129	5,647	143,070	170,178	161,514	0	0	0	0
	SUMMARY NO. 16															
-L-	340+00.00-346+50.00	10,165	0	0	10,165	0	10,165	2,747	0	2,747	3,159	0	0	0	7,006	7,006
	TOTAL SUMMARY NO. 16	10,165	0	0	10,165	0	10,165	2,747	0	2,747	3,159	0	0	0	7,006	7,006
	SUMMARY NO. 17															
-L-	346+50.00-356+00.00	16,241	0	0	16,241	0	16,241	36,278	0	36,278	41,720	25,479	0	0	0	0
-Y5-	10+00.00-15+00.00	1,844	0	0	1,844	0	1,844	1,283	0	1,283	1,475	0	0	0	369	369
	TOTAL SUMMARY NO. 17	18,085	0	0	18,085	0	18,085	37,561	0	37,561	43,195	25,479	0	0	369	369
	SHEET SUBTOTAL	1,197,700	1,040,511	0	157,189	1,300,639	1,457,828	948,786	49,452	886,972	1,069,469	989,747	0	1,238,824	126,919	1,365,743