

DIVISION OF HIGHWAYS
 STATE OF NORTH CAROLINA

SUMMARY OF EARTHWORK
 IN CUBIC YARDS

LOCATION	UNCLASSIFIED EXCAVATION	EMBT + 30%	BORROW	WASTE
SUMMARY NO. 1 (LT & RT)				
-L- 16+46.17 TO 19+84.31	406	1398	1398	406
SUMMARY NO. 2 (LT & RT)				
-L- 20+75.69 TO 24+13.05	451	2023	2023	451
-L- TOTALS	857	3421	3421	857
PROJECT TOTAL	857	3421	3421	857
LOSS DUE TO C&G				
EST. 5% TO REPLACE TOPSOIL ON BORROW PIT			171	
GRAND TOTAL	857	3421	3592	857
SAY	857	3421	3600	857
UNDERCUT	500			
INCLUDE DRAINAGE DITCH EXCAVATION	528			528

NOTES:

1. UNDERCUT 500 CY.
2. -L- PAVEMENT STRUCTURE VOLUME = 21 CY.

APPROXIMATE QUANTITIES ONLY,
 UNCLASSIFIED EXCAVATION, BORROW
 EXCAVATION, FINE GRADING, CLEARING
 AND GRUBBING, AND REMOVAL OF
 EXISTING PAVEMENT WILL BE PAID FOR
 AT CONTRACT LUMP SUM PRICE FOR
 "GRADING".

6/4/99
 SYSTEMS
 DIVISION
 PROJECTS
 SECTION