

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - ~~000000~~ **C20136**

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (27+49.00)
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB- BING
0057000000-E	226	250	CY	UNDERCUT EXCAVATION
0063000000-N	SP	Lump Sum		GRADING
0080000000-E	SP	300	TON	CLASS IV SUBGRADE STABILIZA- TION
0106000000-E	230	19,700	CY	BORROW EXCAVATION
0134000000-E	240	360	CY	DRAINAGE DITCH EXCAVATION
0195000000-E	265	250	CY	SELECT GRANULAR MATERIAL
0196000000-E	270	500	SY	FABRIC FOR SOIL STABILIZATION
0318000000-E	300	53	TON	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS
0343000000-E	310	80	LF	15" SIDE DRAIN PIPE
0345000000-E	310	172	LF	24" SIDE DRAIN PIPE
0366000000-E	310	132	LF	15" RC PIPE CULVERTS, CLASS III
0708000000-E	310	108	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
0806000000-E	310	4	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK
0995000000-E	340	133	LF	PIPE REMOVAL
0996000000-N	350	1	EA	PIPE CLEAN-OUT
1121000000-E	520	55	TON	AGGREGATE BASE COURSE
1220000000-E	545	80	TON	INCIDENTAL STONE BASE
1489000000-E	610	740	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
1498000000-E	610	510	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0B
1514000000-E	610	980	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5A
1560000000-E	620	120	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
1693000000-E	654	5	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR
2000000000-N	806	21	EA	RIGHT OF WAY MARKERS
2286000000-N	840	4	EA	MASONRY DRAINAGE STRUCTURES
2355000000-N	840	4	EA	FRAME WITH GRATE, STD 840.29
2556000000-E	846	400	LF	SHOULDER BERM GUTTER
3030000000-E	862	700	LF	STEEL BM GUARDRAIL
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III
3270000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
3628000000-E	876	20	TON	PLAIN RIP RAP, CLASS I
3649000000-E	876	160	TON	PLAIN RIP RAP, CLASS B
3656000000-E	876	650	SY	FILTER FABRIC FOR DRAINAGE
4400000000-E	1110	559	SF	WORK ZONE SIGNS (STATIONARY)
4410000000-E	1110	144	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
4425000000-N	1125	4	EA	WARNING FLAG SETS
4430000000-N	1130	30	EA	DRUMS
4445000000-E	1145	192	LF	BARRICADES (TYPE III)
4685000000-E	1205	3,600	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
4686000000-E	1205	3,632	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
4905000000-N	1253	23	EA	SNOWPLOWABLE RAISED PAVEMENT MARKERS
5300000000-E	1505	90	TON	FOUNDATION CONDITIONING MATE- RIAL, UTILITIES CLASS ***** (IV)
5306000000-E	SP	90	TON	BEDDING MATERIAL, UTILITIES CLASS ***** (IV)
5318000000-E	1505	25	TON	PAVEMENT REPAIR FOR UTILITY WORK

ItemNumber	Sec #	Quantity	Unit	Description
5360000000-E	1510	115	LF	6" DI WATER PIPE, PC 350
5366000000-E	1510	1,677	LF	8" DI WATER PIPE, PC 350
5378000000-E	1510	55	LF	12" DI WATER PIPE, PC 350
5414000000-E	1510	225	LF	3/4" COPPER WATER PIPE, TYPE K
5480000000-E	1510	1,085	LB	DUCTILE IRON WATER PIPE FIT- TINGS, 250# MIN WP
5510000000-E	1510	4	EA	3/4" CORPORATION STOP
5540000000-E	1510	3	EA	6" GATE VALVE & VALVE BOX, 200# WP
5546000000-E	1510	3	EA	8" GATE VALVE & VALVE BOX, *****WP (200#)
5558000000-E	1510	2	EA	12" GATE VALVE & VALVE BOX, *****WP (200#)
5618000000-E	1510	2	EA	6" TRANSITION COUPLING, ***** (AC TO DI)
5648000000-N	1510	4	EA	RELOCATE EXISTING WATER METER
5672000000-N	1510	1	EA	RELOCATE EXISTING FIRE HYDRANT
5798000000-E	1530	256	LF	FILL OR REMOVE ABANDONED *** PIPE, ***** (6", AC WATER)
5798000000-E	1530	1,310	LF	FILL OR REMOVE ABANDONED *** PIPE, ***** (8", AC WATER)
5882000000-N	SP	4	EA	GENERIC UTILITY ITEM 12" RESTRAINED RETAINER GLAND
5882000000-N	SP	4	EA	GENERIC UTILITY ITEM 6" RESTRAINED RETAINER GLAND
5882000000-N	SP	8	EA	GENERIC UTILITY ITEM 8" RESTRAINED RETAINER GLAND
5888000000-E	SP	100	LF	GENERIC UTILITY ITEM TRENCHLESS INSTALLATION OF 8" WATER PIPE IN SOIL
5888000000-E	SP	100	LF	GENERIC UTILITY ITEM TRENCHLESS INSTALLATION OF 8" WATER PIPE NOT IN SOIL
6000000000-E	1605	425	LF	TEMPORARY SILT FENCE
6006000000-E	1610	175	TON	STONE FOR EROSION CONTROL, CLASS A
6009000000-E	1610	575	TON	STONE FOR EROSION CONTROL, CLASS B
6012000000-E	1610	192	TON	SEDIMENT CONTROL STONE
6015000000-E	1615	3	ACR	TEMPORARY MULCHING
6018000000-E	1620	100	LB	SEED FOR TEMPORARY SEEDING
6021000000-E	1620	0.5	TON	FERTILIZER FOR TEMPORARY SEED- ING
6024000000-E	1622	100	LF	TEMPORARY SLOPE DRAINS
6027000000-N	1622	4	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
6030000000-E	1630	1,535	CY	SILT EXCAVATION
6033000000-E	1631	700	SY	SYNTHETIC ROVING
6036000000-E	1631	1,130	SY	MATting FOR EROSION CONTROL
6042000000-E	1632	80	LF	1/4" HARDWARE CLOTH
6084000000-E	1660	4	ACR	SEEDING & MULCHING
6087000000-E	1660	2	ACR	MOWING
6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
6096000000-E	1662	75	LB	SEED FOR SUPPLEMENTAL SEEDING
6108000000-E	1665	3	TON	FERTILIZER TOPDRESSING
6114000000-N	SP	2	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	12	EA	RESPONSE FOR EROSION CONTROL
6126000000-E	SP	0.07	ACR	STREAMBANK REFORESTATION
6141000000-E	SP	225	SY	GENERIC EROSION CONTROL ITEM COIR FIBER MAT

10-JUL-2003 10:46
MRHussey AT