

SHEET NO. 3 OF 20 DAVIDSON COUNTY WORK ORDER NOS. 9CR.10291.3, 9CR.20291.3, 9CR.302911.3, 9CR.302916.3 NCMA WORK ORDER NOS. 36825, 36950, 36951, 36954, 36957, 36960, 36965, 37824, 37825, 37826, 37830 TYPICAL SECTIONS SHEET (1 OF 3)

PAVEMENT SCHEDULE	
С	PROP. APPROX. 1.5" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, TO BE APPLIED AT AN AVERAGE RATE OF 168 LBS PER SQ YD.
C - 1	PROP. APPROX. 1.62" ASPHALT CONCRETE SURFACE COURSE TYPE S9.5B, TO BE APPLIED AT AN AVERAGE RATE OF 180 LBS PER SQ YD.
C-2	PROP. APPROX. 1.5" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5C, TO BE APPLIED AT AN AVERAGE RATE OF 168 LBS PER SQ YD.
Е	PROP. APPROX. 5.5" ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, TO BE APPLIED AT AN AVERAGE RATE OF 627 LBS. PER SQ. YD.
F	ASPHALT SURFACE TREATMENT MAT COURSE, 78M, CRS-2 AT AN AVERAGE RATE OF 0.35 GAL PER SQ. YD., No. 78M STONE AT AN AVERAGE RATE OF 15-20 LBS PER SQ. YD.
М	MILLING ASPHALT PAVEMENT, 1.5" DEPTH, FULL WIDTH
M - 1	MILLING ASPHALT PAVEMENT, 0" TO 1.5" DEPTH