

SUMMARY OF QUANTITIES

| Work Order No. | County/Municipality | Map No. | Route No./Name | To/From Description | Typ Sect No | Length | Widening | Final Width | Inc Stone Base | Shldr Reconst | Mill Asph Pvmt 1 1/2" | Mill Asph Pvmt 0" to 1 1/2" | ACBC Type B25.0B | ACSC Type S9.5B | ACSC Type S9.5C | PG 64-22 Plant Mix | PG 70-22 Plant Mix | Patch Exist Pvmt | Asph Surf Treat MAT Course #78 Stone | Adj CB | Adj DI | Adj MH | Adj MB/ VB | |
|---|---------------------|---------|---|--|-------------|--------|----------|-------------|----------------|---------------|-----------------------|-----------------------------|------------------|-----------------|-----------------|--------------------|--------------------|------------------|--------------------------------------|--------|--------|--------|------------|----|
| | | | | | | MI | FT | FT | TONS | SMI | SY | SY | TONS | TONS | TONS | TONS | TONS | TONS | TONS | TONS | TONS | TONS | EA | EA |
| 36825 | Davidson | 18 | SR 2060 Emmanuel Church Rd/ Kendall Mill Rd | SR 2031 (Johnsontown Rd) to Pvmt Jt at SR 2085 (Lake Rd) | 1 | 1.333 | 0 | 22 | 13 | | | | | 1,645 | | 99 | | 30 | | | | 1 | 2 | |
| Total for NCMA Work Order No. 36825 | | | | | | 1.333 | | | 13 | 0 | 0 | 0 | 0 | 1,645 | 0 | 99 | 0 | 30 | 0 | 0 | 0 | 1 | 2 | |
| 36950 | Davidson | 19 | SR 1254 Brown St | NC 8 (Cotton Grove Rd) to SR 1104 (Old Linwood Rd) | 10 | 0.737 | 4 | 22 | 7 | 1.47 | | | 665 | 884 | | 82 | | 10 | | | | | 1 | |
| Total for NCMA Work Order No. 36950 | | | | | | 0.737 | | | 7 | 1.47 | 0 | 0 | 665 | 884 | 0 | 82 | 0 | 10 | 0 | 0 | 0 | 0 | 0 | 1 |
| 36951 | Davidson | 20 | SR 1194 Yadkin College Rd | SR 1192 (Old US 64) to US 64 | 12 | 0.540 | 6 | 22 | 11 | 1.08 | | | 706 | 648 | | 69 | | 10 | | | | | 1 | |
| | | 20 | SR 1194 Yadkin College Rd | US 64 to Pvmt Jt Before SR 1186 (Koontz Rd) | 10 | 1.740 | 4 | 22 | 35 | 3.48 | 0 | 244 | 1,569 | 2,087 | | 193 | | 40 | | | | | 1 | |
| Total for NCMA Work Order No. 36951 | | | | | | 2.280 | | | 46 | 4.56 | 0 | 244 | 2,275 | 2,735 | 0 | 262 | 0 | 50 | 0 | 0 | 0 | 0 | 2 | |
| 36954 | Davidson | 21 | SR 2066 Kennedy Rd | Pvmt Jt Below SR 2093 (Ben Lee Rd) to Randolph Co Line | 10 | 2.066 | 4 | 22 | 21 | 4.13 | | | 1,889 | 2,478 | | 230 | | 60 | | | | | 3 | |
| Total for NCMA Work Order No. 36954 | | | | | | 2.066 | | | 21 | 4.13 | 0 | 0 | 1,889 | 2,478 | 0 | 230 | 0 | 60 | 0 | 0 | 0 | 0 | 0 | 3 |
| 36957 | Davidson | 22 | SR 1237 Forest Hill Rd | SR 1192 (Old US 64) to SR 1242 (West Center St Ext) | 10 | 1.250 | 4 | 22 | 13 | 2.50 | | | 1,127 | 1,499 | | 138 | | 40 | | | | | 1 | |
| Total for NCMA Work Order No. 36957 | | | | | | 1.250 | | | 13 | 2.50 | 0 | 0 | 1,127 | 1,499 | 0 | 138 | 0 | 40 | 0 | 0 | 0 | 0 | 0 | 1 |
| 36960 | Davidson | 23 | SR 1505 Payne Rd | Pvmt Jt at SR 1499 (Enterprise Rd) to SR 1511 (Hartman Rd) | 10 | 2.250 | 4 | 22 | 23 | 4.50 | 0 | 244 | 2,029 | 2,699 | | 249 | | 40 | | | | | 1 | |
| Total for NCMA Work Order No. 36960 | | | | | | 2.250 | | | 23 | 4.50 | 0 | 244 | 2,029 | 2,699 | 0 | 249 | 0 | 40 | 0 | 0 | 0 | 0 | 0 | 1 |
| 36965 | Davidson | 24 | SR 2227 New Bowers Rd | SR 2205 (Old US 64) to End of BST | 10 | 1.655 | 4 | 22 | 17 | 3.31 | | | 1,520 | 1,985 | | 185 | | 20 | | | | | 2 | |
| Total for NCMA Work Order No. 36965 | | | | | | 1.655 | | | 17 | 3.31 | 0 | 0 | 1,520 | 1,985 | 0 | 185 | 0 | 20 | 0 | 0 | 0 | 0 | 0 | 2 |
| 37824 | Davidson | 25 | SR 2227 New Bowers Rd | From BST to Pvmt Jt at Island at US 64 | 8 | 0.682 | 2 | 22 | 7 | 0.68 | | | 339 | 818 | | 64 | | 10 | | | | | 2 | |
| Total for NCMA Work Order No. 37824 | | | | | | 0.682 | | | 7 | 0.68 | 0 | 0 | 339 | 818 | 0 | 64 | 0 | 10 | 0 | 0 | 0 | 0 | 0 | 2 |
| 37825 | Davidson | 26 | SR 2247 Rhodes Rd | SR 2248 (Allred Rd) to Pvmt Jt at SR 2205 (Old US 64) | 8 | 2.314 | 2 | 22 | 23 | 2.31 | | | 1,151 | 2,775 | | 216 | | 8 | | | | | 4 | |
| Total for NCMA Work Order No. 37825 | | | | | | 2.314 | | | 23 | 2.31 | 0 | 0 | 1,151 | 2,775 | 0 | 216 | 0 | 8 | 0 | 0 | 0 | 0 | 0 | 4 |
| 37826 | Davidson | 27 | SR 2248 Allred Rd | Pvmt Jt at NC 47 to Pvmt Jt at SR 2205 (Old US 64) | 9 | 3.378 | 2 | 22 | 34 | 3.38 | | | 1,680 | 4,350 | | 333 | | 20 | | | | | 4 | |
| Total for NCMA Work Order No. 37826 | | | | | | 3.378 | | | 34 | 3.38 | 0 | 0 | 1,680 | 4,350 | 0 | 333 | 0 | 20 | 0 | 0 | 0 | 0 | 0 | 4 |
| 37830 | Davidson | 28 | SR 2380 Bethany Rd | Pvmt Jt at SR 2304 (Parks Rd) to Pvmt Jt 75 ft From NC 47 | 11 | 1.382 | 4 | 22 | 14 | 2.76 | | | 1,269 | 1,780 | | 161 | | 20 | | | | | 5 | |
| Total for NCMA Work Order No. 37830 | | | | | | 1.382 | | | 14 | 2.76 | 0 | 0 | 1,269 | 1,780 | 0 | 161 | 0 | 20 | 0 | 0 | 0 | 0 | 0 | 5 |
| TOTAL FOR 2005 NCMA | | | | | | 19.327 | | | 218 | 29.6 | 0 | 488 | 13,944 | 23,648 | 0 | 2019 | 0 | 308 | 0 | 0 | 0 | 1 | 27 | |
| GRAND TOTAL FOR 2005 DAVIDSON COUNTY RESURFACING | | | | | | 57.461 | | | 750 | 29.6 | 11,537 | 5,193 | 13,944 | 61,341 | 16,669 | 4,278 | 1,000 | 1,030 | 7,595 | 5 | 10 | 54 | 82 | |