

SUMMARY OF EARTHWORK IN CUBIC YARD

Station	Station	Uncl. Excav.	Undercut	Embank. +%	Borrow	Waste
-LREV- 6+15 - 13+15		98		445	396	49
-LREV- 13+15 - 37+55		645		4281	3958	322
TOTAL		743		4726	4354	371
PROJECT TOTAL		743		4726	4354	371
EST. 5% TO REPLACE TOPSOIL ON BORROW PIT					218	
GRAND TOTAL		743		4726	4572	371
SAY		800			4600	
EST FOR UNDERCUT			500			

REMOVAL OF EXISTING ASPHALT PAVEMENT

LINE	STATION TO STATION	LOCATION	SQ. YD.
Y2	11+11 11+46	LT	15
TOTAL			15
SAY			100

Approximate quantities only. Unclassified excavation, borrow excavation, shoulder borrow, fine grading, clearing and grubbing, breaking of existing pavement and removal of existing pavement will be paid for at the lump sum price for "Grading".