

WORK ORDER NOS. 9CR.10341.3, 9CR.20341.3,
 9CR.303409.3, 9CR.303418.3, 9CR.303423.3,
 9CR.303426.3, 9CR.303428.3, 9CR.303499.3
 NCMA WORK ORDER NOS. 36913,
 37784, 37785, 37786, 37787, 37807

SUMMARY OF QUANTITIES

Work Order No	County/Municipality	Map No.	Route No/Route Name	To/From Description	Typ Sect No	Length	Widening	Final Width	Inc Stone Base	Shldr Reconst	Mill Asph Pvm 1-1/2" Depth	Mill Asph Pvm 0" To 1-1/2" Depth	ACBC Type B25.0C	ACBC Type B25.0B	ACSC Type S9.5B	ACSC Type S9.5C	Level Course ACSC Type S9.5C	PG 64-22 Plant Mix	PG 70-22 Plant Mix	Patch Exist Pvm	Adjust DI	Adjust MH	Adjust MB / VB
						MI	FT	FT	TONS	SMI	SY	SY	TONS	TONS	TONS	TONS	TONS	TONS	TONS	TONS	TONS	TONS	TONS
9CR.10341.3	Forsyth	1	NC 65	Stokes Co Line to SR 1965 (Belews Creek Rd)	3	2.106		24	21							2,754			165	20			4
		1	NC 65	Pvmt Jt on SR 1965 (Belews Creek Rd) to Guilford Co Line	3	2.595		24	34			533				3,394			204	25			
TOTAL FOR MAP NO. 1						4.701			55	0.00	0	533	0	0	0	6,148	0	0	369	45	0	0	4
		2	US 311	Pvmt Jt at SR 1979 (Grubbs Rd) to Stokes Co Line	3	2.858		24	29							3,670			220				
		3	NC 65	Rural Hall CL to Pvmt Jt at NC 8 (Germanton Rd)	3	3.406		24	34							4,454			267	55	0	0	0
TOTAL FOR WORK ORDER NO. 9CR.10341.3						10.965			118	0.00	0	533	0	0	0	14,272	0	0	856	100	0	0	4
9CR.20341.3	Forsyth	4	SR 1977 Pine Hall Rd	SR 1954 (Salem Chapel Rd) to NC 65	1	3.133		24	31						4,097			286		40			2
		5	SR 1175 Hauser Rd	Pvmt Jt at SR 1001 (Shallowford Rd) to Pvmt Jt at SR 1173 (Williams Rd)	7	2.712	4	24	27	5.42		267		2,446	3,808			334		15			
		6	SR 1455 Balsom Rd	Pvmt Jt at SR 1434 (Grandview Club Rd) to Pvmt Jt at SR 1463 (Seward Rd)	7	2.780	4	24	28	5.56				2,507	3,904			342		25			2
		7	SR 1828 Turfwood Rd	Pvmt Jt at SR 3963 (Thornwood Ln) to SR 1611 (Bethania-Tobaccoville Rd)	1,4	1.153		20	12						1,258			75		40			13
		8	SR 2979 Hope Church Rd	Pvmt Jt at SR 2991 (Fraternity Church Rd) to Winston-Salem CL	1	0.414		20	4						452			27		10			
		9	SR 2014 Vance Rd	Pvmt Jt at US 158 to Pvmt Jt at SR 1969 (Piney Grove Rd)	4	4.951		22	50		73	244			5,938			356					9
		10	SR 2699 Cole Rd	Winston-Salem CL to SR 2698 (Ridgewood Rd)	4	0.033		36							65			4		5			
TOTAL FOR WORK ORDER NO. 9CR.20341.3						15.176			152	10.98	73	511	0	4,953	19,522	0	0	1,424	0	135	0	0	26
9CR.303409.3	Kernersville	11	SR 2029 Perry Rd	NC 66 (W. Mtn St) to Kernersville CL	3	0.262		24	3			213				343			21	10		1	
		12	SR 1005 E Mountain St	Concrete Pavement at I-40 Bus to Guilford Co Line	3	0.940		26	9		289	578				1,443			87	15		1	1
TOTAL FOR WORK ORDER NO. 9CR.303409.3						1.202			12	0.00	289	791	0	0	0	1,786	0	0	108	25	0	2	1