

EROSION CONTROL

Seeding And Mulching

(6)

The kinds of seed and fertilizer, and the rates of application of seed, fertilizer, and limestone, shall be as stated below. During periods of overlapping dates, the kind of seed to be used shall be determined by the Engineer. All rates are in pounds per acre (kilograms per hectare).

August 1 - June 1

May 1 - September 1

100# (110kg) Tall Fescue
15# (17kg) Kentucky Bluegrass
15# (17kg) Hard Fescue
500# (560kg) Fertilizer
4000# (4500kg) Limestone

100# (110kg) Tall Fescue
15# (17kg) Kentucky Bluegrass
15# (17kg) Hard Fescue
25# (28kg) Kobe or Korean Lespedeza
500# (560kg) Fertilizer
4000# (4500kg) Limestone

Approved Tall Fescue Cultivars:

- Adventure, Adventure II, Amigo, Anthem, Apache, Apache II, Arid, Austin, Brookstone, Bonanza, Bonanza II, Chapel Hill, Chesapeake, Chieftain, Coronado, Crossfire II, Debutante, Duster, Falcon, Falcon II, Finelawn Petite, Finelawn, Finelawn I, Genesis, Grande, Guardian, Houndog, Jaguar, Jaguar III, Kentucky 31, Kitty Hawk, Monarch, Montauk, Mustang, Olympic, Pacer, Phoenix, Pixie, Pyramid, Rebel, Rebel Jr., Renegade, Safari, Shenandoah, Tempo, Titan, Tomahawk, Trailblazer, Tribute, Vegas, Wolfpack, Wrangler

Approved Kentucky Bluegrass Cultivars:

- Adelphi, Baron, Bristol, Challenger, Columbia, Fylking, Glade, Kenblue, Merit, Plush, Ram I, Rugby, Sydsport, Touchdown, Vantage

Approved Hard Fescue Cultivars:

- Aurora, Bardur, Crystal, Reliant, Scaldis, Spartan, Valda, Waldina, Warwick

On cut and fill slopes 2:1 or steeper add 25# (28kg) Rye Grain November 1 - March 1.

On cut and fill slopes 2:1 or steeper add 30# (35 kg) Sericea Lespedeza January 1 - December 31.

Fertilizer shall be 10-20-20 analysis. Upon written approval of the Engineer, a different analysis of fertilizer may be used provided the 1-2-2 ratio is maintained and the rate of application adjusted to provide the same amount of plant food as a 10-20-20 analysis.

**All areas adjacent to lawns must be hand finished as directed by the Engineer to give a "lawn type appearance". Remove all trash, debris, and stones  $\frac{3}{4}$  inch (19 mm) and larger in diameter or other obstructions that could interfere with providing a smooth "lawn type appearance".**