PROJ. REFERENCE NO.	SHEET NO.
R-2206AA	X-1

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Approximate quantities only. Unclassified excavation, borrow excavation, shoulder borrow, fine grading, clearing and grubbing, breaking of existing pavement and removal of existing pavement will be paid for at the lump sum price for "Grading".

Station L (LT)	Uncl. Exc. (cu. meters)	Embt (cu. meters)
10+00.000	0	0
10+20.000	34	4
10+40.000	34	4
10+60.000	86	19
10+80.000	86	19
11+20.000	116	32
11+40.000	116	32
11+60.000	70	1
11+80.000	97	4
12+00.000	43	8
12+20.000	26	12
12+40.000	14	21
12+60.000	11	43
12+80.000	19	71
13+00.000	25	112
13+20.000	27	175
13+40.000	31	253
13+60.000	39	237
13+80.000	22	89
14+00.000	35	73
14+20.000	81	139
14+40.000	105	113
14+60.000	130	75
14+80.000	151	35
15+00.000	202	7
15+20.000	289	0
15+40.000	399	0
15+60.000	509	0
15+80.000	598	0
16+00.000	695	0
16+20.000	751	0
16+40.000	754	0
16+60.000	709	0
16+80.000	590	0
17+00.000	258	0

Station L (RT)	Uncl. Exc. (cu. meters)	Embt (cu. meters)
10+00.000	0	0
10+20.000	40	0
10+40.000	40	0
10+60.000	1	18
10+80.000	1	18
11+20.000	7	23
11+40.000	7	23
11+60.000	37	2
11+80.000	78	6
12+00.000	88	12
12+20.000	91	17
12+40.000	69	21
12+60.000	42	23
12+80.000	30	30
13+00.000	26	34
13+20.000	20	29
13+40.000	19	26
13+60.000	19	24
13+80.000	9	12
14+00.000	6	13
14+20.000	18	23
14+40.000	70	57
14+60.000	81	49
14+80.000	44	2
15+00.000	33	0
15+20.000	11	0

Station L	Uncl. Exc. (cu. meters)	Embt (cu. meters)
5+60.000	0	0
5+80.000	217	628
6+00.000	177	814
6+20.000	150	738
6+40.000	140	472
6+60.000	171	209
6+80.000	209	119
7+00.000	233	154
7+20.000	272	94
7+40.000	370	5

Station Rpb	Uncl. Exc. (cu. meters)	Embt (cu. meters)
4+33.568	0	0
4+51.752	2683	0
4+75.845	2365	8
5+00.470	992	72
5+27.523	270	167
5+53.430	98	272
5+70.457	48	260
5+95.488	29	414
6+21.526	0	413
6+46.576	0	346
6+70.056	0	221

Station Rpa	Uncl. Exc. (cu. meters)	Embt (cu. meters)
10+00.000	0	0
10+20.000	0	0
10+40.0000	9	11
10+60.0000	24	17
10+80.0000	38	13
11+00.0000	24	12
11+20.0000	6	22
11+52.312	0	18

Station Cr1	Uncl. Exc. (cu. meters)	Embt (cu. meters)
10+00.000	0	0
10+20.000	0	0
10+40.0000	3	16
10+60.0000	22	16
10+80.0000	49	8
11+00.0000	44	6
11+20.0000	15	15
11+51.990	0	16

Station Cr2	Uncl. Exc. (cu. meters)	Embt (cu. meters)
10+00.000	0	0
10+20.000	0	0
10+40.0000	11	9
10+60.0000	17	24
10+80.0000	13	38
11+00.0000	12	24
11+20.0000	22	6
11+52.312	18	0

Station Cr1 REM	Uncl. Exc. (cu. meters)	Embt (cu. meters)
10+00.000	0	0
10+20.000	0	0
10+40.0000	3	16
10+60.0000	22	16
10+80.0000	49	8
11+00.0000	44	6
11+20.0000	15	15
11+51.990	0	16

Station Cr2 REM	Uncl. Exc. (cu. meters)	Embt (cu. meters)
10+00.000	0	0
10+20.000	0	0
10+40.0000	9	11
10+60.0000	24	17
10+80.0000	38	13
11+00.0000	24	12
11+20.0000	6	22
11+52.312	0	18