

County : Gaston, Lincoln

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|----------------------|--------------|-------|--|--------------|-----------|--------|
| ROADWAY ITEMS | | | | | | |
| 0001 | 0000100000-N | 800 | MOBILIZATION | Lump Sum | L.S. | |
| 0002 | 0000400000-N | 801 | CONSTRUCTION SURVEYING | Lump Sum | L.S. | |
| 0003 | 0008000000-M | 200 | SUPPLEMENTARY CLEARING & GRUB-BING | 0.4 HA | | |
| 0004 | 0022000000-M | 225 | UNCLASSIFIED EXCAVATION | 17,000 M3 | | |
| 0005 | 0106000000-M | 230 | BORROW EXCAVATION | 42,500 M3 | | |
| 0006 | 0134000000-M | 240 | DRAINAGE DITCH EXCAVATION | 10 M3 | | |
| 0007 | 0141000000-M | 240 | BERM DITCH CONSTRUCTION | 100 M | | |
| 0008 | 0156000000-M | 250 | REMOVAL OF EXISTING ASPHALT PAVEMENT | 22,000 M2 | | |
| 0009 | 0177000000-M | 250 | BREAKING OF EXISTING ASPHALT PAVEMENT | 800 M2 | | |
| 0010 | 0318000000-M | 300 | FOUNDATION CONDITIONING MATERIAL, MINOR STRS | 110 MTN | | |
| 0011 | 0360000000-M | 310 | 300MM RC PIPE CULVERTS, CLASS III | 13.2 M | | |
| 0012 | 0366000000-M | 310 | 375MM RC PIPE CULVERTS, CLASS III | 174 M | | |
| 0013 | 0378000000-M | 310 | 600MM RC PIPE CULVERTS, CLASS III | 78 M | | |
| 0014 | 0588000000-M | 310 | 450MM CS PIPE CULVERTS, 1.63MM THICK | 61.2 M | | |
| 0015 | 0684000000-M | 310 | ***MM BIT COAT CS PIPE CULVERTS, TYPE B ****MM THICK (375MM, 1.63MM) | 21.6 M | | |
| 0016 | 0804000000-E | 310 | *** BIT COAT CS PIPE ELBOWS, TYPE B ***** THICK (375MM, 1.63MM) | 3 EA | | |
| 0017 | 0995000000-M | 340 | PIPE REMOVAL | 132 M | | |
| 0018 | 1011000000-N | 500 | FINE GRADING | Lump Sum | L.S. | |

County : Gaston, Lincoln

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|----------------|-----------|--------|
| 0019 | 1044000000-M | 501 | LIME TREATED SOIL (SLURRY METHOD) | 170,850 M2 | | |
| 0020 | 1066000000-M | 501 | LIME FOR LIME TREATED SOIL | 1,920 MTN | | |
| 0021 | 1121000000-M | 520 | AGGREGATE BASE COURSE | 111,500 MTN | | |
| 0022 | 1176000000-M | 542 | ***MM SOIL CEMENT BASE (180MM) | 92,000 M2 | | |
| 0023 | 1187000000-M | 542 | PORTLAND CEMENT FOR SOIL CEMENT BASE | 2,790 MTN | | |
| 0024 | 1198000000-M | SP | AGGREGATE FOR SOIL CEMENT BASE | 1,270 MTN | | |
| 0025 | 1209000000-M | 543 | ASPHALT CURING SEAL | 182,000 L | | |
| 0026 | 1220000000-M | 545 | INCIDENTAL STONE BASE | 1,000 MTN | | |
| 0027 | 1330000000-M | 607 | INCIDENTAL MILLING | 720 M2 | | |
| 0028 | 1491000000-M | 610 | ASPHALT CONC BASE COURSE, TYPE B25.0C | 35,500 MTN | | |
| 0029 | 1498000000-M | 610 | ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B | 8,800 MTN | | |
| 0030 | 1503000000-M | 610 | ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C | 37,000 MTN | | |
| 0031 | 1519000000-M | 610 | ASPHALT CONC SURFACE COURSE, TYPE S9.5B | 8,500 MTN | | |
| 0032 | 1523000000-M | 610 | ASPHALT CONC SURFACE COURSE, TYPE S9.5C | 35,700 MTN | | |
| 0033 | 1560000000-M | 620 | ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22 | 4,250 MTN | | |
| 0034 | 1565000000-M | 620 | ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22 | 2,350 MTN | | |
| 0035 | 2099000000-M | 816 | SHOULDER DRAIN | 6,500 M | | |
| 0036 | 2110000000-M | 816 | 100MM SHOULDER DRAIN PIPE | 6,500 M | | |

County : Gaston, Lincoln

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|---------------|-----------|--------|
| 0037 | 2121000000-M | 816 | 100MM OUTLET PIPE (SHOULDER DRAINS) | 350 M | | |
| 0038 | 2132000000-N | 816 | CONCRETE PAD FOR SHOULDER DRAIN PIPE OUTLET | 33 EA | | |
| 0039 | 2143000000-M | 818 | BLOTTING SAND | 20 MTN | | |
| 0040 | 2253000000-M | 840 | PIPE COLLARS | 0.29 M3 | | |
| 0041 | 2264000000-M | 840 | PIPE PLUGS | 0.1 M3 | | |
| 0042 | 2275000000-M | SP | FLOWABLE FILL | 13 M3 | | |
| 0043 | 2286000000-N | 840 | MASONRY DRAINAGE STRUCTURES | 9 EA | | |
| 0044 | 2365000000-N | 840 | FRAME WITH TWO GRATES, STD 840.22 | 6 EA | | |
| 0045 | 2396000000-N | 840 | FRAME WITH COVER, STD 840.54 | 3 EA | | |
| 0046 | 2407000000-N | 840 | STEEL FRAME WITH TWO GRATES, STD 840.37 | 44 EA | | |
| 0047 | 2549000000-M | 846 | 750MM CONCRETE CURB & GUTTER | 830 M | | |
| 0048 | 2556000000-M | 846 | SHOULDER BERM GUTTER | 3,860 M | | |
| 0049 | 2647000000-M | 852 | 125MM MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED) | 400 M2 | | |
| 0050 | 2703000000-M | 854 | CONCRETE BARRIER, TYPE ***** (I) | 440 M | | |
| 0051 | 2905000000-N | 859 | CONVERT EXISTING DROP INLET TO JUNCTION BOX | 3 EA | | |
| 0052 | 3030000000-M | 862 | STEEL BM GUARDRAIL | 6,320.79 M | | |
| 0053 | 3150000000-N | 862 | ADDITIONAL GUARDRAIL POSTS | 10 EA | | |
| 0054 | 3210000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE CAT-1 | 27 EA | | |
| 0055 | 3215000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE III | 9 EA | | |

County : Gaston, Lincoln

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|---------------|-----------|--------|
| 0056 | 3270000000-N | SP | GUARDRAIL ANCHOR UNITS, TYPE 350 | 39 EA | | |
| 0057 | 3285000000-N | SP | GUARDRAIL ANCHOR UNITS, TYPE M-350 | 2 EA | | |
| 0058 | 3317000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE B-77 | 10 EA | | |
| 0059 | 3360000000-M | 863 | REMOVE EXISTING GUARDRAIL | 170 M | | |
| 0060 | 3420000000-M | SP | GENERIC GUARDRAIL ITEM MEDIAN CABLE BARRIER (SOCKETED POST) (WRSF) | 8,804.13 M | | |
| 0061 | 3435000000-N | SP | GENERIC GUARDRAIL ITEM MEDIAN CABLE BARRIER ANCHOR (WRSF) | 36 EA | | |
| 0062 | 3503000000-M | 866 | WOVEN WIRE FENCE, 1200MM FABRIC | 60 M | | |
| 0063 | 3509000000-M | 866 | 100MM TIMBER FENCE POSTS, 2.30M LONG | 15 EA | | |
| 0064 | 3575000000-M | SP | GENERIC FENCING ITEM VINYL COATED CHAIN LINK FENCE (1219MM) FABRIC W/12.7MM MESH, BARRIER MOUNTED | 513 M | | |
| 0065 | 3649000000-M | 876 | PLAIN RIP RAP, CLASS B | 55 MTN | | |
| 0066 | 3656000000-M | 876 | FILTER FABRIC FOR DRAINAGE | 445 M2 | | |
| 0067 | 4048000000-M | 902 | REINFORCED CONCRETE SIGN FOOTINGS | 9 M3 | | |
| 0068 | 4054000000-M | 902 | PLAIN CONCRETE SIGN FOOTINGS | 3 M3 | | |
| 0069 | 4060000000-M | 903 | SUPPORTS, BREAKAWAY STEEL BEAM | 3,114 KG | | |
| 0070 | 4066000000-M | 903 | SUPPORTS, SIMPLE STEEL BEAM | 1,929 KG | | |
| 0071 | 4072000000-M | 903 | SUPPORTS, 4.5KG STEEL U-CHANNEL | 891 M | | |
| 0072 | 4096000000-N | 904 | SIGN ERECTION, TYPE D | 21 EA | | |

County : Gaston, Lincoln

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|-------------|-----------|--------|
| 0073 | 4102000000-N | 904 | SIGN ERECTION, TYPE E | 57 EA | | |
| 0074 | 4108000000-N | 904 | SIGN ERECTION, TYPE F | 38 EA | | |
| 0075 | 4110000000-N | 904 | SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A) | 13 EA | | |
| 0076 | 4110000000-N | 904 | SIGN ERECTION, TYPE *** (GROUND MOUNTED) (B) | 11 EA | | |
| 0077 | 4155000000-N | 907 | DISPOSAL OF SIGN SYSTEM, U- CHANNEL | 22 EA | | |
| 0078 | 4238000000-N | 907 | DISPOSAL OF SIGN, D, E OR F | 2 EA | | |
| 0079 | 4400000000-M | 1110 | WORK ZONE SIGNS (STATIONARY) | 56 M2 | | |
| 0080 | 4405000000-M | 1110 | WORK ZONE SIGNS (PORTABLE) | 18 M2 | | |
| 0081 | 4410000000-M | 1110 | WORK ZONE SIGNS (BARRICADE MOUNTED) | 4 M2 | | |
| 0082 | 4415000000-N | 1115 | FLASHING ARROW PANELS, TYPE C | 3 EA | | |
| 0083 | 4420000000-N | 1120 | CHANGEABLE MESSAGE SIGNS | 2 EA | | |
| 0084 | 4425000000-N | 1125 | WARNING FLAG SETS | 2 EA | | |
| 0085 | 4430000000-N | 1130 | DRUMS | 235 EA | | |
| 0086 | 4435000000-N | 1135 | CONES | 75 EA | | |
| 0087 | 4445000000-M | 1145 | BARRICADES (TYPE III) | 58 M | | |
| 0088 | 4455000000-N | 1150 | FLAGGER | 200 MD | | |
| 0089 | 4520000000-N | 1266 | TUBULAR MARKERS (FIXED) | 100 EA | | |
| 0090 | 4615000000-M | 1205 | REMOVABLE TAPE PAVEMENT MARK- ING LINES (100MM) | 6,170 M | | |
| 0091 | 4650000000-N | 1251 | TEMPORARY RAISED PAVEMENT MARKERS | 1,198 EA | | |

County : Gaston, Lincoln

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|-------------|-----------|--------|
| 0092 | 4685000000-M | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 2.3MM) | 2,149 M | | |
| 0093 | 4686000000-M | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 3.1MM) | 2,906 M | | |
| 0094 | 4695000000-M | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (200MM, 2.3MM) | 70 M | | |
| 0095 | 4710000000-M | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (600MM, 3.1MM) | 49 M | | |
| 0096 | 4725000000-M | 1205 | THERMOPLASTIC PAVEMENT MARKING SYMBOL (2.3MM) | 27 EA | | |
| 0097 | 4770000000-M | 1205 | COLD APPLIED PLASTIC PAVEMENT MARKING LINES (100MM) | 698 M | | |
| 0098 | 4805000000-N | 1205 | COLD APPLIED PLASTIC PAVEMENT MARKING SYMBOL | 4 EA | | |
| 0099 | 4810000000-M | 1205 | PAINT PAVEMENT MARKING LINES (100MM) | 47,399 M | | |
| 0100 | 4820000000-M | 1205 | PAINT PAVEMENT MARKING LINES (200MM) | 1,863 M | | |
| 0101 | 4835000000-M | 1205 | PAINT PAVEMENT MARKING LINES (600MM) | 9 M | | |
| 0102 | 4840000000-N | 1205 | PAINT PAVEMENT MARKING CHARACTER | 39 EA | | |
| 0103 | 4845000000-N | 1205 | PAINT PAVEMENT MARKING SYMBOL | 33 EA | | |
| 0104 | 4847000000-M | SP | POLYUREA PAVEMENT MARKING LINES (100MM) | 47,399 M | | |
| 0105 | 4847110000-M | SP | POLYUREA PAVEMENT MARKING LINES (200MM) | 1,863 M | | |
| 0106 | 4847140000-M | SP | POLYUREA PAVEMENT MARKING LINES (600MM) | 9 M | | |
| 0107 | 4847200000-N | SP | POLYUREA PAVEMENT MARKING CHARACTER | 39 EA | | |
| 0108 | 4847220000-N | SP | POLYUREA PAVEMENT MARKING SYMBOL | 33 EA | | |

County : Gaston, Lincoln

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|--------------|-----------|--------|
| 0109 | 4850000000-M | 1205 | REMOVAL OF PAVEMENT MARKING LINES (100MM) | 773 M | | |
| 0110 | 4860000000-M | 1205 | REMOVAL OF PAVEMENT MARKING LINES (200MM) | 137 M | | |
| 0111 | 4870000000-M | 1205 | REMOVAL OF PAVEMENT MARKING LINES (600MM) | 4 M | | |
| 0112 | 4875000000-N | 1205 | REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS | 2 EA | | |
| 0113 | 4900000000-N | 1252 | PERMANENT RAISED PAVEMENT MARKERS | 247 EA | | |
| 0114 | 4905000000-N | 1253 | SNOWPLOWABLE PAVEMENT MARKERS | 1,067 EA | | |
| 0115 | 6000000000-M | 1605 | TEMPORARY SILT FENCE | 340 M | | |
| 0116 | 6006000000-M | 1610 | STONE FOR EROSION CONTROL, CLASS A | 205 MTN | | |
| 0117 | 6009000000-M | 1610 | STONE FOR EROSION CONTROL, CLASS B | 480 MTN | | |
| 0118 | 6012000000-M | 1610 | SEDIMENT CONTROL STONE | 435 MTN | | |
| 0119 | 6015000000-M | 1615 | TEMPORARY MULCHING | 7 HA | | |
| 0120 | 6018000000-M | 1620 | SEED FOR TEMPORARY SEEDING | 275 KG | | |
| 0121 | 6021000000-M | 1620 | FERTILIZER FOR TEMPORARY SEEDING | 2.25 MTN | | |
| 0122 | 6030000000-M | 1630 | SILT EXCAVATION | 5,770 M3 | | |
| 0123 | 6036000000-M | 1631 | MATTING FOR EROSION CONTROL | 13,000 M2 | | |
| 0124 | 6042000000-M | 1632 | 6.4MM HARDWARE CLOTH | 270 M | | |
| 0125 | 6084000000-M | 1660 | SEEDING & MULCHING | 6.5 HA | | |
| 0126 | 6087000000-M | 1660 | MOWING | 4 HA | | |
| 0127 | 6090000000-M | 1661 | SEED FOR REPAIR SEEDING | 100 KG | | |

County : Gaston, Lincoln

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|------------|-----------|--------|
| 0128 | 6093000000-M | 1661 | FERTILIZER FOR REPAIR SEEDING | 0.5 MTN | | |
| 0129 | 6096000000-M | 1662 | SEED FOR SUPPLEMENTAL SEEDING | 200 KG | | |
| 0130 | 6108000000-M | 1665 | FERTILIZER TOPDRESSING | 11 MTN | | |
| 0131 | 6109000000-M | SP | SPECIALIZED SEEDING UNDER GUIDERAIL & GUARDRAIL (HARD FESCUE/BUEGRASS) | 0.15 HA | | |
| 0132 | 6114000000-N | SP | SPECIALIZED HAND MOWING | 6.5 HR | | |
| 0133 | 6117000000-N | 1675 | RESPONSE FOR EROSION CONTROL | 12 EA | | |
| 0134 | 6123000000-M | 1670 | REFORESTATION | 1.4 HA | | |
| 0135 | 7060000000-M | 1705 | SIGNAL CABLE | 295 M | | |
| 0136 | 7120000000-M | 1705 | VEHICLE SIGNAL HEAD (300MM, 3 SECTION) | 11 EA | | |
| 0137 | 7132000000-M | 1705 | VEHICLE SIGNAL HEAD (300MM, 4 SECTION) | 1 EA | | |
| 0138 | 7144000000-M | 1705 | VEHICLE SIGNAL HEAD (300MM, 5 SECTION) | 1 EA | | |
| 0139 | 7216000000-N | SP | MODIFY EXISTING VEHICLE SIGNAL HEAD | 7 EA | | |
| 0140 | 7252000000-M | 1710 | MESSENGER CABLE (6.35MM) | 640 M | | |
| 0141 | 7264000000-M | 1710 | MESSENGER CABLE (9.52MM) | 360 M | | |
| 0142 | 7279000000-M | 1715 | TRACER WIRE | 1,513 M | | |
| 0143 | 7300000000-M | 1715 | TRENCHING (UNPAVED) | 178 M | | |
| 0144 | 7301000000-M | SP | DIRECTIONAL DRILL POLYETHYLENE CONDUIT, *****MM (** CONDUIT) (50MM, 1) | 355 M | | |
| 0145 | 7324000000-N | 1716 | JUNCTION BOX (STANDARD SIZE) | 7 EA | | |
| 0146 | 7336000000-N | 1716 | JUNCTION BOX (OVER-SIZED) | 13 EA | | |

County : Gaston, Lincoln

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|------------|-----------|--------|
| 0147 | 7360000000-N | 1720 | WOOD POLE | 1 EA | | |
| 0148 | 7372000000-N | 1721 | GUY ASSEMBLY | 6 EA | | |
| 0149 | 7420000000-M | 1722 | 50MM RISER WITH WEATHERHEAD | 1 EA | | |
| 0150 | 7432000000-M | 1722 | 50MM RISER WITH HEAT SHRINK TUBING | 6 EA | | |
| 0151 | 7444000000-M | 1725 | INDUCTIVE LOOP SAWCUT | 373 M | | |
| 0152 | 7456000000-M | 1726 | LEAD-IN CABLE | 740 M | | |
| 0153 | 7484000000-N | SP | MICROWAVE VEHICLE DETECTOR | 2 EA | | |
| 0154 | 7516000000-M | 1730 | COMMUNICATIONS CABLE (**FIBER) (12) | 2,327 M | | |
| 0155 | 7552000000-N | 1731 | INTERCONNECT CENTER | 4 EA | | |
| 0156 | 7564000000-N | 1732 | FIBER-OPTIC TRANSCEIVER | 4 EA | | |
| 0157 | 7566000000-N | 1733 | DELINEATOR MARKER | 13 EA | | |
| 0158 | 7576000000-N | 1740 | METAL STRAIN SIGNAL POLE | 8 EA | | |
| 0159 | 7613000000-N | SP | SOIL TEST | 8 EA | | |
| 0160 | 7614000000-M | SP | DRILLED PIER FOUNDATION (**MM DIA) (1067MM) | 37 M | | |
| 0161 | 7636000000-N | 1745 | SIGN FOR SIGNALS | 1 EA | | |
| 0162 | 7684000000-N | 1750 | SIGNAL CABINET FOUNDATION | 2 EA | | |
| 0163 | 7688000000-N | SP | CABINET BASE ADAPTER | 3 EA | | |
| 0164 | 7756000000-N | 1751 | CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED) | 3 EA | | |
| 0165 | 7780000000-N | SP | DETECTOR CARD (TYPE 2070L) | 12 EA | | |

County : Gaston, Lincoln

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|----------|-----------|--------|
| 0166 | 7990000000-M | SP | GENERIC SIGNAL ITEM UNDERGROUND POLYETHYLENE CONDU IT, 50MM (1 CONDUIT) | 1,159 | M | |

1556/Nov16/Q964951.01/D695660170000/E166

Total Amount Of Bid For Entire Project :

C200894 (R-2206AA)
GASTON AND LINCOLN COUNTIES

2/16/99

Contract No: C200894

Counties: Gaston and Lincoln

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General