

PROJECT NO.	SHEET NO.	TOTAL NO.
5CR.10391.3, 5CR.20391.3, 5CR.303919.3,	2	

## SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LENGTH MI	WIDTH FT	INCIDENTAL STONE BASE TONS	SHOULDER RECONSTRUCTION SMI	INCIDENTAL MILLING SY	BASE COURSE, B25.0B TONS	LEVELING COURSE, SF9.5A TONS	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, SF9.5A TONS	PG 64-22 PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	SEED & MULCHING AC
5CR.10391.3	Granville	1	US 158	FROM .6 MI E OF SR 1145 TO SR 1309	1	2.3	25	184	4.6	150	4,089	300	3,133		364	250	3.33
		2	NC 96	FROM OXFORD CL TO SR 1609	2	0.61	32	49	1.22	180			1,062		64		0.88
<b>TOTAL FOR PROJ NO. 5CR.10391.3</b>						<b>2.91</b>		<b>233</b>	<b>5.82</b>	<b>330</b>	<b>4,089</b>	<b>300</b>	<b>4,195</b>		<b>428</b>	<b>250</b>	<b>4.21</b>
5CR.20391.3	Granville	3	SR 1713 (BRUCE GARNER RD)	FROM FRANKLIN CO L TO SR 1712 (MAY'S STORE RD)	3	0.2	22	16	0.4		199	50		236	23	50	0.29
		4	SR 1712 (MAYS STORE ROAD)	FROM SR 1713 (BRUCE GARNER RD) TO SR 1711 (BRUCE GARNER RD)	3	1.15	22	92	2.3		1,142	150		1,410	134	150	1.67
		5	SR 1711 (BRUCE GARNER RD)	FROM SR 1712 (MAYS STORE RD) TO WAKE CO L	3	6	22	480	12		5,959	300		7,618	713	250	8.70
<b>TOTAL FOR PROJ NO. 5CR.20391.3</b>						<b>7.35</b>		<b>588</b>	<b>14.7</b>		<b>7,300</b>	<b>500</b>		<b>9,264</b>	<b>870</b>	<b>450</b>	<b>10.66</b>
5CR.303919.3	Granville	6	NC 96	FROM SR 1606 (ORPHANAGE RD) TO OXFORD CL	2	0.25	32	20	0.5	180			435		26	75	0.36
<b>TOTAL FOR PROJ NO. 5CR.303919.3</b>						<b>0.25</b>		<b>20</b>	<b>0.5</b>	<b>180</b>			<b>435</b>		<b>26</b>	<b>75</b>	<b>0.36</b>
<b>GRAND TOTAL</b>						<b>10.51</b>		<b>841</b>	<b>21.02</b>	<b>510</b>	<b>11,389</b>	<b>800</b>	<b>4,630</b>	<b>9,264</b>	<b>1,324</b>	<b>775</b>	<b>15.23</b>