COMPUTED BY:	DSP	DATE:	03/14/03
CHECKED BY:	KJH	DATE:	Ø3/14/Ø3
0.120.120			

PROJECT REFERENCE NO. SHEET NO.

B-3485 3-A

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

SUMMARY OF EARTHWORK

IN CUBIC YARDS

	FROM STATION	TO STATION	SIDE	TOTAL UNCLASSIFIED EXCAVATION	UNDERCUT	EMBANKMENT +%	BORROW	WASTE
-L -	13+00	14 + 72	LT & RT	2	0	284	282	0
BRIDGE								
-L-	16 + 32	18 + 70	LT & RT	509	0	431	0	78
SUBTOTAL SUMMARY			511	0	715	282	78	
EARTH TO REPLACE BORROW			•	•	•	-78	–78	
PROJECT TOTAL			511		715	204	0	
ESTIMATE 5% FOR TOPSOIL FOR BORROW PITS						10		
GRAND TOTAL			511	0	715	214	0	
SAY			550		750	250		

NOTE:

APPROXIMATE QUANTITIES ONLY. UNCLASSIFIED EXCAVATION, BORROW EXCAVATION, FINE GRADING, CLEARING AND GRUBBING, AND REMOVAL OF EXISTING PAVEMENT WILL BE PAID FOR AT THE CONTRACT LUMP SUM PRICE FOR "GRADING".

RIGHT OF WAY AREA DATA

PARCEL NO.	PROPERTY OWNERS NAME	TOTAL	AREA TAKEN	AREA REMAINING RIGHT	AREA REMAINING LEFT	CONSTR.	PERMANENT DRAINAGE EASEMENT	TEMPORARY DRAINAGE EASEMENT	
1	CHARLES SILER SLAGLE	190.40	-	-	_	0.45 ac.	-	_	
							,		

SUMMARY OF PAVEMENT REMOVAL

IN SQUARE METERS

LOCATION	ASPHALT REMOVAL	ASPHALT BREAK-UP	CONCRETE REMOVAL	CONCRETE BREAK-UP	COMMENTS
L STA 16+32 TO 16+75		81			
-L- STA 16+75 TO 17+50	150				
					······································
					•
· · · · · · · · · · · · · · · · · · ·					
TOTAL	150	81			
SAY	160	100			

oroj\2870\2870-104\USTATION\RDWY\104ew.su nifer.starnes