

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (15+52.00 -L-)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	4 TON		
0006	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	32 LF		
0007	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0008	1220000000-E	545	INCIDENTAL STONE BASE	150 TON		
0009	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	100 TON		
0010	1514000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5A	160 TON		
0011	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	15 TON		
0012	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0013	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0014	2556000000-E	846	SHOULDER BERM GUTTER	35 LF		
0015	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0016	3420000000-E	SP	GENERIC GUARDRAIL ITEM STEEL BM GUARDRAIL WEATHERING STEEL W/ WOOD POSTS	112.5 LF		
0017	3435000000-N	SP	GENERIC GUARDRAIL ITEM GUARDRAIL ANCHOR UNITS, TYPE III , WEATHERING STEEL	4 EA		

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	3435000000-N	SP	GENERIC GUARDRAIL ITEM GUARDRAIL ANCHOR UNITS, TYPE350, WEATHERING STEEL	4 EA		
0019	3559000000-E	866	** STRAND BARBED WIRE FENCE WITH POSTS (6)	2,000 LF		
0020	3563000000-E	SP	TEMP *** WOVEN WIRE FENCE, COMPLETE W/POSTS (47")	800 LF		
0021	3649000000-E	876	PLAIN RIP RAP, CLASS B	62 TON		
0022	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	850 SY		
0023	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	192 SF		
0024	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	134 SF		
0025	4445000000-E	1145	BARRICADES (TYPE III)	96 LF		
0026	6000000000-E	1605	TEMPORARY SILT FENCE	275 LF		
0027	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0028	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	125 TON		
0029	6012000000-E	1610	SEDIMENT CONTROL STONE	50 TON		
0030	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0031	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0032	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0033	6024000000-E	1622	TEMPORARY SLOPE DRAINS	30 LF		
0034	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0035	6030000000-E	1630	SILT EXCAVATION	200 CY		

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	6033000000-E	1631	SYNTHETIC ROVING	225 SY		
0037	6036000000-E	1631	MATTING FOR EROSION CONTROL	425 SY		
0038	6042000000-E	1632	1/4" HARDWARE CLOTH	50 LF		
0039	6084000000-E	1660	SEEDING & MULCHING	1.5 ACR		
0040	6087000000-E	1660	MOWING	1 ACR		
0041	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0042	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0043	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0044	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		
0045	6114000000-N	SP	SPECIALIZED HAND MOWING	1 HR		
0046	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		
0047	6123000000-E	1670	REFORESTATION	0.5 ACR		

STRUCTURE ITEMS

0048	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (15+52.00 -L-)	Lump Sum	L.S.	
0049	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+52.00 -L-)	Lump Sum	L.S.	
0050	8105500000-E	SP	***.*** DIA DRILLED PIERS IN SOIL (3'-6")	35.4 LF		
0051	8105600000-E	SP	***.*** DIA DRILLED PIERS NOT IN SOIL (3'-6")	44 LF		

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	8111000000-E	SP	PERMANENT STEEL CASING FOR ***"*** DIA DRILLED PIER (3'-6")	40.9 LF		
0053	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0054	8116000000-E	SP	CSL TUBES	331.2 LF		
0055	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (15+52.00 -L-)	Lump Sum	L.S.	
0056	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	4,141 SF		
0057	8161000000-E	420	GROOVING BRIDGE FLOORS	3,308 SF		
0058	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	73.7 CY		
0059	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15+52.00 -L-)	Lump Sum	L.S.	
0060	8217000000-E	425	REINFORCING STEEL (BRIDGE)	15,474 LB		
0061	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,364 LB		
0062	8262000000-E	430	45" PRESTRESSED CONCRETE GIR- DERS	620.34 LF		
0063	8364000000-E	450	HP12X53 STEEL PILES	180 LF		
0064	8468000000-E	460	ONE BAR METAL RAIL	300.69 LF		
0065	8517000000-E	460	1'-***"X ***** CONCRETE PARA- PET (1'-0" x 18")	315.69 LF		
0066	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	1,888 TON		
0067	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	2,098 SY		
0068	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0069	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0070	8889000000-E	SP	GENERIC STRUCTURE ITEM GLASS FIBER REINFORCED POLYMER	21,460 LB		

1031/Nov08/Q59071.67/D380199200000/E70

Total Amount Of Bid For Entire Project :

C201308 (B-3485)
MACON COUNTY

2/16/99

Contract No: C201308

County: Macon

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General