

FINAL PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	PAY ITEM QUANTITY BREAKDOWN		TOTAL QUANTITY
		FINAL		
PAVEMENT MARKINGS				
THERMOPLASTIC (100MM, 2.3MM)				
TA	WHITE EDGELINE	199	M	TOTAL 199 M
THERMOPLASTIC (100MM, 3.1MM)				
TI	YELLOW DOUBLE CENTER	374	M	TOTAL 374 M
THERMOPLASTIC (600MM, 3.1MM)				
T4	WHITE STOPBAR	38	M	TOTAL 51 M
T3	WHITE CROSSWALK LINE	13	M	
THERMOPLASTIC PAVEMENT MARKING CHARACTER (3.1MM)				
UI	ALPHANUMERIC CHAR.	2	EA	TOTAL 2 EA
COLD APPLIED PLASTIC (100MM)				
CA	WHITE EDGELINE	201	M	TOTAL 637 M
CI	YELLOW DOUBLE CENTER	436	M	
COLD APPLIED PLASTIC (400MM)				
C3	WHITE LINE, RR CROSSB	13	M	TOTAL 13 M
COLD APPLIED PLASTIC (600MM)				
C4	WHITE STOPBAR	16	M	TOTAL 16 M
COLD APPLIED PLASTIC PAVEMENT MARKING CHARACTER				
DI	ALPHANUMERIC CHAR.	2	EA	TOTAL 2 EA
MARKERS				
SNOWPLOWABLE RAISED PAVEMENT MARKERS				
ME	YELLOW & YELLOW	39	EA	TOTAL 39 EA

APPROVED:	DATE: 9/21/04	FINAL PAVEMENT MARKING SCHEDULE	
	SCALE: NONE		
	DATE: 9/2004		
	DWG. BY: JTD		
	DESIGN BY: JTD		
REVIEWED BY: KWB		REVISIONS	