

County : Madison

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (11+03.000-Y-)	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (12+20.085)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-M	226	SUPPLEMENTARY CLEARING & GRUB- BING	0.4 HA		
0006	0057000000-M	226	UNDERCUT EXCAVATION	200 M3		
0007	0134000000-M	240	DRAINAGE DITCH EXCAVATION	90 M3		
0008	0199000000-M	SP	TEMPORARY SHORING	60 M2		
0009	0318000000-M	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	20.8 MTN		
0010	0366000000-M	310	375MM RC PIPE CULVERTS, CLASS III	24 M		
0011	0706000000-M	310	300MM BIT COAT CS PIPE CUL- VERTS, TYPE B 1.63MM THICK	12 M		
0012	0708000000-M	310	400MM BIT COAT CS PIPE CUL- VERTS, TYPE B 1.63MM THICK	27.6 M		
0013	0805000000-M	310	300MM BIT COAT CS PIPE ELBOWS, TYPE B 1.63MM THICK	2 EA		
0014	0806000000-M	310	400MM BIT COAT CS PIPE ELBOWS, TYPE B 1.63MM THICK	6 EA		
0015	1220000000-M	545	INCIDENTAL STONE BASE	200 MTN		
0016	1489000000-M	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	550 MTN		
0017	1498000000-M	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	350 MTN		

County : Madison

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1525000000-M	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	400 MTN		
0019	1560000000-M	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	70 MTN		
0020	2000000000-N	806	RIGHT OF WAY MARKERS	21 EA		
0021	2022000000-M	815	SUBDRAIN EXCAVATION	55.2 M3		
0022	2033000000-M	815	SUBDRAIN FINE AGGREGATE	41.4 M3		
0023	2044000000-M	815	150MM PERFORATED SUBDRAIN PIPE	100 M		
0024	2055000000-M	815	150MM SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0025	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0026	2077000000-M	815	150MM OUTLET PIPE (SUBDRAINS)	2 M		
0027	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	8 EA		
0028	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	5 EA		
0029	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	1 EA		
0030	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	1 EA		
0031	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	1 EA		
0032	2500000000-M	842	CONCRETE RETAINING WALLS	85 M3		
0033	2549000000-M	846	750MM CONCRETE CURB & GUTTER	115 M		
0034	2556000000-M	846	SHOULDER BERM GUTTER	7 M		
0035	2591000000-M	848	100MM CONCRETE SIDEWALK	185 M2		

County : Madison

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	2598000000-M	848	CONCRETE WHEELCHAIR RAMPS	16.86	M2	
0037	2612000000-M	848	150MM CONCRETE DRIVEWAY	9.173	M2	
0038	2619000000-M	850	100MM CONCRETE PAVED DITCH	75	M2	
0039	3030000000-M	862	STEEL BM GUARDRAIL	7.62	M	
0040	3045000000-M	862	STEEL BM GUARDRAIL, SHOP CURVED	22.86	M	
0041	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
0042	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (III SC)	2	EA	
0043	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1	EA	
0044	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3	EA	
0045	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (NESTED ON BRIDGE RAIL)	1	EA	
0046	3635000000-M	876	PLAIN RIP RAP, CLASS II	350	MTN	
0047	3649000000-M	876	PLAIN RIP RAP, CLASS B	35	MTN	
0048	3656000000-M	876	FILTER FABRIC FOR DRAINAGE	1,340	M2	
0049	4400000000-M	1110	WORK ZONE SIGNS (STATIONARY)	11	M2	
0050	4405000000-M	1110	WORK ZONE SIGNS (PORTABLE)	20	M2	
0051	4410000000-M	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	8	M2	
0052	4430000000-N	1130	DRUMS	60	EA	
0053	4435000000-N	1135	CONES	30	EA	
0054	4445000000-M	1145	BARRICADES (TYPE III)	22	M	

County : Madison

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	4455000000-N	1150	FLAGGER	100 MD		
0056	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	4 EA		
0057	4475000000-N	1165	TRUCK MOUNTED IMPACT ATTENUATOR (45 MPH)	1 EA		
0058	4490000000-M	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	225 M		
0059	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	25 EA		
0060	4685000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 2.3MM)	199 M		
0061	4686000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 3.1MM)	374 M		
0062	4710000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (600MM, 3.1MM)	51 M		
0063	4721000000-M	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (3.1MM)	2 EA		
0064	4770000000-M	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES (100MM)	637 M		
0065	4790000000-M	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES (400MM)	13 M		
0066	4795000000-M	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES (600MM)	16 M		
0067	4800000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING CHARACTER	2 EA		
0068	4810000000-M	1205	PAINT PAVEMENT MARKING LINES (100MM)	1,742 M		
0069	4830000000-M	1205	PAINT PAVEMENT MARKING LINES (400MM)	56 M		
0070	4835000000-M	1205	PAINT PAVEMENT MARKING LINES (600MM)	96 M		
0071	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	8 EA		

County : Madison

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	4850000000-M	1205	REMOVAL OF PAVEMENT MARKING LINES (100MM)	200 M		
0073	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	39 EA		
0074	5300000000-M	1505	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)	8.7 MTN		
0075	5306000000-M	SP	BEDDING MATERIAL, UTILITIES CLASS ***** (IV)	8.7 MTN		
0076	5318000000-M	1505	PAVEMENT REPAIR FOR UTILITY WORK	2.2 MTN		
0077	5360000000-M	1510	150MM DI WATER PIPE, PC 2.41MPA	37 M		
0078	5396000000-M	1510	***MM DI RESTRAINED JOINT WATER PIPE, CLASS ***** WP (150MM, 2.41)	3 M		
0079	5396000000-M	1510	***MM DI RESTRAINED JOINT WATER PIPE, CLASS ***** WP (200MM, 2.41)	250.47 M		
0080	5402000000-M	1510	DI RESTRAINED JOINT WATER PIPE FITTINGS, 1.72MPA MIN WP	170.1 KG		
0081	5480000000-M	1510	DUCTILE IRON WATER PIPE FITTINGS, 1.72MPA MIN WP	226.8 KG		
0082	5540000000-M	1510	150MM GATE VALVE & VALVE BOX, 1.38MPA WP	2 EA		
0083	5546000000-M	1510	200MM GATE VALVE & VALVE BOX, ****MPA WP (1.38 MPA)	1 EA		
0084	5576000000-M	1510	*** X ***MM TAPPING SLEEVE, VALVE & VALVE BOX, ****MPA WP (150MM X 150MM, 1.38MPA)	2 EA		
0085	5672000000-N	1510	RELOCATE EXISTING FIRE HYDRANT	1 EA		
0086	6000000000-M	1605	TEMPORARY SILT FENCE	235 M		
0087	6006000000-M	1610	STONE FOR EROSION CONTROL, CLASS A	110 MTN		

County : Madison

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0088	6009000000-M	1610	STONE FOR EROSION CONTROL, CLASS B	185 MTN		
0089	6012000000-M	1610	SEDIMENT CONTROL STONE	610 MTN		
0090	6015000000-M	1615	TEMPORARY MULCHING	0.5 HA		
0091	6018000000-M	1620	SEED FOR TEMPORARY SEEDING	25 KG		
0092	6021000000-M	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 MTN		
0093	6030000000-M	1630	SILT EXCAVATION	215 M3		
0094	6036000000-M	1631	MATting FOR EROSION CONTROL	800 M2		
0095	6042000000-M	1632	6.4MM HARDWARE CLOTH	50 M		
0096	6070000000-N	SP	SPECIAL STILLING BASINS	24 EA		
0097	6084000000-M	1660	SEEDING & MULCHING	0.5 HA		
0098	6087000000-M	1660	MOWING	0.5 HA		
0099	6090000000-M	1661	SEED FOR REPAIR SEEDING	25 KG		
0100	6093000000-M	1661	FERTILIZER FOR REPAIR SEEDING	0.25 MTN		
0101	6096000000-M	1662	SEED FOR SUPPLEMENTAL SEEDING	25 KG		
0102	6108000000-M	1665	FERTILIZER TOPDRESSING	0.75 MTN		
0103	6114000000-N	SP	SPECIALIZED HAND MOWING	1 HR		
0104	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		
0105	7060000000-M	1705	SIGNAL CABLE	140 M		
0106	7120000000-M	1705	VEHICLE SIGNAL HEAD (300MM, 3 SECTION)	6 EA		
0107	7288000000-M	1715	TRENCHING (PAVED)	11 M		

County : Madison

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0108	7300000000-M	1715	TRENCHING (UNPAVED)	3 M		
0109	7302000000-M	SP	DIRECTIONAL DRILL POLYETHYLENE CONDUIT, 31.75MM (** CONDUIT) (1)	13 M		
0110	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	2 EA		
0111	7444000000-M	1725	INDUCTIVE LOOP SAWCUT	60 M		
0112	7456000000-M	1726	LEAD-IN CABLE	30 M		
0113	7588000000-N	1741	SIGNAL SUPPORT MAST ARM WITH METAL POLE	1 EA		
0114	7590000000-N	SP	DOUBLE MAST ARM WITH METAL POLE	1 EA		
0115	7613000000-N	SP	SOIL TEST	2 EA		
0116	7614000000-M	SP	DRILLED PIER FOUNDATION (***MM DIA) (1067MM)	10 M		
0117	7631000000-N	1744	MAST ARM WITH METAL POLE DESIGN	2 EA		
0118	7768000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, POLE MOUNTED)	1 EA		
0119	7780000000-N	SP	DETECTOR CARD (TYPE 2070L)	1 EA		
0157	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	

STRUCTURE ITEMS

0120	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (11+03.000 -Y1-)	Lump Sum	L.S.	
0121	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (12+21.750 -L-)	Lump Sum	L.S.	

County : Madison

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0122	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (12+21.750 -L-)	Lump Sum	L.S.	
0123	8105540000-M	SP	1066MM DIA DRILLED PIERS IN SOIL	2.2 M		
0124	8105560000-M	SP	1220MM DIA DRILLED PIERS IN SOIL	53.6 M		
0125	8105640000-M	SP	1066MM DIA DRILLED PIERS NOT IN SOIL	15 M		
0126	8105660000-M	SP	1220MM DIA DRILLED PIERS NOT IN SOIL	59 M		
0127	8111400000-M	SP	PERMANENT STEEL CASING FOR 1066MM DRILLED PIER	10 M		
0128	8111600000-M	SP	PERMANENT STEEL CASING FOR 1220MM DRILLED PIER	54.6 M		
0129	8115000000-N	SP	CROSSHOLE SONIC LOGGING	6 EA		
0130	8116000000-M	SP	CSL TUBES	590.1 M		
0131	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (11+03.000 -Y1-)	Lump Sum	L.S.	
0132	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (12+21.750 -L-)	Lump Sum	L.S.	
0133	8147000000-M	420	REINFORCED CONCRETE DECK SLAB	726.8 M2		
0134	8161000000-M	420	GROOVING BRIDGE FLOORS	1,990.5 M2		
0135	8175000000-M	420	CLASS AA CONCRETE (BRIDGE)	158.3 M3		
0136	8182000000-M	420	CLASS A CONCRETE (BRIDGE)	424.8 M3		
0137	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (11+03.000 -Y1-)	Lump Sum	L.S.	
0138	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (12+21.750 -L-)	Lump Sum	L.S.	

County : Madison

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0139	8217000000-M	425	REINFORCING STEEL (BRIDGE)	58,206 KG		
0140	8224000000-M	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	3,758 KG		
0141	8238000000-M	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	8,751 KG		
0142	8262000000-M	430	1143MM PRESTRESSED CONCRETE GIRDERS	334.852 M		
0143	8364000000-M	450	HP310X79 STEEL PILES	178.5 M		
0144	8391000000-N	450	STEEL PILE POINTS	9 EA		
0145	8433000000-M	452	****MM STEEL SHEET PILES (460MM)	27 M2		
0146	8608000000-M	876	PLAIN RIP RAP CLASS II (600MM THICK)	311 MTN		
0147	8622000000-M	876	FILTER FABRIC FOR DRAINAGE	317 M2		
0148	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0149	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0150	8727000000-N	SP	ELECTRICAL CONDUIT SYSTEM, STA ***** (12+21.750 -L-)	Lump Sum	L.S.	
0151	8860000000-N	SP	GENERIC STRUCTURE ITEM FOOTING, RAIL, AND SIDEWALK BETWEEN STRUCTURES	Lump Sum	L.S.	
0152	8860000000-N	SP	GENERIC STRUCTURE ITEM INSTALL 150MM DI RJ WATER MAIN AT STATION 11+03.000 -Y1-	Lump Sum	L.S.	
0153	8860000000-N	SP	GENERIC STRUCTURE ITEM INSTALL 200MM DI RJ WATER MAIN AT STATION 12+21.750 -L-	Lump Sum	L.S.	
0154	8867000000-M	SP	GENERIC STRUCTURE ITEM 914MM X 838MM PRESTRESSED CONCRETE BOX BEAMS	2,545.608 M		
0155	8867000000-M	SP	GENERIC STRUCTURE ITEM CLASSIC CONCRETE BRIDGE RAIL	504.517 M		

County : Madison

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0156	8893000000-M	SP	GENERIC STRUCTURE ITEM CONCRETE WEARING SURFACE	1,725.9 M2		

1112/Dec03/Q92542.91/D806055900000/E157

Total Amount Of Bid For Entire Project :

C200955
MADISON COUNTY

2/16/99

Contract No: C200955

County: Madison

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General