

PROJECT NO.	SHEET NO.	TOTAL NO.
36966 - ALTERNATE TWO	5	

SUMMARY OF QUANTITIES - ALTERNATE ONE										
PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LENGTH MI	WIDTH FT	2" TO 4" MILLING SY	SURFACE COURSE, S9.5C TON	ASPHALT BINDER FOR PLANT MIX, PG 70-22 TON
36966	MOORE	1	US 1	FROM SCL ABERDEEN TO US 15-501/NC 211	1	0.20	64	8,811	1,480	89
		2	US 1 (INCL. RAMP)	FROM US 15-501 TO CONSTRUCTION JOINT AT NC 5	2	0.19	36	9,627	1,618	97
		3	US 1	FROM CONSTRUCTION JOINT NORTH OF RAILROAD TO SR 2053	1	2.16	72	91,727	15,410	925
		4	US 1 (INCL. RAMPS)	FROM SR 2053 TO NORTH END OF BRIDGE NO. 32	3	0.30	28	8,972	1,530	92
TOTAL FOR PROJ NO. 36966						2.85		119,137	20,038	1,203
GRAND TOTAL						2.85		119,137	20,038	1,203

SUMMARY OF QUANTITIES - ALTERNATE TWO													
PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LENGTH MI	WIDTH FT	2" TO 4" MILLING SY	EMULSIFIED ASPHALT REJUVENATING AGENT GAL	HOT-IN-PLACE RECYCLING, TYPE S9.5C SY	HOT MIX ASPHALT ADMIXTURE, TYPE S9.5C TON	SURFACE COURSE, S9.5C TON	ASPHALT BINDER FOR PLANT MIX, PG 70-22 TON
36966	MOORE	1	US 1	FROM SCL ABERDEEN TO US 15-501/NC 211	1	0.20	64	489	332	8,322	333	91	25
		2	US 1 (INCL. RAMP)	FROM US 15-501 TO CONSTRUCTION JOINT AT NC 5	2	0.19	36	956	867	8,671	347	172	31
		3	US 1	FROM CONSTRUCTION JOINT NORTH OF RAILROAD TO SR 2053	1	2.16	72	1404	9,033	90,323	3,613	227	231
		4	US 1 (INCL. RAMPS)	FROM SR 2053 TO NORTH END OF BRIDGE NO. 32	3	0.30	28	1126	785	7,846	314	173	29
TOTAL FOR PROJ NO. 36966						2.85		3,975	11,017	115,162	4,607	663	316
GRAND TOTAL						2.85		3,975	11,017	115,162	4,607	663	316