

PROJECT NO.	SHEET NO.	TOTAL NO.
39695	4	4

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	468500000-E	468600000-E	481000000-E		490500000-N
					4" X 90 M WHITE THERMO LF	4" X 120 M YELLOW THERMO LF	4" WHITE PAINT LF	4" YELLOW PAINT LF	SNOW PLOWABLE MARKERS Y&Y EA
39695	Moore	1	NC 24-27	FROM CJ WEST OF NC 22 TO SR 1477	4,020	3,220	4,020	3,220	30
		2	NC 24-27	FROM SR 1477 TO CJ EAST OF NC 705	48,800	39,100	48,800	39,100	305
TOTAL FOR PROJ NO. 39695					52,820	42,320	52,820	42,320	335
					95,140				
GRAND TOTAL					52,820	42,320	52,820	42,320	335
					95,140				