

STATE OF NORTH CAROLINA
 DIVISION OF HIGHWAYS

SUMMARY OF EARTHWORK

IN CUBIC METERS

COMPUTED BY: K. DUNN *KVD* DATE: 6/29/04
 CHECKED BY: J. JATKO *JJ* DATE: 6/29/04

QUANTITIES ARE APPROXIMATE ONLY. THE RESIDENT ENGINEER WILL
 RE-CROSS-SECTION THE WORK ACCURATELY WHEN THE PROJECT IS STAKED
 OUT. THESE CROSS-SECTION NOTES WILL BE USED IN COMPUTING THE
 FINAL QUANTITIES FOR WHICH THE CONTRACTOR WILL BE PAID.



PROJECT REFERENCE NO. R-2514A SHEET NO. 3-H

LOCATION	UNCL. EXCAVATION	UNDERCUT	EMBT + %	BORROW	WASTE
-LMED- RT 104+00 TO 114+00	1,114	2,878	21,518	21,295	3,769
SUBTOTAL SUMMARY NO. 1	1,114	2,878	21,518	21,295	3,769
-LMED- RT 114+00 TO 124+00	385	1	26,913	26,836	309
SUBTOTAL SUMMARY NO. 2	385	1	26,913	26,836	309
-LMED- RT 124+00 TO 134+00	1,440		34,266	33,978	1,152
SUBTOTAL SUMMARY NO. 3	1,440		34,266	33,978	1,152
-LMED- RT 134+00 TO 144+00	1,348		27,434	27,164	1,078
SUBTOTAL SUMMARY NO. 4	1,348		27,434	27,164	1,078
-LMED- RT 144+00 TO 154+00	689		25,746	25,608	551
SUBTOTAL SUMMARY NO. 5	689		25,746	25,608	551
-LMED- RT 154+00 TO 164+00	4,413		30,158	29,275	3,530
SUBTOTAL SUMMARY NO. 6	4,413		30,158	29,275	3,530
-LMED- RT 164+00 TO 174+00	5,000	3,476	12,149	11,149	7,476
-Y2- 0+00 TO 1+10	422		209	125	338
SUBTOTAL SUMMARY NO. 7	5,422	3,476	12,358	11,274	7,814
-LMED- RT 174+00 TO 182+66.40	5,415	2,185	12,823	11,740	6,517
SUBTOTAL SUMMARY NO. 8	5,415	2,185	12,823	11,740	6,517
-LMED- RT 183+08.40 TO 193+00	3,090	1,630	16,901	16,283	4,102
-Y4- 0+00 TO 1+05	354		380	309	283
SUBTOTAL SUMMARY NO. 9	3,444	1,630	17,281	16,592	4,385
-LMED- RT 193+00 TO 195+80	264	560	4,128	4,075	771
SUBTOTAL SUMMARY NO. 10	264	560	4,128	4,075	771
-LMED- RT 99+00 TO 100+80	18		923	919	14
-Y8- 0+00 TO 1+00	244		128	79	195
SUBTOTAL SUMMARY NO. 11	262		1,051	998	209
-LMED- RT 101+65 TO 104+00	856	176	2,463	2,292	861
-DETI- 0+00 TO 3+00.385			758	758	
SUBTOTAL SUMMARY NO. 12	856	176	3,221	3,050	816
-NBITE- 193+70 TO 197+70.709			776	776	
SUBTOTAL SUMMARY NO. 13			776	776	
-LMED- RT 100+80 TO 101+65	344		213	144	275
SUBTOTAL SUMMARY NO. 14	344		213	144	275
-LMED- LT 107+20 TO 117+00	764		414	261	611
SUBTOTAL SUMMARY NO. 15	764		414	261	611
-LMED- LT 117+00 TO 127+00	401		270	190	321
SUBTOTAL SUMMARY NO. 16	401		270	190	321
-LMED- LT 127+00 TO 137+00	421		285	201	337
SUBTOTAL SUMMARY NO. 17	421		285	201	337
-LMED- LT 137+00 TO 147+00	492		228	130	394
SUBTOTAL SUMMARY NO. 18	492		228	130	394
-LMED- LT 147+00 TO 157+00	347		559	490	278
SUBTOTAL SUMMARY NO. 19	347		559	490	278
-LMED- LT 157+00 TO 167+00	366		776	703	293
SUBTOTAL SUMMARY NO. 20	366		776	703	293
SUBTOTAL FOR SHEET 1	28,187	10,906	220,418	214,780	33,455