

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201075

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+47.5)
0043000000-N	226	Lump Sum		GRADING
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING
0057000000-E	226	200	CY	UNDERCUT EXCAVATION
0255000000-E	SP	40	TON	GENERIC GRADING ITEM DISPOSAL OF CONTAMINATED SOIL
0318000000-E	300	65	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS
0360000000-E	310	44	LF	12" RC PIPE CULVERTS, CLASS III
0366000000-E	310	284	LF	15" RC PIPE CULVERTS, CLASS III
0372000000-E	310	160	LF	18" RC PIPE CULVERTS, CLASS III
0396000000-E	310	72	LF	42" RC PIPE CULVERTS, CLASS III
0714000000-E	310	44	LF	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
0995000000-E	340	60	LF	PIPE REMOVAL
1220000000-E	545	200	TON	INCIDENTAL STONE BASE
1489000000-E	610	933	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
1498000000-E	610	858	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B
1519000000-E	610	955	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
1560000000-E	620	138	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
1693000000-E	654	20	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR
2275000000-E	SP	14	CY	FLOWABLE FILL
2286000000-N	840	17	EA	MASONRY DRAINAGE STRUCTURES
2367000000-N	840	2	EA	FRAME WITH TWO GRATES, STD 840.29

ItemNumber	Sec #	Quantity	Unit	Description
2374000000-N	840	5	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)
2374000000-N	840	4	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)
2374000000-N	840	2	EA	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)
2396000000-N	840	4	EA	FRAME WITH COVER, STD 840.54
2473000000-N	SP	2	EA	GENERIC DRAINAGE ITEM FLAP GATE
2535000000-E	846	540	LF	***X*** CONCRETE CURB (9" X 12")
2549000000-E	846	1,630	LF	2'-6" CONCRETE CURB & GUTTER
2591000000-E	848	645	SY	4" CONCRETE SIDEWALK
2598000000-E	848	41	SY	CONCRETE WHEELCHAIR RAMPS
2612000000-E	848	286	SY	6" CONCRETE DRIVEWAY
2830000000-N	858	10	EA	ADJUSTMENT OF MANHOLES
2845000000-N	858	5	EA	ADJUSTMENT OF METER BOXES OR VALVE BOXES
3649000000-E	876	3	TON	PLAIN RIP RAP, CLASS B
3656000000-E	876	160	SY	FILTER FABRIC FOR DRAINAGE
3982000000-N	SP	Lump Sum		GENERIC WALL ITEM PILE/PANEL RETAINING WALL
4400000000-E	1110	73	SF	WORK ZONE SIGNS (STATIONARY)
4405000000-E	1110	52	SF	WORK ZONE SIGNS (PORTABLE)
4410000000-E	1110	57	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
4415000000-N	1115	1	EA	FLASHING ARROW PANELS, TYPE C
4420000000-N	1120	5	EA	CHANGEABLE MESSAGE SIGNS
4425000000-N	1125	2	EA	WARNING FLAG SETS
4430000000-N	1130	260	EA	DRUMS
4435000000-N	1135	260	EA	CONES
4445000000-E	1145	80	LF	BARRICADES (TYPE III)

ItemNumber	Sec #	Quantity	Unit	Description
4455000000-N	1150	200	MD	FLAGGER
4650000000-N	1251	41	EA	TEMPORARY RAISED PAVEMENT MARKERS
4686000000-E	1205	2,984	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
4697000000-E	1205	145	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)
4710000000-E	1205	44	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)
4725000000-E	1205	16	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)
4810000000-E	1205	5,966	LF	PAINT PAVEMENT MARKING LINES (4")
4820000000-E	1205	290	LF	PAINT PAVEMENT MARKING LINES (8")
4835000000-E	1205	88	LF	PAINT PAVEMENT MARKING LINES (24")
4845000000-N	1205	32	EA	PAINT PAVEMENT MARKING SYMBOL
4900000000-N	1252	41	EA	PERMANENT RAISED PAVEMENT MARKERS
5300000000-E	1505	68.1	TON	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)
5306000000-E	SP	68.1	TON	BEDDING MATERIAL, UTILITIES CLASS ***** (IV)
5540000000-E	1510	1	EA	6" GATE VALVE & VALVE BOX, 200# WP
5564000000-E	SP	1	EA	*** BUTTERFLY VALVE & VALVE BOX (16")
5666000000-E	1510	1	EA	FIRE HYDRANT, *****# WP (150 # WP)
5775000000-E	1525	1	EA	4' DIA PRECAST CONC SEWER MANHOLE 0-6' DEPTH
5780000000-E	1525	4	LF	PRECAST CONC MANHOLE WALL, 4" DIA, OVER 6' HT (4' DIA, OVER 6' HT)
5798000000-E	1530	399	LF	FILL OR REMOVE ABANDONED *** PIPE, ***** (8", TC SEWER)
5810000000-E	1530	478	LF	FILL OR REMOVE ABANDONED 16" PIPE, ***** (DI WATER)

ItemNumber	Sec #	Quantity	Unit	Description
5882000000-N	SP	1	EA	GENERIC UTILITY ITEM 4' DIA PRECAST CONC SEWER MANHOLE, 0-6' DEPTH WITH WATERTIGHT RING & COVER
5882000000-N	SP	1	EA	GENERIC UTILITY ITEM INSTALL 4" WATER METER & VAULT
5882000000-N	SP	1	EA	GENERIC UTILITY ITEM REMOVE & STOCKPILE EXT FIRE HYDRANT
5888000000-E	SP	493.3	LF	GENERIC UTILITY ITEM 16" DI WATER PIPE, PC 350
5888000000-E	SP	10	LF	GENERIC UTILITY ITEM 6" DI WATER PIPE, PC 350
5888000000-E	SP	279.4	LF	GENERIC UTILITY ITEM 8" DI RESTRAINED JOINT SEWER PIPE, CLASS 50
5888000000-E	SP	154.25	LF	GENERIC UTILITY ITEM 8" DI SEWER PIPE, CLASS 50
5888000000-E	SP	357.05	LF	GENERIC UTILITY ITEM 8" DI WATER PIPE, PC 350
5894000000-E	SP	4	CY	GENERIC UTILITY ITEM CONCRETE FOR PIERS, CLASS A
5906000000-E	SP	2,405	LB	GENERIC UTILITY ITEM DUCTILE IRON WATER PIPE FITTINGS, 250# MIN WP
5912000000-N	SP	Lump Sum		GENERIC UTILITY ITEM INSTALL 6" GAS MAIN
6000000000-E	1605	1,550	LF	TEMPORARY SILT FENCE
6006000000-E	1610	50	TON	STONE FOR EROSION CONTROL, CLASS A
6009000000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS B
6012000000-E	1610	65	TON	SEDIMENT CONTROL STONE
6015000000-E	1615	1.5	ACR	TEMPORARY MULCHING
6018000000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING
6021000000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING
6024000000-E	1622	35	LF	TEMPORARY SLOPE DRAINS
6027000000-N	1622	1	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
6030000000-E	1630	85	CY	SILT EXCAVATION

ItemNumber	Sec #	Quantity	Unit	Description
6036000000-E	1631	785	SY	MATTING FOR EROSION CONTROL
6042000000-E	1632	220	LF	1/4" HARDWARE CLOTH
6084000000-E	1660	1.5	ACR	SEEDING & MULCHING
6087000000-E	1660	1	ACR	MOWING
6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
6096000000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
6108000000-E	1665	1	TON	FERTILIZER TOPDRESSING
6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
7060000000-E	1705	475	LF	SIGNAL CABLE
7120000000-E	1705	2	EA	VEHICLE SIGNAL HEAD (12", 3 SECTION)
7144000000-E	1705	4	EA	VEHICLE SIGNAL HEAD (12", 5 SECTION)
7264000000-E	1710	295	LF	MESSENGER CABLE (3/8")
7288000000-E	1715	25	LF	TRENCHING (PAVED)
7300000000-E	1715	130	LF	TRENCHING (UNPAVED)
7324000000-N	1716	6	EA	JUNCTION BOX (STANDARD SIZE)
7360000000-N	1720	2	EA	WOOD POLE
7372000000-N	1721	4	EA	GUY ASSEMBLY
7408000000-E	1722	1	EA	1" RISER WITH WEATHERHEAD
7420000000-E	1722	2	EA	2" RISER WITH WEATHERHEAD
7444000000-E	1725	1,755	LF	INDUCTIVE LOOP SAWCUT
7456000000-E	1726	1,180	LF	LEAD-IN CABLE
7636000000-N	1745	5	EA	SIGN FOR SIGNALS
7852000000-N	SP	1	EA	DETECTOR CARD (NEMA TS-2)