








NOTE: TRANSITION EXISTING PAVEMENT TO T.S #1 STA. 9+74.50 TO STA. 9+99.50



NOTE: TRANSITION T.S #4 TO EXISTING PAVEMENT STA. 19+86.35 TO STA. 20+11.35



**NOTE: SIDEWALK ENDS AT STA. 14+57.00 RT.



CODE	PAVEMENT SCHEDULE
(C1)	PROP. APPROX. 3" ASPHALT CONC. SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD. IN EACH OF TWO LAYERS.
(C2)	PROP. VAR. DEPTH ASPHALT CONC. SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 112 LBS. PER SQ. YD. PER 1" DEPTH TO BE PLACED IN LAYERS NOT LESS THAN 1" OR GREATER THAN 1.5" IN DEPTH.
(D1)	PROP. APPROX. 4" ASPHALT CONC. INTERMEDIATE COURSE, TYPE 119.0B, AT AN AVERAGE RATE OF 456 LBS. PER SQ. YD.
(D2)	PROP. VAR. DEPTH ASPHALT CONC. INTERMEDIATE COURSE, TYPE 119.0B, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1" DEPTH TO BE PLACED IN LAYERS NOT LESS THAN 2 1/4" IN DEPTH OR GREATER THAN 4" IN DEPTH.
(E1)	PROP. APPROX. 4" ASPHALT CONC. BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 456 LBS. PER SQ. YD.
(E2)	PROP. VAR. DEPTH ASPHALT CONC. BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1" DEPTH TO BE PLACED IN LAYERS NOT LESS THAN 3" IN DEPTH OR GREATER THAN 5 1/2" IN DEPTH.
(R)	2'-6" CONCRETE CURB AND GUTTER.
(S)	CONCRETE SIDEWALK
(T)	EARTH MATERIAL.
(U)	EXISTING ASPHALT PAVEMENT.
(W)	VARIABLE DEPTH ASPHALT PAVEMENT (SEE WEDGING DETAIL).

NOTE: ALL SLOPES 1:1 UNLESS OTHERWISE SPECIFIED