

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

STATE PROJECT REFERENCE NO.	SHEET NO.
B-3685	TCP-01

**PLAN FOR PROPOSED
TRAFFIC CONTROL, MARKING & DELINEATION**

PITT COUNTY

B-3685

ROADWAY STANDARD DRAWINGS

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS"-ROADWAY DESIGN UNIT-N.C. DEPARTMENT OF TRANSPORTATION-RALEIGH, N.C., DATED JANUARY 2002 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
1101.02	TEMPORARY LANE CLOSURES
1101.03	TEMPORARY ROAD CLOSURES
1101.05	WORK ZONE VEHICLE ACCESSES
1101.11	TRAFFIC CONTROL DESIGN TABLES
1110.01	STATIONARY WORK ZONE SIGNS
1110.02	PORTABLE WORK ZONE SIGNS
1130.01	DRUMS
1135.01	CONES
1145.01	BARRICADES
1150.01	FLAGGERS
1205.01	PAVEMENT MARKINGS - LINE TYPES & OFFSETS
1205.02	PAVEMENT MARKINGS - 2 LANE & MULTILANE ROADWAYS
1205.04	PAVEMENT MARKINGS - INTERSECTIONS
1205.12	PAVEMENT MARKINGS - BRIDGES
1250.01	PAVEMENT MARKER SPACING
1262.01	GUARDRAIL END DELINEATION

INDEX OF SHEETS

SHEET NO.	TITLE
TCP-01	LIST OF APPLICABLE ROADWAY STANDARD DRAWINGS, LEGEND, INDEX OF SHEETS AND TEMPORARY PAVEMENT MARKINGS
TCP-02	PROJECT NOTES AND PHASING
TCP-03	DETAIL A
TCP-03A	DETAIL B
TCP-04	DETOUR ROUTE
TCP-05	SIGN DESIGN
TCP-06	DRUM DETAIL
PM-01	FINAL PAVEMENT MARKING SCHEDULE AND PAVEMENT MARKINGS
THRU	
PM-02	

LEGEND

- GENERAL**
- DIRECTION OF TRAFFIC FLOW
 - NORTH ARROW
 - PROPOSED PVMT. EXIST. PVMT.
 - WORK AREA
 - REMOVAL OF EXISTING PAVEMENT
- TRAFFIC CONTROL DEVICES**
- TYPE I BARRICADE
 - TYPE II BARRICADE
 - TYPE III BARRICADE
 - CONE
 - DRUM
 - FLASHING ARROW PANEL (TYPE C)
 - TYPE 'B' WARNING LIGHT
 - STATIONARY SIGN
 - PORTABLE SIGN
 - STATIONARY OR PORTABLE SIGN
 - WARNING FLAGS
 - CRASH CUSHION
 - CHANGEABLE MESSAGE SIGN
 - TRUCK MOUNTED IMPACT ATTENUATOR (TMIA)
 - POLICE
 - FLAGGER

- PAVEMENT MARKINGS**
- CRYSTAL/CRYSTAL PAVEMENT MARKER
 - YELLOW/YELLOW PAVEMENT MARKER
 - CRYSTAL/RED PAVEMENT MARKER
 - PAVEMENT MARKING SYMBOLS

Pavement Marking Schedule TIP Project # B-3685				
SYMBOL	DESCRIPTION	PAY ITEM	QUANTITY BREAKDOWN	TOTAL QUANTITY
TEMPORARY PAVEMENT MARKINGS PAINT (4")				
PD	2 FT. WHITE MINISKIP (2X)		197 LF	
PE	WHITE SOLID LANE LINE (2X)		1086 LF	
PF	10 FT. YELLOW SKIP (2X)		667 LF	
PH	YELLOW SINGLE CENTER (2X)		2668 LF	
PI	YELLOW DOUBLE CENTER (2X)		1348 LF	
			TOTAL	5966 LF
PAINT (8")				
PX	WHITE CROSSWALK LINE (2X)		290 LF	
			TOTAL	290 LF
PAINT (24")				
P4	WHITE STOPBAR (2X)		88 LF	
			TOTAL	88 LF
PAINT MARKING SYMBOLS				
QA	LEFT TURN ARROW (2X)		18 EA	
QB	RIGHT TURN ARROW (2X)		2 EA	
QC	STRAIGHT ARROW (2X)		6 EA	
QE	COMBO. STRAIGHT/RIGHT (2X)		6 EA	
			TOTAL	32 EA
MARKERS TEMPORARY RAISED PAVEMENT MARKERS				
MH	YELLOW & YELLOW		41 EA	
			TOTAL	41 EA

APPROVED: DATE: 7/20/2004	PLAN PREPARED BY: N.C.D.O.T. TRAFFIC CONTROL, MARKING & DELINEATION SECTION
SEAL 	STUART BOURNE, P.E. TRAFFIC CONTROL ENGINEER J. STEVE KITE, P.E. TRAFFIC CONTROL PROJECT ENGINEER CHARLES MULLEN TRAFFIC CONTROL PROJECT DESIGN ENGINEER STEPHEN SYKES TRAFFIC CONTROL DESIGN ENGINEER / TECHNICIAN

TIP PROJECT: